

This discussion paper is/has been under review for the journal Atmospheric Chemistry and Physics (ACP). Please refer to the corresponding final paper in ACP if available.

Glycine in aerosol water droplets: a critical assessment of Köhler theory by predicting surface tension from molecular dynamics simulations

X. Li^{1,3}, T. Hede², Y. Tu⁴, C. Leck², and H. Ågren¹

¹Department of Theoretical Chemistry, School of Biotechnology, Royal Institute of Technology, 10691 Stockholm, Sweden

²Department of Meteorology, Stockholm University, 10691 Stockholm, Sweden

³Laboratory for Advanced Materials and Institute of Fine Chemicals, East China University of Science and Technology, Shanghai 200237, China

⁴School of Science and Technology, Örebro University, 70182 Örebro, Sweden

Received: 24 September 2010 – Accepted: 27 September 2010 – Published: 7 October 2010

Correspondence to: H. Ågren (agren@theochem.kth.se)

Published by Copernicus Publications on behalf of the European Geosciences Union.

23169

Abstract

Aerosol particles in the atmosphere are important participants in the formation of cloud droplets and have significant impact on cloud albedo and global climate. According to the Köhler theory which describes the nucleation and the equilibrium growth of cloud droplets, the surface tension of an aerosol droplet is one of the most important factors that determine the critical supersaturation of droplet activation. In this paper, with specific interest to remote marine aerosol, we predict the surface tension of aerosol droplets by performing molecular dynamics simulations on two model systems; the pure water droplets and glycine in water droplets. The curvature dependence of the surface tension is interpolated by a quadratic polynomial over the nano-sized droplets and the limiting case of a planar interface, so that the so-called Aitken mode particles which are critical for droplet formation could be covered and the Köhler equation could be improved by incorporating surface tension corrections.

1 Introduction

Clouds, particularly marine stratocumulus in mid to high latitudes, have been shown to exert a large net negative cooling effect on the Earth (Ramanathan et al., 1989). The radiative or reflective (albedo) properties of clouds are strongly dependent on the number concentration of airborne water-soluble particles, known as cloud condensation nuclei (CCN) (Twomey, 1974). However, this so-called indirect effect of aerosol particles on clouds still constitutes a large uncertainty in the models (Solomon et al., 2007) projecting future climate.

Given that the number of CCN over remote marine areas generally show remarkable stability, the existence of a source that continually restores the CCN population is implied. Blanchard (1971) and Blanchard and Syzdek (1988) have long advocated that a significant proportion of the remote oceanic aerosol is derived from bubble bursting. The bubbles result from entrainment of air induced by wind stress at the air-water inter-

23170

face, which produces primary aerosol particles in CCN sizes. In this process, bubbles scavenge sea-salt, debris and high molecular weight soluble organic surface-active compounds as they rise through the water prior to their injection into the atmosphere.

The discovery of proteinaceous material in Antarctic cloud water sample (Saxena et al., 1983) led us to the assumption that proteins and bacterial enzymes are present in the bursting bubbles. Support for this assumption comes from the presence of free and combined amino acids in marine aerosol and precipitation, which are greatly enriched relative to sea water concentrations because, in the atmosphere, proteins are subject to degradation to amino acids by bacterial enzymes. Typical levels of dissolved amino acids found in marine rain (Mopper and Zika, 1987) showed enrichment by two orders of magnitude over typical seawater values. The amino acids were found predominantly in their L-optical isomers and were therefore probably of biological origin.

The uncertainty in explaining the maintenance of the number of CCN over remote marine areas apparently is a critical element in improving our ability to assess the potential role of marine biogenic CCN in climate forcing. Relevant studies include chemical composition, concentration, shape and size of the cloud activating nuclei but also particular properties like surface tension, density, and hydrophilicity of the nuclei.

A well-established model that guides the so-called critical supersaturation, under which the droplet is activated, is given by the Köhler theory (Köhler, 1936). This theory accounts for surface tension and droplet curvature and also the change in water activity and vapor pressure in the presence of solute substances.

The Köhler theory has been widely used to describe the nucleation and the equilibrium growth of cloud droplets since it was first introduced in 1936. Two balancing terms, the Kelvin term and the Raoult term, compose the theory and determine the growth behavior of the cloud droplets. The surface tension of the droplet appears in the Kelvin term and has an important impact on the critical supersaturation. It has been suggested that a decrease in cloud droplet size, which may increase the droplet population and cloud albedo, can result from a decrease of the surface tension of the droplets (Facchini, 1999). The size distribution of the cloud droplets has significant ef-

23171

fect on the cloud albedo or reflectivity, and consequently on the absorption of terrestrial infrared radiation and reflection of solar irradiation (Sun and Ariya, 2006). Therefore, the surface tension of aerosol droplets is of great importance and the knowledge of the surface tension could help in understanding climatic issues.

Theoretical prediction of liquid surface tension has been common due to the fast development of the molecular dynamics (MD) and the Monte Carlo (MC) simulation techniques. However, most studies focus on the surface tension of planar interfaces, where the surface tension could be obtained from the diagonal components of the pressure tensor and the length of the simulation box (e.g., Alejandrea et al., 1995; Chen and Smith, 2007). Only a few MD or MC simulation studies on liquid drops have been reported (Thompson et al., 1984; Zakharova et al., 1997; van Giessen and Blokhuis, 2009; Sampayo et al., 2010). Thompson et al. studied simple Lennard-Jones liquid drops by using the thermodynamic route and the mechanical route (Thompson et al., 1984); the thermodynamic route requires the knowledge of the surface tension of planar surface and assumes the first-order truncation of the Tolman equation (Tolman, 1949), while the mechanical route is based on the Irving-Kirkwood pressure tensor (Irving and Kirkwood, 1950). Thompson's results suggest a positive Tolman length, which means that the surface tension increases monotonically as the droplet radius increases. Differently, a recent MD study by van Giessen and Blokhuis suggests a negative Tolman length (van Giessen and Blokhuis, 2009). Sampayo et al. also claimed that the second-order contribution in liquid droplets cannot be neglected and the surface tension-radius curve has a weak maximum which indicates a negative Tolman length (Sampayo et al., 2010).

In our previous paper (Li et al., 2010), we reported a molecular dynamics study of the surface-active *cis*-pinonic acid in small water clusters under atmospheric conditions, and showed that the amount of decrease in surface tension of a droplet is not only related to the concentration of the surfactant, but also dependent on the size of the droplet. In particular, we found that *cis*-pinonic acid molecules are remarkably concentrated on the droplet surface and, with the increase of the size of the droplet,

23172

a lower concentration of *cis*-pinonic acid is needed to reduce the surface tension by a certain amount. In this paper, we discuss the curvature dependence of the surface tension of pure water droplets and water droplets containing glycine – an amino acid that appears in aerosol particles and behaves as an effective CCN material (Kristensson et al., 2010). Glycine in water is selected as a test system, motivated by that amino acid-water clusters are produced in marine environments by sea spray of phytoplankton and bacteria, and commonly assumed to form aerosols. The choice is also motivated by that activation properties of amino acid-water clusters have been analyzed in laboratory tests (Kristensson et al., 2010). In this work, the surface tension is studied over a range of cluster sizes, from sub-nanometers to the limiting case of a planar interface. By carefully analyzing the dependence of the surface tension on the parameterization of molecular dynamics we find it possible to interpolate the size dependence of the surface tension over the so-called Aitken mode particles, critical for water droplet formation. In our previous study (Li et al., 2010) the surface tension of water droplets has been calculated by using the rigid SPC/E (extended simple point-charge) water model (Berendsen et al., 1987), and the computed values are between 50 and 60 mJ m⁻², lower than the experimental value of 72 mJ m⁻². A more flexible water model which provides more degrees of freedom is expected to give larger surface tension and therefore better agreement with experimental measurements (Alejandrea et al., 1995; Zakharova et al., 1997). In this work, we employed the so-called semi-flexible SPC/E water model with constrained OH bond lengths and flexible HOH angle and followed the procedure described in our previous paper (Li et al., 2010) to study the surface tension for water droplets. The radial distributions of molecules in the droplets are analyzed and the curvature dependence of the surface tension were discussed. The surface tension change induced by the presence of glycine is also discussed in the framework of Köhler theory.

23173

2 Theory

2.1 Surface tension for planar interfaces

The surface tension of planar liquid/gas interface is usually divided into two contributions, the original part σ_o and the dispersion correction σ_d . The original part can easily be calculated from the diagonal components of the pressure tensor as described in the previous paper by Alejandrea et al. (Alejandrea et al., 1995)

$$\sigma_o = \frac{1}{2} L_z \left[P_{zz} - \frac{1}{2} (P_{xx} + P_{yy}) \right] \quad (1)$$

where P_{xx} , P_{yy} and P_{zz} denote the diagonal elements of the pressure tensor and L_z is the box length along z -axis.

Due to the use of the truncated Lennard-Jones potential, the dispersion correction to the surface tension has to be evaluated. To do this, the number density of the liquid along the z -axis is fitted to the hyperbolic tangent function

$$\rho(z) = \frac{1}{2} (\rho_\alpha + \rho_\beta) - \frac{1}{2} (\rho_\alpha - \rho_\beta) \tanh \left(\frac{z - z_0}{\xi} \right) \quad (2)$$

where ρ_α and ρ_β are densities for the liquid phase and the gas phase, respectively. Then the dispersion correction is calculated as (Blokhuys et al., 1995)

$$\begin{aligned} \sigma_d &= 12\pi\epsilon\sigma^6(\rho_L - \rho_V)^2 \int_0^1 ds \int_{r_c}^{\infty} dr (3s^3 - s) r^{-3} \coth \left(\frac{rs}{\xi} \right) \\ &= 12\pi\epsilon\sigma^6(\rho_L - \rho_V)^2 \int_0^1 ds \int_0^{1/r_c} dr' (3s^3 - s) r' \coth \left(\frac{s}{r'\xi} \right) \end{aligned} \quad (3)$$

23174

where we have used the substitution $r' = r^{-1}$ to perform the double integration on finite intervals. For liquids consisting of multiple components, the average value of $\varepsilon\sigma^6$ is used

$$\langle \varepsilon\sigma^6 \rangle = \frac{2}{N(N-1)} \sum_{i=1}^N \sum_{j>1}^N \varepsilon_{ij}\sigma_{ij}^6 \quad (4)$$

5 2.2 Surface tension evaluation of the spherical interface

In our previous paper (Li et al., 2010) we have demonstrated that the surface tension of an isolated spherical water cluster could be evaluated from the work of formation and the radius of the equimolar dividing surface, where the work of formation can be obtained from the Irving-Kirkwood pressure tensor, according to McGraw and Laaksonen (1996) and Zakharova et al. (1997). In this paper we implement the same procedure to calculate the surface tension for spherical interfaces. First, the radial number density is fitted to the hyperbolic tangent function

$$\rho(r) = \frac{1}{2}(\rho_\alpha + \rho_\beta) - \frac{1}{2}(\rho_\alpha - \rho_\beta) \tanh\left(\frac{r-r_0}{\xi}\right) \quad (5)$$

where ρ_α and ρ_β are densities for the liquid phase and the gas phase, respectively. Then the radius of the equimolar dividing surface is calculated from the density profile

$$R_e^3 = -\frac{1}{\rho_\alpha - \rho_\beta} \int_0^\infty r^3 \frac{d\rho(r)}{dr} dr \quad (6)$$

The normal component of the Irving-Kirkwood pressure tensor is calculated according to the formula given by Thompson et al. (1984)

$$\begin{aligned} P_N(r) &= P_K(r) + P_U(r) \\ &= k_B T \rho(r) + S^{-1} \sum_k f_k \end{aligned} \quad (7)$$

23175

where k_B is Boltzmann constant, T is temperature, S is the area of the spherical surface of radius r , and f_k is the normal component of the force between a pair of molecules acting across the surface S . Afterward the work of formation is obtained by performing integration over the $P_N(r)$ function as described by McGraw and Laaksonen (1996) and Zakharova et al. (1997)

$$\begin{aligned} W &= 2\pi \int_0^{R_\beta} [P_N(r) - P_\beta] r^2 dr \\ &= 2\pi \int_0^{R_\beta} P_N(r) r^2 dr - \frac{2\pi}{3} P_\beta R_\beta^3 \end{aligned} \quad (8)$$

where R_β is the radius of a sphere in the vapor region and $P_\beta = P_N(R_\beta)$ is the vapor pressure. Finally, the surface tension can be obtained from the work of formation and radius of equimolar surface

$$\sigma = \frac{3W}{4\pi R_e^3} \quad (9)$$

3 Computational details

The GROMACS program package (version 4.0.7) (Hess et al., 2008; van der Spoel et al., 2005) was used to carry out the molecular dynamics simulations. For water molecules the semi-flexible SPC/E (extended simple point-charge) water model (Berendsen et al., 1987) was employed, with the two OH bond lengths constrained at 1.0 Å by the LINCS (linear constraint solver) algorithm (Hess et al., 1997; Hess, 2008) and the HOH angle kept flexible. The HOH angle was modeled by a harmonic potential with an equilibrium angle of 109.47° and a force constant of 383.0 kJ mol⁻¹ rad⁻².

23176

For zwitterionic glycine molecules the OPLS (optimized parameter for liquid simulations) all-atom force field (Jorgensen et al., 1996) was used, with the bonds containing H atoms constrained by the LINCS algorithm (Hess et al., 1997; Hess, 2008). All simulations were performed in canonical (constant- NVT) ensembles, with temperature maintained at 298 K by the N se-Hoover thermostat (N se, 1984; Hoover, 1985). Periodic boundary conditions were applied during the simulations. The van der Waals interaction was modeled by the Lennard-Jones potential truncated at the cutoff radius of 10  . The Coulomb interaction was evaluated by the Ewald summation, where the real part of the potential is truncated at 10   and the reciprocal interaction is calculated by the SPME (smoothed particle mesh Ewald) (Darden et al., 1993; Essmann et al., 1995) method with a mesh of reciprocal vectors of 1.2   in every direction and a spline of order 4. The time step of the simulations was set to 2 fs.

To model the surface tension of spherical and planar interfaces, twelve systems consisting of either pure water or glycine/water mixtures were constructed, as listed in Table 1. Each system was initially set up from pre-equilibrated cubic simulation boxes, by using the “genbox” utility of the GROMACS program package (van der Spoel et al., 2005). In systems 1–10, the pre-equilibrated simulation boxes were enlarged in three dimensions so that the lengths of the boxes were 6.0 nm longer than the diameters of the spherical clusters, in order to minimize the interaction between the cluster and its periodic images. Here the diameter of the spherical cluster was estimated from the volume of the initial cubic box. In systems 11–12, the boxes were elongated three times along the z -axis to create the planar liquid/gas interfaces. Each system was subject to energy minimization and then 2 ns simulation to reach equilibrium, and another 2 ns simulation was carried out and the trajectories are saved every 0.2 ps for further analysis and calculations.

After the simulations were finished and the trajectories recorded, surface tension calculations were carried out as described in Sect. 2. The surface tension values for planar interfaces were evaluated from the diagonal components of the pressure tensor, while for spherical interfaces the surface tension data were obtained from the

23177

normal component of the Irving-Kirkwood pressure tensor. The curvature dependent surface tension was modeled by a polynomial function of the inverse of the radius of the equimolar dividing surface, and the glycine-induced surface tension change was extracted from the calculated data. The densities and radial distributions were also analyzed.

To get insight into the effect of glycine on the growth of aerosol droplets, the K hler theory was used to model the activation behavior of the droplets. The K hler theory (K hler, 1936) describes the nucleation and the equilibrium growth of cloud droplets. Two terms comprise the theory; the Kelvin term relates to the curvature of the droplet, which decreases the ability of droplet nucleation, a necessary step prior to further growth of the droplets, while the Raoult term increases the ability for droplet growth because of the solution of the aerosol constituents inside the droplet. Here the Kelvin term is related to the surface tension of the droplet, and an increase in the surface tension would result in an increase of the critical supersaturation.

4 Results and discussion

4.1 Spherical interface simulations

The calculated results for systems 1–6 are listed in Table 2, including the liquid density, the radius for equimolar dividing surface, the work of formation, and the surface tension. A decrease in density is found as the size of water droplet grows, and all the densities are larger than the standard density of the SPC/E water model (0.998 g cm^{-3} (Berendsen et al., 1987), equivalent to 33.361 nm^{-3}). This indicates a compression in water droplet induced by the surface tension, although such effect is very small. As the droplet grows larger, the effect of surface tension on the density of bulk phase becomes smaller. The radius number densities of water molecules are shown in Fig. 1, which can readily be fitted to the hyperbolic tangent function to derive the radius for the equimolar dividing surface as described in Sect. 2.

23178

The calculated normal component of the Irving-Kirkwood pressure tensor in systems 1–6 are shown in Fig. 2. In previous simulations for pure Lennard-Jones droplets (Thompson et al., 1984), it has been hypothesized that the $P_N(r)$ profile could also be fitted to a hyperbolic tangent function like density profile, however, this is not the case for water droplets we studied here. As can be seen from Fig. 2, each $P_N(r)$ curve has a peak near the surface, which could be tentatively attributed to the presence of the strong surface tension. In the bulk phase of each water droplet, the P_N curve is flatter, and the P_N value in bulk phase decreases as the size of the droplet increases. This again shows that the effect of surface tension on the bulk phase is becoming smaller as the droplet grows larger.

Listed in Table 3 are the computational results for systems 7–10. Clearly the densities in these systems are smaller than those in systems 1–6, due to the presence of the larger glycine molecules. The density decreases from system 7 to system 9, while in system 10 the density increases. A plausible interpretation to this phenomenon is that the glycine molecules are more uniformly distributed in larger droplets and that the decrease in the density would not be as pronounced as in smaller droplets. Figure 3 shows the number densities for glycine molecules in the droplets, in which the vertical dashed lines indicate the positions of the surfaces. The peaks in the $0 < r < 0.5$ region do not mean much due to the lack of statistics. It can be seen that in all droplets the density of glycine vanishes at the surface, indicating that the zwitterionic glycine molecules are very hydrophilic and prefer the bulk phase of the droplet.

The $P_N(r)$ profile for systems 7–10 are also calculated, as shown in Fig. 4. Comparing to Fig. 2, the $P_N(r)$ curves for systems 7–10 also have similar peaks near the surface. This is in accordance with the fact that the glycine molecules stay inside the droplet and have minor effect on the surface of the droplet. Consequently, the $P_N(r)$ curve in bulk phase of the droplet is significantly affected by the presence of glycine molecules. In system 8 (red lines in Figs. 3 and 4), the density of glycine has a small peak at around $r=1.0$ nm, resulting in the decrease of $P_N(r)$ at the same radius. In system 9 (blue lines in Figs. 3 and 4), the peak density at round $r=0.7$ nm results in a

23179

trough of $P_N(r)$ in the same region.

4.2 Planar interface simulations

The calculated densities and surface tension values for planar interfaces are listed in Table 4. The density in system 11 is smaller than those in systems 1–6, and the density in system 12 is smaller than those in systems 7–10, proving the compressing effect of the surface tension on spherical interfaces. The calculated surface tension for pure water (system 11) is obtained as $\sigma_o + \sigma_d = 65.63 \text{ mJ m}^{-2}$. This value is smaller than that reported by Alejandra et al. (1995) since they used limited number of lattice vectors in the reciprocal sum when evaluating the long-range electrostatic interaction, which is expected to overestimate the surface tension (Chen and Smith, 2007). On the other hand, our calculated surface tension for the planar water/air interface is larger than that reported by Chen and Smith (2007) in that we used the semi-flexible SPC/E model which could give larger surface tension and better agreement with experimental value than the rigid model. In the presence of glycine molecules (system 12) the surface tension becomes 66.17 mJ m^{-2} . Since the concentration of 10 glycine molecules in 1000 water molecules is 0.56 mol/L , the slope of surface tension with respect to concentration can be estimated as $d\sigma/dC = 0.96 \text{ mJ m}^{-2} \text{ L mol}^{-1}$, in good agreement with experimental measurements: $d\sigma/dC = 0.92$ (Pappenheimer et al., 1936) or 1.12 (Bull and Breese, 1974).

4.3 Curvature dependence of the surface tension

Regarding the planar interface as spherical interface with infinite radius, the relationship between the surface tension and the inverse of droplet radius could be drawn by fitting to a polynomial function. Tolman suggested a linear relationship between σ and $1/R$ by neglecting higher-order terms (Tolman, 1949); however our results suggest a quadratic relationship, with non-negligible contribution from the $1/R^2$ term.

The two fitted curves in Fig. 5 are $\sigma_w = 65.45 + 50.66/R_e - 100.00/R_e^2$ and

23180

$\sigma_{\text{GLY}} = 66.27 + 56.92/R_e - 132.71/R_e^2$, respectively, where R_e is the radius of the droplet (in nm) and σ is the surface tension (in mN/m). Note that the second equation is for a glycine concentration of 0.56 mol/L. As shown in Fig. 5, the two curves intersect at $R_e = 3.57$ nm, meaning that glycine will suppress the surface tension for droplets with smaller radius while increase the surface tension for droplets with larger radius. Assuming the deviation of the surface tension is linearly dependent on the concentration of glycine, as observed in experimental measurements (Pappenheimer et al., 1936; Bull et al., 1974) we can obtain the following formula for calculating the glycine-induced change in the surface tension for the planar case

$$\sigma = \sigma_W + (66.27 - 65.45) \times C/0.56 \quad (10)$$

and the spherical case

$$\sigma = \sigma_W + (0.82 + 6.26/R_e - 32.71/R_e^2) \times C/0.56 \quad (11)$$

where C is the concentration of glycine (in mol/L). These formulas are suitable for calculating the surface tension of aerosol droplets containing low-concentration of glycine.

4.4 Surface tension correction to the Köhler theory

The Köhler theory is formulated in terms of the Raoult effect and the Kelvin effect

$$s \equiv \frac{p}{p_0} = a_w \exp \left(\frac{4M_w \sigma}{RT \rho D_p} \right) \quad (12)$$

where p is the vapor pressure of water over a droplet, p_0 is the water vapor pressure over a flat surface of pure water, a_w is the water activity of the solution, M_w is the molar mass of water, σ is the surface tension, R is the gas constant, T is the temperature, ρ is the density of the solution, and D_p is the droplet diameter. By applying the surface tension formula to the Köhler equation, the Köhler curve for a glycine dry particle with diameter of 50 nm could be drawn, as shown in Fig. 6. All parameters in the Köhler equation were taken from the paper by Kristensson et al. (2010). The black line denotes the

23181

Köhler curve obtained by using the surface tension of pure water, that is, $\sigma = \sigma_W = 72.4$. The red dashed line denotes the Köhler curve obtained by using the planar surface tension correction: $\sigma = \sigma_W + (66.27 - 65.45) \times C/0.56$, $\sigma_W = 72.4$. The blue line denotes the Köhler curve obtained by using the curvature-dependent surface tension correction, $\sigma = \sigma_W + (0.82 + 6.26/R_e - 32.71/R_e^2) \times C/0.56$, $\sigma_W = 72.4 + 50.66/R_e - 100.00/R_e^2$. Here the value of σ_W has been shifted upward so that σ_W is equal to the experimental value of 72.4 when R_e is infinity. All the surface tension values are in mJ m^{-2} . From Fig. 6 it can be seen that for the three cases the critical supersaturation (the supersaturation are the Köhler curve is at its maximum) are 0.546%, 0.548%, and 0.553%, respectively, while the experimental value reported by Kristensson et al. (2010) is between 0.6% and 0.7%. Clearly the surface tension correction gives rise to a better agreement with experimental observation, although the correction to the critical supersaturation is relatively small.

5 Conclusions

In summary, atmospheric aerosol droplets, representative for remote marine areas, consisting of either pure water or glycine/water mixtures, were studied by molecular dynamics simulations. The surface tension for each droplet was estimated from the normal component of the Irving-Kirkwood pressure tensor. Different from the simple Lennard-Jones liquid droplet, the $P_N(r)$ profile for water cluster possesses a peak at the surface, indicating that the surface molecules are under strong tension. This is in accordance with the fact that water has a large surface tension and a low vapor pressure under ambient conditions. The radial distributions of glycine molecules were also studied in water droplets, and it was found that the radial densities vanish at the surface. In other words, the zwitterionic glycine molecules are very hydrophilic and tend to stay in the bulk phase of the droplet. The $P_N(r)$ profile of the droplet was perturbed by the presence of glycine molecules, resulting in glycine-induced surface tension change. To access the curvature dependence of the surface tension, the planar

interface was also investigated as the limiting case. The surface tension for the planar water/air interface was calculated to be 65.63 mJ m^{-2} , close to the experimental value of 72 mJ m^{-2} . The surface tension change induced by glycine is computed as $d\sigma/dC = 0.96 \text{ mJ m}^{-2} \text{ L mol}^{-1}$, in agreement with experimental measurements.

- 5 By interpolating the surface tension over the nano-sized droplets and the limiting case of the planar interface, a quadratic relationship is found between the surface tension and the inverse of the radius of the droplet, indicating a strong curvature dependence of the droplet surface tension. In this case the Aitken mode particles with larger sizes could be covered and the Köhler equation could be improved by incorporating surface tension corrections. By applying our results on the activation process of glycine dry particle with diameter of 50 nm, the critical supersaturation is improved from 0.546% to 0.553%. The correction is not so pronounced, since glycine is not a strong surfactant as, for instance, cis-pinonic acid and its effect on the surface tension is expected to be small. Nevertheless, our approach provides an efficient way of evaluating the surface tension for aerosol droplets, which could be of use in improving the accuracy of the Köhler equation in predicting the critical supersaturation of the activation process of cloud droplets in general and with specific interest to the remote marine aerosol derived from biology at the ocean surface.

Acknowledgement. The authors thank the Swedish Infrastructure Committee (SNIC) for providing computational resources for the project "Multiphysics Modeling of Molecular Materials", SNIC 022/09-25.

References

- Alejandre, J., Tildesley, D. J., and Chapela, G. A.: Molecular dynamics simulation of the orthobaric densities and surface tension of water, *J. Chem. Phys.*, 102, 4574–4583, 1995.
- 25 Berendsen, H. J. C., Grigera, J. R., and Straatsma, T. P.: The missing term in effective pair potentials, *J. Phys. Chem.*, 91, 6269–6271, 1987.
- Blanchard, D. C.: The oceanic production of volatile cloud nuclei, *J. Atmos. Sci.*, 28, 811–812, 1971.

23183

- Blanchard, D. C. and Syzdek, L. D.: Film drop production as a function of bubble size, *J. Geophys. Res.*, 93, 3649–3654, 1988.
- Blokhuis, E. M., Bedeaux, D., Holcomb, C. D., and Zollweg, J. A.: Tail corrections to the surface tension of a Lennard-Jones liquid-vapour interface, *Mol. Phys.*, 85, 665–669, 1995.
- 5 Bull, H. B. and Breese, K.: Surface tension of amino acid solutions: a hydrophobicity scale of the amino acid residues, *Arch. Biochem. Biophys.*, 161, 665–670, 1974.
- Chen, F. and Smith, P. E.: Simulated surface tensions of common water models, *J. Chem. Phys.*, 126, 221101-1–221101-3, 2007.
- Darden, T., York, D., and Pedersen, L.: Particle mesh Ewald: An N -log(N) method for Ewald sums in large systems, *J. Chem. Phys.*, 98, 10089–10092, 1993.
- 10 Essmann, U., Perera, L., Berkowitz, M. L., Darden, T., Lee, H., and Pedersen, L. G.: A smooth particle mesh Ewald method, *J. Chem. Phys.*, 103, 8577–8592, 1995.
- Facchini, M. C., Mircea, M., Fuzzi, S., and Charlson, R. J.: Cloud albedo enhancement by surface-active organic solutes in growing droplets, *Nature*, 401, 257–259, 1999.
- 15 Hess, B.: P-LINCS: A parallel linear constraint solver for molecular simulation, *J. Chem. Theory Comput.*, 4, 116–122, 2008.
- Hess, B., Bekker, H., Berendsen, H. J. C., and Fraaije, J. G. E. M.: LINCS: A linear constraint solver for molecular simulations, *J. Comput. Chem.*, 18, 1463–1472, 1997.
- Hess, B., Kutzner, C., van der Spoel, D., and Lindahl, E.: GROMACS 4: Algorithms for highly efficient, load-balanced, and scalable molecular simulation, *J. Chem. Theory Comput.*, 4, 435–447, 2008.
- 20 Hoover, W. G.: Canonical dynamics: equilibrium phase-space distributions, *Phys. Rev. A*, 31, 1695–1697, 1985.
- Irving, J. H. and Kirkwood, J. G.: The statistical mechanical theory of transport processes. IV. The equations of hydrodynamics, *J. Chem. Phys.*, 18, 817–829, 1950.
- 25 Jorgensen, W. L., Maxwell, D. S., and Tirado-Rives, J.: Development and testing of the OPLS all-atom force field on conformational energetics and properties of organic liquids, *J. Am. Chem. Soc.*, 118, 11225–11236, 1996.
- Kristensson, A., Rosenørn, T., and Bilde, M.: Cloud droplet activation of amino acid aerosol particles, *J. Phys. Chem. A*, 114, 379–386, 2010.
- 30 Köhler, H.: The nucleus in and the growth of hygroscopic droplets, *Trans. Faraday Soc.*, 32, 1152–1161, 1936.
- Li, X., Hede, T., Tu, Y., Leck, C., and Ågren, H.: Surface-active cis-pinonic acid in atmospheric

23184

- droplets: a molecular dynamics study, *J. Phys. Chem. Lett.*, 1, 769–773, 2010.
- McGraw, R. and Laaksonen, A.: Scaling properties of the critical nucleus in classical and molecular-based theories of vapor-liquid nucleation, *Phys. Rev. Lett.*, 76, 2754–2757, 1996.
- Mopper, K. and Zika, R. G.: Free amino acids in marine rains: evidence for oxidation and potential role in nitrogen cycling, *Nature*, 325, 246–249, 1987.
- 5 Nosé, S.: A molecular dynamics method for simulations in the canonical ensemble, *Mol. Phys.*, 52, 255–268, 1984.
- Pappenheimer, J. R., Lepie, M. P., and Wyman Jr., J.: The surface tension of aqueous solutions of dipolar ions, *J. Am. Chem. Soc.*, 58, 1851–1855, 1936.
- 10 Ramanathan, V., Cess, R. D., Harrison, E. F., Minnis, P., Barkstrom, B. R., Ahmad, E., and Hartmann, D.: Cloud-radiative forcing and climate: results from the Earth radiation budget experiment, *Science*, 243, 57–63, 1989.
- Sampayo, J. G., Maličevský, A., Müller, E. A., de Miguel, E., and Jackson, G.: Communications: Evidence for the role of fluctuations in the thermodynamics of nanoscale drops and the implications in computations of the surface tension, *J. Chem. Phys.*, 132, 141101, 2010.
- 15 Saxena, V. K.: Evidence of the biogenic nuclei involvement in Antarctic coastal clouds, *J. Phys. Chem.*, 87, 4130–4134, 1983.
- Solomon, S., Qin, D., Manning, M., Chen, Z., Marquis, M., Averyt, K. B., Tignor, M., and Miller, H. L. (eds.): *Climate Change 2007: The Physical Science Basis*, Contribution of Working Group I to the Fourth Assessment Report of the Intergovernmental Panel on Climate Change, 2007.
- 20 Sun, J. and Ariya, P. A.: Atmospheric organic and bio-aerosols as cloud condensation nuclei (CCN): a review, *Atmos. Environ.*, 40, 795–820, 2006.
- Thompson, S. M., Gubbins, K. E., Walton, J. P. R. B., Chantry, R. A. R., and Rowlinson, J. S.: A molecular dynamics study of liquid drops, *J. Chem. Phys.*, 81, 530, 1984.
- 25 Tolman, R. C.: The effect of droplet size on surface tension, *J. Chem. Phys.*, 17, 333–337, 1949.
- Twomey, S.: Pollution and the planetary albedo, *Atmos. Environ.*, 8, 1251–1256, 1974.
- van der Spoel, D., Lindahl, E., Hess, B., van Buuren, A. R., Apol, E., Meulenhoff, P. J., Tieleman, D. P., Sijbers, A. L. T. M., Feenstra, K. A., van Drunen, R., and Berendsen, H. J. C.: *Gromacs User Manual version 4.0*, www.gromacs.org, 2005.
- 30 van Giessen, A. E. and Blokhuis, E. M.: Direct determination of the Tolman length from the bulk pressures of liquid drops via molecular dynamics simulations, *J. Chem. Phys.*, 131, 164705,

23185

- 2009.
- Zakharova, V. V., Brodskaya, E. N., and Laaksonen, A.: Surface tension of water droplets: a molecular dynamics study of model and size dependencies, *J. Chem. Phys.*, 107, 10675–10683, 1997.

23186

Table 1. Number of molecules and length of the box in the twelve systems. In systems 1–10 the interfaces are spherical and $L_z=L_x=L_y$, while in systems 11–12 the interfaces are planar and $L_z=3L_x=3L_y$.

System	Interface	N_{GLY}	N_{W}	L_z/nm
1	Spherical	0	750	9.52
2	Spherical	0	1000	9.86
3	Spherical	0	1500	10.44
4	Spherical	0	2000	10.89
5	Spherical	0	3000	11.57
6	Spherical	0	5000	12.59
7	Spherical	10	1000	9.96
8	Spherical	20	2000	10.90
9	Spherical	30	3000	11.65
10	Spherical	50	5000	12.72
11	Planar	0	1000	9.36
12	Planar	10	1000	9.57

23187

Table 2. Calculated liquid density, radius for equimolar dividing surface, work of formation, and surface tension values for spherical interfaces in systems 1–6.

System	ρ_a/nm^{-3}	R_e/nm	$W/10^{-19} \text{ J}$	$\sigma/\text{mJ m}^{-2}$
1	34.636	1.73	7.61	60.78
2	34.614	1.90	9.74	64.16
3	34.469	2.18	13.73	68.83
4	34.357	2.40	16.91	69.84
5	34.267	2.75	22.55	70.96
6	34.187	3.27	31.38	70.13

23188

Table 3. Calculated liquid density, radius for equimolar dividing surface, work of formation, and surface tension values for spherical interfaces in systems 7–10.

System	ρ_a/nm^{-3}	R_e/nm	$W/10^{-19} \text{ J}$	$\sigma/\text{mJ m}^{-2}$
7	33.566	1.93	9.46	60.66
8	33.506	2.43	16.33	65.88
9	33.377	2.79	22.66	69.60
10	33.445	3.30	33.02	72.24

23189

Table 4. Calculated liquid density, radius for equimolar dividing surface, work of formation, and surface tension values for spherical interfaces in systems 11–12.

System	ρ_a/nm^{-3}	ξ/nm	$\sigma_o/\text{mJ m}^{-2}$	$\sigma_d/\text{mJ m}^{-2}$
11	33.674	0.141	60.01	5.62
12	33.251	0.137	60.15	6.02

23190




Fig. 1. Radial number densities of water molecules in systems 1–6.

23191




Fig. 2. Normal component of Irving-Kirkwood pressure tensor in systems 1–6.

23192




Fig. 3. Radial number densities of glycine molecules in systems 7–10. Vertical dashed lines indicate the positions of equimolar dividing surfaces of the clusters.

23193




Fig. 4. Normal component of Irving-Kirkwood pressure tensor in systems 7–10.

23194




Fig. 5. Curvature dependence of surface tension of pure water and glycine-water mixture.

23195




Fig. 6. Köhler curves for glycine (dry particle diameter=50 nm) without and with surface tension corrections.

23196