

Response to Editor comments to paper “The contribution of soil biogenic NO emissions from a managed hyper-arid ecosystem to the regional NO₂ emissions during growing season”

We sincerely thank the editor for her constructive comments and helpful suggestions. We carefully considered your comments and suggestions as described in detail below.

The revised MS has been improved based on your guidance, we:

- attempt to estimate the uncertainties of HONO and NO
- calculate the NO_x (NO, NO₂) emissions in terms of mass of atomic Nitrogen
- correct the grammatical errors within MS
- the title of the MS has been changed as “The contribution of soil biogenic NO and HONO emissions from a managed hyper-arid ecosystem to the regional NO_x emissions during growing season”

Our responses (AC, in italics) to the editor’s comments (EC) are given below.

EC 1. I appreciate the new text on HONO emissions. However, I agree with Referee 1 that some attempt to quantitatively bound the uncertainty surrounding HONO is necessary and still absent. Use of the HONO-NO emission relationships is apropos considering comparable soil types were studied. But the new text states that conditions were optimum for HONO to NO emission. Does this mean your estimates represent an upper bound to the HONO source? At a minimum provide a statement to whether your HONO estimates are an upper or lower bound. I imagine Oswald et al., provided uncertainty estimates to their emission factors and some way to think qualitatively about whether the HONO:NO emission factor they observed would change with season. Substitute this kind of bounding for your statement, “this may result in a certain error of the calculated HONO emissions, which unfortunately can not be quantified more precisely at the moment.”

Secondly, I do not quite agree with the implication in (page 27, line 24–26):

“nevertheless, the qualitative and, in particular, the quantitative agreement between bottom-up and top-down estimates indicates that our assumptions are largely justified.”

Instead, you might say the agreement between bottom-up and top-down estimates provides support for broader applicability of the lab derived HONO-NO emission relationships in space and time.

AC: *We appreciate the idea about a quantitative estimation of the uncertainty of the HONO fluxes. Since we used the ratio for the optimum condition ($F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$), the estimated HONO emissions represent an upper bound to the HONO source. Figure 8 (in the previous MS and also in the revised MS) thus showed the upper and lower bounds of soil biogenic emissions (either only NO emissions or NO plus HONO emissions).*

Oswald et al. (2013) do not provide uncertainty estimates to their emission factors.

But based on the errors for concentration measurements (12 % for HONO, see Soergel et al. 2011 and 5 % for NO, see Behrendt et al. 2014) we have conservatively

estimated the uncertainty of the calculated HONO emissions (upper bound) to about 10%. In our revised MS the following sentences were added:

- *In sect. 2.3.4 (page 16, lines 7-11): To quantify the uncertainties of calculated HONO emissions, the mean relative errors for concentration measurements of 12% for HONO (Soergel et al., 2011) and 5% for NO (Behrendt et al., 2014) were adopted. Based on these estimates, we performed a conservative error propagation calculation of the additional HONO emissions (at optimum conditions), which resulted in a relative error of 10%.*
- *In sect. 3.1.3 (page 23, lines 14-17): It is stressed, however, that the estimated HONO emissions are an upper bound to the HONO source since we used the ratio for the optimum condition ($F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$). The lower bounds can be determined when the HONO emissions source is omitted (see Fig 8.).*
- *In sect. 3.3. (page 28, lines 9-11): “which unfortunately can not be quantified more precisely at the moment “ was deleted. Here, it was added: “Taking the relative errors of the underlying concentration measurements, and the resulting scale factor into account, a relative error of the calculated optimum HONO emissions accounts for 10%”.*
- *On page 28 (lines 22-24): “nevertheless, the qualitative... largely justified.” In the revised MS, this sentence has been rewritten as: “Nevertheless, the agreement between bottom-up and top-down estimates provides support for the broader applicability of the lab-derived HONO-NO emission relationships in space and time”.*

EC 2. Although the new text attempts to clarify use of the term NO₂ emission, it is still hindering the readability of the text. This is in part because nothing appears to be gained from employing this unusual convention. The authors state that in using NO₂ emission, “the reported mass becomes independent of the ratio of portioning between NO and NO₂,” but this is exactly why the convention of ‘NO_x emission’ is prevalent in the literature, or even N emission. If regional NO_x emission estimates are reported as ‘NO₂ emission,’ then regional accounts either mean NO_x, or have somehow not accounted for the portion of NO_x that is NO. Simply stating that they are reported as ‘NO₂ emissions,’ but are in fact ‘NO_x emissions’ and then using the latter term would greatly aid the reader. Also, most of the soil emission text and Fig. 7 (and Fig. 6?) discuss NO emission, not NO₂ or NO_x emission, and there are a number of uses of NO_x when, by the authors’ convention, I believe NO₂ is meant.

AC: *We agree with the editor related to the above comment. Thus, we changed the above sentence to “...expressed as in terms of mass of atomic Nitrogen - partly because... “. The following changes can be found in revised MS:*

- *“Regional NO₂ emissions” has been changed as “Regional NO_x emissions”*
- *All calculated bottom-up emissions estimates (soil NO, soil HONO and anthropogenic NO_x) within MS and supplement are now expressed in terms of N (atomic mass of nitrogen).*

- *Monthly mean top-down emissions and their daily averages are now expressed in terms of N.*
- *All units of the related Figures have been changed accordingly (Fig. 4, Fig. 7, Fig. 8, Fig. 11, Fig. S6, Fig. S11 and Fig. S12)*

EC 3. Referee 1 technical comment 2: The change does not address the comment. Referee 1 was not asking for clarity in the sentence but for evidence for the claim that a winter and summer peak provide confidence in the method.

AC: *This sentence is changed to “The resulting total NO_x emissions show a strong peak in winter and a secondary peak in summer and the second maximum in summer was only found if the soil emissions were taken into account, which provides confidence in both completely independent methods”.*

EC4. Referee 1 technical comment 37: The response does not address the comment. The referee was asking for a statistical measure of agreement. Numerical agreement can only be to within uncertainties. That the agreement was surprising to you is irrelevant and should be deleted.

Referee 1 asks for quantification of the rough magnitude of the total error, in addition to discussion of the individual sources of uncertainty. I agree with the referee that this is needed. The new text does not provide this.

AC: *The sentence “Especially the quantitative agreement was better than expected taking into account the uncertainties of the bottom-up and top down emission estimates” was deleted.*

We added an estimation of the error of the soil emissions in sections 2.3.4 and 3.3, see also reply to comment 9 below.

EC5. Referee 2 technical comment 9: I agree with the referee that use of word ‘assimilation’ is unclear.

AC: *“Data assimilation” is believed to be the correct “state-of-the-art”-term, if sources of different “source quality” are considered. We added the sentence to the supplement (page 12).*

EC6. I do not think of agriculture as a biogenic source. Consider replacing ‘biogenic’ with a term that makes it clear you mean the emission from the oasis, where human activities have had a large impact on the NO flux. Also, use of the word ‘anthropogenic’ here really refers combustion emissions, not human activity.

AC: *We added to the manuscript the following text (sec. 1, page 5, lines 11-13): “Please note that in this study we use the term ‘biogenic emissions’ for all kinds of microbiological activities. Here also enhanced microbiological emissions caused by agricultural activities are included. We use the term ‘anthropogenic emissions’ for emissions from combustion.”*

EC7. Abstract, line 24: The paper makes no attempt place results from the Tohsun oasis in the broader context of global managed dry lands. I agree that in this study the oasis

source was sizable, but the paper does not address whether Tohsun oasis are scalable such that they are “strong evidence that biogenic emissions from soils of managed drylands ... are much more important contributors to regional NO₂ budgets ... than thought before.” The statement on photochemistry is also not discussed in the text, especially since if the soil HONO is large, than the more important effect may be that soils are directly emitting a HO_x source. Additionally, oases should have a disproportionate impact compared to cities as oases are NO_x sources to low NO_x environments, which will drive O₃ production, by contrast increased NO_x emission in cities may suppress O₃ production, at least in the near field.

AC: *The text in the abstract have been changed as follows: “Despite the regional character of these findings, particularly the second maximum in summer provides substantial evidence to hypothesize that biogenic emissions from soils of managed drylands (irrigated and fertilized) in the growing period may be much more important contributors to regional NO_x budgets of dryland regions than thought before.” The editor is right concerning the photochemical consequences of large HONO emissions with respect to a (potentially substantial) local HO_x source, particularly in a low NO_x environment. But again, due to the complexity of the HONO emissions from soils, the role of photochemistry should not be overstressed; consequently, we deleted the phrase “(hence to regional photochemistry)” in line 22-25 of the abstract.*

EC8. Section 2.5, line 6: Is not the height of the boundary layer (no caps) assumed? Also, is it not assumed that the boundary layer height does not vary with season, which is likely a poor assumption?

Section 2.5, line 10: Change “the characteristic time (lifetime) of the depletion” to “the NO_x chemical lifetime.” I would restate the assumed lifetime here. A second assumption is that the NO_x chemical lifetime does not vary seasonally or as a function of the NO_x abundance. The NO_x lifetime may increase by up to an order of magnitude in the winter. Do you see the same seasonal pattern in urban combustion emissions if the NO_x lifetime is treated as longer in the winter, especially in a shallow winter boundary layer? (Some text to this affect appears in Sect 3.3, but should be moved or at least mentioned where described.)

AC: *To calculate the top-down emission estimates (Section 2.5), the height of the boundary layer was not explicitly considered. Instead, as said in sect. 2.5 of the manuscript, we assumed that the abundance of NO₂ molecules of the tropospheric vertical column is concentrated within its lowermost part, the Atmospheric Boundary Layer (ABL). Therefore, a seasonal variation of boundary layer height has explicitly not been considered, the NO₂ concentration at ground level will generally correlate to the temporal pattern of the boundary layer height. However, in arid and semi-arid regions, due to the convective heating of the ground by the sun which produces buoyant thermals particularly at mid-day condition (at satellite overpass time), the entire atmospheric boundary layer is intensively mixed: under this condition NO₂ is well mixed within boundary layer and it is reasonable to expect that the tropospheric NO₂ vertical column density is dominated by the NO₂ concentration of the boundary layer. “The characteristic time (lifetime) of the depletion” has been changed to “chemical lifetime of the NO_x”. For the study area (section 2.5.2), we adopted a rough estimation of the lifetime from low and mid-latitudes, particularly from the dryland cities of Isfahan (32.6°N) and*

Riyadh (24.6°N). As already mentioned (page 27, lines 5-23), due to the lower wintery OH concentration, lifetime in winter is longer than corresponding values in summer. However, to keep the estimation of the top-down inventory simple, we used a temporally constant mean lifetime of 4 hours; which leads to a certain overestimation of the emissions in winter. Nevertheless, the considered lifetime within the study is a good approximation for the growing season, which is the focus of the study.

EC9. Section 3.3, line 29: Rewrite this sentence so as not to say agreement is “perfect.” Instead, agreement should be stated within (or outside) some designated uncertainty range. I recommend that the uncertainty discussion be moved to followed emission estimates. Also, while the discussion is useful, some attempt should be made to quantify total uncertainties. See comment 4.

AC: *Many thanks to the editor for her comment. This sentence was rewritten as: “However, a well quantitative agreement between bottom-up and top-down total emissions can be observed for the months of April, May, and October”.*

As we have already written in replies 1 and 4, in the revised MS, we added error estimations of both, the NO and HONO emissions to the revised version of the manuscript. In revised MS, we added the following information.

In section 2.3.4 (page 15, lines 1-8):

- *The soil temperature is usually the dominating factor of the uncertainties of NO fluxes because of the exponential dependence of the NO flux on soil temperature (typically expressed as the increase of the NO flux for a 10°C increase in soil temperature known as a Q10, see sec. 2.3.1). The mean Q10 value is 2 for both cotton and grape soils. The total uncertainties of bottom-up NO emissions were determined from: (a) the errors of the concentration measurements of NO, which was conservatively assumed as 5% (Behrendt et al., 2014); (b) errors of the simulated soil temperatures, which were assumed to be 1.5°-2.5°C in both estimates (satellite-derived (see Fig. S4) and estimated land surface temperatures (see Fig. S7)).*

In section 3.3 (page 27, lines 27-30; page 28, lines 9-17):

- *“Since the dependence of the NO flux on soil temperature is exponential, the calculated relative errors of NO by taking into consideration errors of soil temperature (1.5°-2.5°C) at Q10=2 accounts for 20% so that a total uncertainty of 25 % was assumed for the NO emission estimates”.*
- *“Taking the relative errors of the underlying concentration measurements, and the resulting scale factor into account, a relative error of the calculated optimum HONO emissions accounts for 10%. It is difficult, however, to estimate the total uncertainty of the calculated HONO emissions, because it is not clear how representative the emissions ratios determined by Oswald et al. (2013) are for the actual emissions from Tohsun oasis. However, we can safely assume that these HONO emissions lie between zero and the value shown in Fig. 8, which constitute emissions for optimum conditions. Thus we estimate the total uncertainty of the HONO emissions to be about 50%.”*
- *We, therefore, expect the uncertainty of total biogenic bottom-up emissions to be about 40%.*

- *In section 4 (page 30, lines 11-12): However, the uncertainty of the total biogenic bottom-up emission estimates is estimated to be about 40%.*

In response to the above comment of the editor as: "I recommend that the uncertainty discussion be moved to followed emission estimates."

We acknowledge the suggestion of the editor. However, we believe that the illustrative list of the uncertainties, as written in this work, might be more suitable for the present state-of-the-art knowledge.

EC10. The manuscript has a number of grammatical errors and the revised version should be read carefully to correct these.

AC: *Thank you for this comment. After including the changes based on editor's comments, we also worked to correct the existing grammatical mistakes.*

Again, we appreciate all your comments. Thank you for taking the time and energy to help us improve the paper.

Reference:

Soergel, M., Trebs, I., Serafimovich, A., Moravek, A., Held, A., and Zetsch, C.:
Simultaneous HONO measurements in and above a forest canopy: influence of
turbulent exchange on mixing ratio differences, *Atmos. Chem. Phys.*, 11, 841–855,
2011.

The contribution of soil biogenic NO and HONO emissions from a managed hyper-arid ecosystem to the regional NO_x emissions during growing season

5

Buhalqem Mamtimin^(1, 2) *, Franz X. Meixner⁽²⁾, Thomas Behrendt^(2,4), Moawad Badawy^(2, 3), and Thomas Wagner⁽¹⁾

10

⁽¹⁾ *Max Planck Institute for Chemistry, Satellite Research Group, Mainz Germany.*

⁽²⁾ *Max Planck Institute for Chemistry, Biogeochemistry Department, Mainz Germany.*

⁽³⁾ *Department of Geography, Faculty of Arts, Ain Shams University, Egypt.*

⁽⁴⁾ *Max Planck Institute for Biogeochemistry, Jena Germany.*

*Corresponding author: buhalqem.mamtimin@mpic.de

Abstract

A study was carried out to understand the contributions of soil biogenic NO emissions from managed (fertilized and irrigated) hyper-arid ecosystems in NW-China to the regional NO_x emissions during the growing season. Soil biogenic net potential NO fluxes were quantified by laboratory incubation of soil samples from the three dominating ecosystems (desert, cotton and grape fields). Regional biogenic NO emissions were calculated bottom-up hourly for the entire growing season (April-September 2010) by considering corresponding land use, hourly data of soil temperature, gravimetric soil moisture, and fertilizer enhancement factors. **The regional HONO emissions were estimated using the ratio for the optimum condition ((F_{N,opt}(HONO) to F_{N,opt}(NO)).**

Regional anthropogenic NO_x emissions were calculated bottom-up from annual statistical data provided by regional and local government bureaus which have been downscaled to monthly value. Regional top-down emission estimates of NO_x were derived on the monthly basis from satellite observations (OMI) of tropospheric vertical NO₂ column densities and prescribed values of the tropospheric NO_x lifetime. **In order to compare the top-down and bottom-up emission estimates, all emission estimates were expressed in terms of mass of atomic Nitrogen.** Consequently, monthly top-down NO_x emissions (total) were compared with monthly bottom-up NO_x emissions (biogenic + anthropogenic) for the time of the satellite overpass (around 13:00 LT) with the consideration of the diurnal cycle of bottom-up estimates. Annual variation of total Tohsun Oasis NO_x emissions is characterized by a strong peak in winter (December-February) and a secondary peak in summer (June-August). During summer, soil biogenic emissions were from equal to twofold of related anthropogenic emissions, and grape soils were the main contributor to soil biogenic emissions, followed by cotton soils while emissions from the desert were negligible. The top-down and bottom-up emission estimates were shown to be useful methods to estimate the monthly/seasonal cycle of the total regional NO_x emissions. The resulting total NO_x emissions show a strong peak in winter and a secondary peak in summer **and the second maximum in summer was only found if the soil emissions were taken into account, which is provides** confidence in both completely independent methods. **Despite the regional character of these findings, particularly the second maximum in summer provides substantial evidence to hypothesize that biogenic emissions from soils of managed drylands (irrigated and fertilized) in the growing period may be much more important contributors to regional NO_x budgets of dryland regions than thought before.**

1. Introduction

Atmospheric carbon monoxide, methane, and volatile organic compounds are oxidized by the hydroxyl and other radicals through various catalytic cycles (Crutzen, 1987). In these cycles, nitrogen oxides ($\text{NO}_x = \text{NO} + \text{NO}_2$) are key catalysts, and their ambient concentrations determine whether ozone (O_3) is generated or destroyed in the troposphere (Chameides et al., 1992). Ozone is usually generated in polluted, industrialized regions, where ambient levels of NO_x are high. Moreover, the intensification of agriculture is associated with increased NO emissions, which also causes an increase of available nitrogen in the atmosphere (Denman et al., 2007). NO_x in the troposphere originates mostly as NO, which reaches a photo-stationary equilibrium with NO_2 within a few minutes. The current evolution of anthropogenic as well as biogenic NO_x sources triggers a potential increase of global tropospheric O_3 concentrations. According to recent estimates (Kasibhatla et al., 1993; Davidson and Kingerlee, 1997; Denman et al., 2007; Feig et al., 2008), anthropogenic sources amount to 45-67% of the mid-2000s total global NO_x emissions ($42\text{-}47 \text{ Tg a}^{-1}$, in terms of mass of N), and other globally important sources are soil biogenic NO emissions (10-40%), biomass burning (13-29%) and lightning (5-16%). The considerable uncertainty about the range of soil biogenic NO emissions stems from widely differing estimates of the NO emissions. Based on field measurements worldwide Davidson and Kingerlee (1997) estimated the global NO soil source strength to be 21 Tg a^{-1} (with an error margin of 4 to 10 Tg a^{-1} , 40% of the total), while the 4th IPCC estimate is 8.9 Tg a^{-1} (Denman et al., 2007), which is higher than the 3rd IPCC estimate of 5.6 Tg a^{-1} (IPCC, 2001). Moreover, the uncertainties in the NO emission data from semi-arid, arid, and hyper-arid regions are very large (mainly due to a very small number of measurements being available). In this context, one should be aware, that approximately 40% of planet Earth's total land surface consists of semi-arid, arid and hyper-arid land and more than 30% of the world's inhabitants live in arid, semiarid and hyper-arid regions (Lai 2001). In many parts of the world's drylands, the land-cover is strongly changing due to the encroachment of deserts by bushy vegetation (desert → dryland farming; bushy vegetation → dryland farming). This leads and will result in dramatic changes in soil microbial production and consumption of NO. Consequently, it will have a strong impact on the (at least) regional budgets of those reactive trace gasses (NO_x , O_3 , volatile organic compounds (VOC), etc.) which are involved in the tropospheric oxidizing capacity. For this reason, it is necessary to quantify the NO emissions from both, natural and agricultural managed soils of the drylands.

Recently, Oswald et al. (2013) pointed out, that (a) the release of odd reactive nitrogen gasses from soils due to microbial activity is not confined to NO only, (b) about equal amounts of gaseous nitrous acid (HONO) are simultaneously emitted along with NO, and (c) HONO emissions from soils are one of the most relevant sources in arid areas with regard to tropospheric chemistry. In addition, daytime NO production from HONO photolysis contributes to the total production of NO_x emissions. Therefore, it is meaningful to consider HONO emissions for any estimates of biogenic total reactive nitrogen emissions from soil.

The biogenic emissions of NO (as well as HONO) depend crucially on soil temperature and soil moisture because these factors affect the availability of organic compounds and the microbial activity in the soil (Conrad, 1996; Meixner and Yang, 2006; Ludwig et al., 2001; Oswald et al., 2013). Sufficient soil moisture, high soil temperatures, and regular supply of nutrients (N-containing fertilizer) are optimum conditions for soil biogenic NO (and HONO) emissions, particularly from arid and hyper-arid land.

An oasis is an agriculturally used area in a desert region. The intensification (economically driven) of oasis agriculture, however, needs enlargement of the arable land area, enhancement of necessary irrigation, and the increase of fertilizer use, which leads inevitably to increasing soil biogenic NO (and HONO) emissions. Microbial processes, which underlay NO production (and NO consumption) in soils (e.g., nitrification, denitrification) are confined to the uppermost soil layers (<0.05 m depth, Rudolph et al., 1996). The most direct method for the characterization of these processes and the quantification of the NO (and HONO) release from soils is usually realized by laboratory incubation of soil samples taken from top soil layers. In those laboratory incubation systems, the net release rate of NO is determined from the NO concentration difference between incoming and outgoing air. The application of this method in the past has proved that the release of NO can be described by specific and unique functions of soil moisture, soil temperature, and ambient NO concentration (Otto et al., 1996; van Dijk et al., 2002; Meixner and Yang, 2006; Feig et al., 2008; Behrendt et al., 2014; Mamtimin et al., 2015).

Due to the industrialization of Chinese drylands and also to the intensification of their agriculture, not only significant anthropogenic NO_x emissions from growing oasis cities are expected, but also the current and future land use will intensify the "hot spot" character of soil biogenic NO emissions from oases. The general aim of the present study is to determine the contributions of soil biogenic NO emissions of a selected oasis in the Taklimakan desert to the regional NO_x emissions during the

growing season. For that, we concentrate (a) on the determination of net potential biogenic NO fluxes derived from laboratory incubation measurements of soil samples, (b) on the bottom-up calculation of regional biogenic NO and HONO emissions for the growing season taking into account the corresponding land use, soil temperatures, gravimetric soil moistures, and fertilizer factors, (c) on the bottom-up estimation of regional anthropogenic NO_x emissions of the oasis based on energy consumption and NO_x emission factors of different energy sectors and fuel types, (d) on the top-down calculation of regional total NO_x emissions from satellite observations (OMI) of the vertical NO₂ column densities and prescribed values of tropospheric NO_x lifetime, and (e) on the quantitative comparison of regional total NO_x emissions obtained by both (bottom-up (biogenic + anthropogenic) and total top-down) approaches.

Please note that in this study we use the term “biogenic emissions” for all kinds of microbiological activities. Here also enhanced microbiological emissions caused by agricultural activities are included. We use the term “anthropogenic emissions” for emissions from combustion.

2. Materials and methods

2.1 Site description and soil sampling

The study area “Tohsun Oasis” (Fig. 1) is a hyper-arid region located in the Xinjiang Uyghur Autonomous Region of P.R. China (Mamtimin et al., 2005). The Tohsun Oasis belongs administratively to Turpan County with Turpan City as capital (50 km NE from Tohsun Oasis). The Tohsun Oasis has an extension of 1479 km², a population of 138 thousand, and topographically constitutes the deepest point of P.R. China (154 m below sea-level; Pu, 2011). Major landform types of the Tohsun Oasis are sandy-desert and Gobi-desert (stone desert), surrounded on three sides by the mountains of Bogda (north), Qoeltagh (south), and Alagou (west). Topographically, the Tohsun Oasis slopes down from northwest to southeast. According to the Koeppen classification (Kottek et al., 2006), the climate of Tohsun Oasis is classified as “cold desert”; i.e. hot summers (July: 33°C), cold winters (January: -6°C), and very low precipitation. Mean annual potential evaporation is about 3400 mm (see Fig. 2), while the mean annual precipitation is as low as 7 mm.

The mean monthly precipitation for Tohsun (not shown in Fig. 2) is extremely low: rainfall in June and July is about 2 mm, in January, August, and September 1 mm, respectively; and there is no rain for the rest of the year. Agriculture played and plays a significant role in Tohsun Oasis; it was one of the most flourishing oases on the ancient Silk Road (Weggel, 1985). Due to the substantial lack of

rainfall, regular dry-land farming is impossible without massive irrigation. Water supplies for irrigated agriculture are dependent on groundwater (pumping-wells), and on the Bai Yanggou River, which originates from the Bogda Mountains. The Bai Yanggou River is temporally, defined by the strong seasonal pattern of snow-melt and rain in the mountains (Mamtimin, 2005).

- 5 Tohsun Oasis' agriculture is dominated by intensive mono-cultivation of grapes and cotton. Grapes from the Turpan County are naturally dried to raisins which are sold on the Chinese internal market and also exported to some Asian countries (Jin, 2011; Pu, 2011). Grapes from Turpan County account for 52 % of grape production in the Xinjiang Uyghur Autonomous Region, and for 20 % of entire China. There, more than 100 small and medium size companies are engaged in raisin processing (Wan, 2012). In 2008, Turpan's raisin production was 130.000 tons which accounted for more than 90 % of all raisins produced in P.R. China (Wan, 2012; Li et al., 2012; Jin, 2011; Pu, 2009). Approximately 40% of Turpan's grape production is from the Tohsun Oasis (Pu, 2009). To raise the yields of grapes and cotton, the corresponding cultivation techniques have been optimized, which resulted in the extensive application of nitrogen containing fertilizers.
- 10
- 15 Soil samples from the study area were collected in 2010 from a total of three sites of Tohsun's cotton fields, and from a total of two sites of grape fields (for sample locations, see Fig. 1). Since the primary production and consumption zones for NO are located within a very shallow layer at the soil surface (1 to 5 cm, e.g. Meixner and Yang, 2006), only soil samples 5 cm top soil were taken. At each of the sampling sites ten soil samples (approx. 150 g) with stainless steel soil cores (5 cm
- 20 length, 2.5 cm radius) were taken (randomly from a 10x10m² area); these were then combined to constitute a representative soil sample of approximately 1.5 kg in mass. These soil samples were stored at 4°C for a maximum 3 months until analysis since the microbial alterations are not expected within storage for up to 3 months at 4° C (Stotzky et al., 1962). In this study, we also used soil samples from the (non-fertilized) desert ecosystem as the reference, where the desert soil data was adapted from the study of Mamtimin et al. (2015).
- 25

2.2 Remote sensing and accompanying data

- Remote sensing data from both Landsat and Aura satellites (measurements by the Ozone Monitoring Instrument, OMI) were used in combination with a Geographical Information System (GIS). Landsat images, provided by United States Geological Survey, are widely applicable for purposes of our study because of their rather high spatial resolution (30-15 m). Since the aim of our study is the
- 30

quantification of biogenic NO emissions from intensively managed arid soils, the consideration of the growth state of the corresponding agro-ecosystems is important. For the representation of the different seasons, we selected four individual months: April (spring) for the beginning, July and August (summer) for the middle and September (autumn) for the end of the vegetation period. The winter season was not considered as most of the agro-ecosystems are frozen. Hence, any microbial activities are negligible. As proposed by many authors (Schott et al., 1985; Markham et al., 1986; Irish, 2003; Chander et al., 2003) we derived areal distributions of land surface temperature (LST), and land cover types from corresponding satellite data using remote sensing digital image processing. For the selection of Landsat images we confined ourselves to the year 2010 when we have taken the soil samples. Six individual Landsat images of the Tohsun Oasis (25 April, 28 July, 13 and 21 August, 06 and 22 September 2010) were used.

Tropospheric NO₂ column densities derived from the OMI satellite instrument (DOMINO version 2.0, Boersma et al., 2011) for the year of 2010 were used for top-down estimates of total NO_x emissions and comparison with total bottom-up emission estimates (biogenic + anthropogenic). The long-term seasonal variability of the tropospheric NO₂ was derived from the data of 2006-2010. For the estimation of anthropogenic sources of NO_x, we used fossil fuel consumption data from different economic sectors (manufacturing, electricity, transportation and domestic) which were obtained from the Xinjiang Statistical Yearbooks (Jin et al., 2009; Jin et al., 2011) and the Turpan Statistical Yearbooks (Pu, 2011). The emission-reduction coefficient for coal-fired thermal power industry was taken from “China Electric Power Yearbook” (Zhou, 2006). The land use map of Xinjiang (1:10.000.000; Ma, 2010) and the Traffic Map of Tohsun (1: 1.050.000; Ma, 2010) were involved in this study as additional tools for land use classification.

The meteorological data set (1971-2005) of the Tohsun County Meteorological Station (42.7833°N, 88.6500°E; +1 m a.s.l.) was supplied by the Xinjiang Meteorological Bureau. It contains monthly mean (1971-2005) data of air temperature, precipitation, evaporation, wind speed, and direction. Unfortunately, soil moisture content and soil temperature have not been measured routinely at Tohsun County Meteorological Station. *In-situ* measurements have been performed with a suitable sensor (MSR® 165 data logger; Rotronic, Switzerland) which has been buried at the site of Tohsun County Meteorological Station at 2.5 cm depth between July and September 2010. While soil temperature data was measured directly, data of gravimetric soil water content were obtained by gravimetric calibration of the sensor’s signal (relative humidity of soil air).

2.3 Bottom-up calculation of biogenic NO emission estimates

Estimates of seasonal (monthly) bottom-up biogenic NO emissions for Tohsun Oasis need (a) laboratory derived, land use type specific net potential NO fluxes (sect. 2.3.1), (b) the areal distribution of the three land use types (cotton, grapes, and desert) of Tohsun Oasis (sect. 2.3.2), and (c) land use type specific and temporally high-resolution data (sect. 2.3.3) of soil temperature, gravimetric soil moisture content, and fertilizer (enhancement) factors.

2.3.1 Laboratory determination of land use type specific net potential NO fluxes

During the last two decades, the laboratory incubation method has been used to measure the net NO release from soil (Yang and Meixner, 1997; Otter et al., 1999; Kirkman et al., 2001; Feig et al., 2008; Yu et al., 2008; Ashuri, 2009; Gelfand et al., 2009; Bargsten et al., 2010; Behrendt et al., 2014; and Mamtimin et al., 2015). However, today's knowledge of soil biogenic NO emission rates from managed arid soils is still rather limited (c.f. Behrendt et al., 2014; Mamtimin et al., 2015; Delon et al., 2015). The laboratory incubation method is usually dynamic chamber system which are consists gas dilution, thermostat valve, thermostat cabinet, and analyzers (Behrendt et al., 2014). The dynamic chamber was made of Plexiglas with a diameter and height of 9.2 cm and 13.6 cm (Behrendt et al., 2014), respectively. Five chambers were used for soil samples while one was kept empty as a reference and the thickness of the sample in the dynamic chamber kept the same (approx. 5 cm). The wetted soil samples were placed into five chambers while one was kept empty as reference chamber. Then, the net potential NO release rates were measured until the soil was completely dried out. Laboratory measured NO fluxes by using the incubation method have repeatedly been shown to be in good agreement with those measured in the field (Mayer et al., 2011; van Dijk et al., 2002, Ludwig et al., 2001). The net release of NO from soil is the result of microbial production and consumption processes which occur simultaneously (Conrad, 1996). In our study, we investigated net NO releases (J_{NO} ; in terms of mass of nitrogen per mass of dry soil and time), as well as potential NO fluxes (F_{NO} ; in terms of mass of atomic nitrogen per area and time) of cotton, grapes and desert soils. The methodology for the laboratory soil measurements which is used in the frame of this study is described in detail in Behrendt et al. (2014) and Mamtimin et al. (2015). By application of the laboratory dynamic chamber method, the net potential NO flux F_{NO} ($\text{ng m}^{-2} \text{s}^{-1}$, in terms of mass of N) is defined by

$$F_{NO}(\theta_g, T_{soil}) = J_{NO}(\theta_g, T_{soil}) \frac{m_{soil}}{A} \quad (1)$$

where J_{NO} (in $\text{ng kg}^{-1} \text{s}^{-1}$) is derived from the laboratory measurements, as well as the dimensionless gravimetric soil moisture θ_g . The soil temperature T_{soil} (in $^{\circ}\text{C}$), the total mass of the dry soil sample m_{soil} (in kg), and the cross section of the dynamic chamber A (in m^2) were directly measured.

Soil moisture and soil temperature had been identified as the most dominant influencing factors of the net NO release; therefore, J_{NO} is usually parameterized by these two quantities (Yang and Meixner, 1997; Otter et al., 1999; Kirkman et al., 2001; van Dijk et al., 2002; Meixner and Yang, 2006; Yu et al., 2008, 2010; Feig et al., 2008; Ashuri, 2009; Gelfand et al., 2009 and Bargsten et al., 2010). While the dependence of J_{NO} on T_{soil} is exponential, the dependence of J_{NO} on θ_g has the form of an optimum curve. These dependencies are described by two explicit dimensionless functions, the so-called optimum soil moisture curve $g(\theta_g)$ and the exponential soil temperature curve $h(T_{\text{soil}})$ which are described in detail by Behrendt et al. (2014). Introducing $\theta_{g,0}$, the so-called optimum gravimetric soil moisture content (i.e., where the maximum NO release has been observed), and $T_{\text{soil},0} = 25^{\circ}\text{C}$ as the reference soil temperature, the net potential NO flux, specific for the soils of each land use type i (i : grape fields, cotton fields, desert) is given by

$$F_{NO,i}(\theta_{g,i}, T_{\text{soil},i}) = J_{NO,i}(\theta_{g,0,i}, T_{\text{soil},0,i}) g_i(\theta_{g,i}) h_i(T_{\text{soil},i}) * (m_{\text{soil}} / A) \quad (2)$$

The land use type specific exponential soil temperature curve $h(T_{\text{soil},i})$ and the land use type specific optimum soil moisture curve $g(\theta_{g,i})$ are defined by eqs. (3) and (4):

$$h(T_{\text{soil},i}) = \exp \left[\frac{\ln Q_{10,NO,i}}{10} (T_{\text{soil},i} - T_{\text{soil},0}) \right] \quad (3)$$

$$g(\theta_{g,i}) = \left(\frac{\theta_{g,i}}{\theta_{0,i}} \right)^a \exp \left[-a \left(\frac{\theta_{g,i}}{\theta_{0,i}} - 1 \right) \right] \quad (4)$$

Land use type specific shape factors “a” of the corresponding optimum soil moisture curves were derived from laboratory drying-out incubation studies on the corresponding soil samples according to Behrendt et al. (2014). The land use type specific quantity $Q_{10,NO}$ is the (logarithmic) slope of $h(T_{\text{soil}})$, which was also derived from the laboratory measurements; applying two different soil temperatures, $T_{\text{soil},0}$ and $T_{\text{soil},1}$ ($T_{\text{soil},1} - T_{\text{soil},0} = 10$ K), the land use type specific $Q_{10,NO}$ is defined by

$$Q_{10,NO} = \frac{\ln F_{NO}(\theta_{g,0}, T_{\text{soil},1}) - \ln F_{NO}(\theta_{g,0}, T_{\text{soil},0})}{T_{\text{soil},1} - T_{\text{soil},0}} \quad (5)$$

2.3.2 Determination of land use types and corresponding land surface temperatures from Landsat Imagery

We used Landsat images since Landsat provides land surface information in a fine scale matrix (30x30 m²). The Landsat TM/ETM+ sensors acquire land surface information and store it as a digital number (DN) which ranges between 0 and 255. Landsat images are widely applied for the estimation of biospheric applications, such as the Normalized Differenced Vegetation Index (NDVI), Land Surface Temperature (LST), Soil Moisture Index (SMI), and fluxes of matter between different ecosystems, etc. (Goward and Williams, 1997; Liang et al., 2002; Lu et al., 2002). To perform land use classification and to derive the corresponding land use specific surface soil temperature, we have developed a tool by using ARCGIS 10.x, namely the so-called “Geoscience General Tool Package” (GGTP, see supplement, sections S1.1 – S1.7). Within GGTP model, we also calculated the 2D distributions of soil biogenic NO emissions (s. section S1.9).

Land use classification

To classify these field-specific vegetation types, pre-processing the Landsat imagery and image interpretation has to be performed. To effectively record the image data, histogram equalization and edge detector techniques (Jensen, 2005) were applied to image pre-processing. By using suitable edge detecting functions, Landsat images were enhanced, and boundaries between different classes were strongly highlighted for effective subsequent image interpretation. Due to the significant requirements for the different areas of interests (AOIs) of image classification, in-situ GPS data (160 points) from the field campaigns (2010) and also from previous field investigations (2006, 2008) were used. Spectral signatures of *in-situ* data were collected by digitizing and were consequently used to classify all pixels. For that, image spectral analysis and the mostly used supervised classification method of maximum likelihood by Jensen (2005) was performed. This procedure ensured that (a) spectral characteristics of all AOIs were used, and (b) every pixel (both, within and outside AOIs), was assessed and associated to that land-cover of which it has the highest likelihood of being a member.

Land surface temperature T_s

Knowledge of the land surface emissivity (ϵ) is highly indispensable to retrieve the land surface temperature (T_s) from remotely sensed data. As the land cover varies greatly from place to place, land

surface emissivity widely varies from one location to another. Therefore the land surface temperature T_s is defined as:

$$T_s = \frac{1}{\varepsilon^{0.25}} T_B \quad (6)$$

- 5 The land surface emissivity (ε) can be obtained from red and near-infrared (NIR) spectral reflectance, while at-sensor brightness temperature (T_B) can be calculated from the satellite image's thermal band of high gain mode (band 6.2); more details are given in the supplement (section S1.2 – S1.6).

2.3.3 Temporally high-resolution data

Bottom-up calculations in this study aim for regional, seasonal (monthly), and land-use-specific soil biogenic NO emissions via laboratory-derived net potential NO fluxes, which depend on soil temperature, gravimetric soil moisture (sect. 2.3.1), and fertilizer factors (i.e., amplification of NO fluxes due to the application of fertilizer). However, the necessary timescale for this data must be much shorter than a seasonal (monthly) timescale: (a) there is a strong nonlinear response of the net potential NO flux to soil temperature and gravimetric soil moisture (eqs. (3), (4)), as well as to fertilizer applications; and (b) there are large diel variations of the topsoil temperature (e.g., 10–60°C in July; Tohsun Oasis desert soil) and large diel to weekly variations of soil moisture and soil nutrient content caused by the applied irrigation and fertilization schedules. Consequently, seasonal (monthly) land-use-type specific soil NO emissions have to be averaged from data calculated on much shorter timescales (< 1 h).

20 Soil temperature, T_{soil}

Due to the very low soil temperature before and after the growing season (s. Fig. 1b), most of the soil surface is expected to be frozen, and biogenic emissions from any soils of the Tohsun Oasis can be neglected. Thus, mean monthly soil NO emissions were only calculated for the period between April to September. *In-situ* measurements of soil temperature (and soil moisture; 2.5 cm depth; 5 min resolution) at the Tohsun Oasis have been performed only for the land use type "desert", and only for the period 01 July to 30 September 2010 (see sect. 2.2). However, soil temperature (and soil moisture; 2.5 cm depth; 5 min resolution) have also been measured at two other Taklimakan oases during the same period, namely at Kuche (41.5360°N, 82.8546°E; "cotton soils") and Minfeng (37.0534°N; 82.0760°E; "jujube soils"). For this study, data from Kuche were adopted for the land use type "cotton soils" of Tohsun Oasis, while data from Minfeng were chosen to substitute "grape soils" data of

Tohsun Oasis. The latter is justified by the fact that both grapes and jujube belong to the bushy agricultural landscape type; they have similar height, distance in rows, water requirements, and percent ground cover by their canopy. For each of the three land use type data sets, each original measured data point (5 min, July-September, 2010) of a particular day has been normalized by the mean value observed at 10:45 LT (Landsat satellite overflight, supplement Fig. S7). Then, a mean diel variation data set (30 min) has been created by averaging all respective data between 1 July–30 September constituting the representative diel variation of the (normalized) soil temperature of the respective land use type valid for the entire growing period (supplement, S3.1; Fig. S8). As described in section S3.1 of the supplement, land-use-type specific surface temperatures (T_s ; sect. 2.3.2) derived from Landsat observations on 25 April, 28 July, 13 and 21 August, 06 and 22 September 2010 (sect. 2.2) have been temporally upscaled for the entire growing season (01 April – 30 September 2010). Finally, the diel variation of soil temperatures of the land use types “desert”, “cotton soils”, and “grape soils” for every day of the growing season in 2010 was obtained by multiplying the normalized soil temperatures.

The interpolation of the satellite-derived data was done by a 3rd order polynomial. To estimate the corresponding uncertainties we compared results using polynomials of degree 2 and 3 for the fitted curve. We found that R^2 in the 2nd degree model was 89 % while in the 3rd degree model it is 98 %.

Gravimetric soil moisture θ_g

Evaluation of the MSR[®] 165 data logger measurements (see sect. 2.2) at the site of Tohsun County Meteorological station (bare desert soil) have demonstrated a temporally quite constant, very low gravimetric soil moisture content of 0.0028, which has been adapted for the entire growing season (April–September 2010) land use type “desert” of Tohsun Oasis. Temporal variation of gravimetric soil moisture content of the two other land use types, “cotton soils” and “grape soils” depend strongly on irrigation amounts and schedules. Unfortunately, there is no official information on Tohsun Oasis's irrigation available, neither on amounts or schedules, and, consequently, none on the gravimetric soil moisture contents during the drying-out phases between individual irrigation events. Therefore, as for data assimilation of soil temperatures (see above), gravimetric soil moisture content data observed at Taklimakan's oases Minfeng (“cotton soils”) and Kuche (“jujube soils”) have been adapted for Tohsun Oasis's land use types “grape soils” and “cotton soils”, respectively. That consists of temporally constant irrigation schedules, starting on 1 April 2010 and repeated every 2 weeks.

From the observations at Minfeng and Kuche, so-called “drying-out” shape functions could be defined, which were scaled by multiples of the soil specific physical quantity “field capacity (FC)”, the amount of water content held in the soil after excess (irrigation) water has drained away. The quantity FC is typically used in irrigation scheduling, calculation of plant available water, and
5 **calculation of** water depth to be applied by irrigation (Diallo and Mariko, 2013). FC-data of soil samples from Minfeng and Kuche oases have been determined by laboratory measurements (see sect. S1.8, supplement). Finally, for Tohsun Oasis's land use types, “cotton soils” and “grape soils”, the following gravimetric soil moisture contents have been chosen (for details, see sect. S3.2, supplement): (a) 0.086 (“grape soils”) and 0.167 (“cotton soils”) before the first irrigation event
10 (corresponding to mean gravimetric soil moisture contents at conditions of $0.25 \times FC$ and $0.5 \times FC$, respectively), and (b) 0.514 (“grape soils”) and 0.586 (“cotton soils”) after each irrigation (corresponding to mean gravimetric soil moisture contents at conditions of $1.5 \times FC$ and $1.75 \times FC$, respectively). Since for each irrigation event (every 14 days) the starting and end conditions in terms of gravimetric soil moisture content were known, as well as the functional relationship for the
15 temporal drying-out of “cotton soils” and “grape soils” between the irrigation events, temporally high-resolution data (30 min) could be calculated. The result, the seasonal variation (01 April 2010 (DOY 90) – 30 September 2010 (DOY 273)) of the gravimetric soil moisture content (at 30 min resolution) for the land use types “cotton fields” and “grape fields” of Tohsun Oasis is illustrated in Fig. S9 (supplement).

20 **Fertilizer factor FF**

To maintain the productivity of the grape and cotton fields of Tohsun Oasis, the soils regularly receive considerable N-containing fertilizer amounts (see sect. 2.1). The impact of the fertilizer application on the NO-fluxes from arable soils of Taklimakan oases was recently investigated by Fechner (2014) using the laboratory dynamic chamber system described by Behrendt et al. (2014).
25 Dependent on the applied fertilizer amount (FA), NO-fluxes from all soil samples increased considerably and immediately after fertilizer application, which was accomplished by dissolving the mineral fertilizer in that amount of water **that** was used to wet the soil samples (just to mirror the fertilization procedures of the Taklimakan oases). The impact of fertilization is twofold: (a) it strongly amplifies the net release (net potential flux) of NO over the entire range of gravimetric soil
30 moisture, and (b) there is a moderate amplification of the net NO release (net NO potential flux) with

soil temperature. Furthermore, the impact of fertilization has also a temporal dimension: it has been shown that the fertilizer effect on the emission of N-containing gases is temporally declining after each fertilization event (Chen et al., 2011). Therefore, the fertilizer effect may be considered (a) by the multiplicative, *FA*-dependent, time-dependent, dimensionless “fertilizer factor (*FF*)” applied to the standard net release $J_{NO}(\theta_{g,0}, T_{soil,0})$ in Eq. (2) and (b) by the *FA*-dependent, time-dependent, dimensionless “ Q_{10} factor ($Q_{10}F$)” that is also multiplicatively applied to Q_{10} (the logarithmic slope of the exponential soil temperature curve $h(T_{soil})$). According to Fechner (2014), initial fertilizer effects are $FF = 142, 179, 205, \text{ and } 226$ and $Q_{10}F = 1.21, 1.24, 1.25, \text{ and } 1.26$ for fertilization amounts $FA = 100, 200, 300, \text{ and } 400 \text{ kg (N) ha}^{-1}$, respectively. From recommendations of Tohsun Oasis' local agricultural administration (personal information, 2010) and our personal communication with farmers there (2010), data for applied fertilizer amounts as well as for fertilizing schedules could be inferred. With the assumption of an exponential decay of the fertilizer effects, corresponding functional relationships for the temporal behaviors of *FF* and $Q_{10}F$ have been developed (see sect. S3.3, supplement), and temporally high-resolution data (30 min) of *FF* and $Q_{10}F$ were calculated. The result, the seasonal variation (01 April 2010 (DOY 90) – 30 September 2010 (DOY 273)) of the (dimensionless) factors *FF* and $Q_{10}F$ for the land use types "cotton fields" and "grape fields" of Tohsun Oasis, is illustrated in Fig. S10 (supplement).

2.3.4 Monthly soil biogenic NO and HONO bottom-up emissions of Tohsun Oasis

Estimates of soil biogenic NO fluxes can be calculated from net potential NO fluxes (see sec. 2.3.1) according to eqs. (1)-(4), since those NO fluxes that are derived from laboratory incubations have repeatedly been shown to be in good agreement with those measured in the field (Mayer et al., 2011; van Dijk et al., 2002; Ludwig et al., 2001). Consequently, soil biogenic NO fluxes for Tohsun Oasis were calculated every 30 min from land-use specific net potential NO fluxes (see sec. 2.3.1) using land-use specific data of soil temperature (see sec. 2.3.3), gravimetric soil moisture contents (see 2.3.3), and fertilizer factors (see sec. 2.3.3). Monthly, bottom-up soil biogenic NO emissions for the entire region of Tohsun Oasis were calculated by (a) averaging temporally high-resolution data (30 min) of the three land-use specific soil biogenic net NO fluxes for each month of the growing period (April–September 2010), (b) weighing by the areal contribution of each of the three land use types (1117, 80, and 150 km² for desert, grape, and cotton soils; see sect. 2.3.2), and (c) summing up for each month of 2010.

The soil temperature is usually the dominating factor of the uncertainties of NO fluxes because of the exponential dependence of the NO flux on soil temperature (typically expressed as the increase of the NO flux for a 10°C increase in soil temperature known as a Q10, see sec. 2.3.1). The mean Q10 value is 2 for both cotton and grape soils. The total uncertainties of bottom-up NO emissions were determined from: (a) the errors of the concentration measurements of NO, which was conservatively assumed as 5% (Behrendt et al., 2014); (b) errors of the simulated soil temperatures, which were assumed to be 1.5°-2.5°C in both estimates (satellite-derived (see Fig. S4) and estimated land surface temperatures (see Fig. S7)).

The studies by Su et al. (2011) and Oswald et al. (2013) pointed out that the HONO and NO emissions have to feature similar dependencies on soil properties, and there exist a co-emission of HONO with NO from the soil; so, it could be expected that the HONO and NO emission processes follow similar parameters (Naegele and Conrad, 1990; Skopp et al., 1990, Götter and Conrad, 2000; Oswald et al., 2013).

The recent findings of Oswald et al. (2013), namely, that a large amount of gaseous nitrous acid (HONO) is concurrently emitted along with NO, have been considered for the monthly estimation of biogenic emissions of the Tohsun Oasis. They have investigated a total of 17 soil samples, which have been taken from a variety of natural and agriculturally managed soils around the globe. Fortunately, five of these samples (no. S13–S17 in Oswald et al., 2013) were cotton, jujube, and desert soils of the Taklimakan region; they have the same arid climate condition and irrigation regime as well as fertilizer application to those used for this study. The strong dependency of HONO emissions on soil water content and soil properties were determined by laboratory experiments with dynamic chamber systems (Oswald et al., 2013). Since the HONO emissions were not directly measured within the present study, the land-use specific constant scale factor — namely the ratios of HONO to NO releases for the optimum conditions to estimate the HONO emissions ($F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$) — were adapted from the study of Oswald et al. (2013). This is justified by: (a) the strong assumption that the soil from our study emits the same magnitude of HONO as the soil by Oswald et al. (2013) because they have the same soil properties and they experienced the same irrigation regimes and fertilizer applications, and (b) the soil release of HONO and NO by Oswald et al. (2013) has been measured also in the Max Planck Institute for Chemistry by a next-laboratory version of that dynamic chamber system which was used to measure the soil release of NO in the present study. Consequently, corresponding ratios for the optimum conditions of HONO and NO

emissions (i.e., $F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$) have been used to calculate monthly HONO emissions from Tohsun Oasis from the measured NO emissions. Monthly land-use-type specific contributions of HONO emissions for the Tohsun Oasis during the growing period 2010 were estimated by multiplying the corresponding NO emissions with the mean, land use type specific factors (0.8 for grape and desert soils, and 1.6 for cotton soils). These were calculated from individual values provided by Oswald et al. (2013), which are derived from the ratio for the optimum condition $F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$. To quantify the uncertainties of calculated HONO emissions, the mean relative errors for concentration measurements of 12% for HONO (Soergel et al., 2011) and 5% for NO (Behrendt et al., 2014) were adopted. Based on these estimates, we performed a conservative error propagation calculation of the additional HONO emissions (at optimum conditions), which resulted in a relative error of 10%.

In the present study, the total bottom-up biogenic emission estimates (NO and HONO) were expressed as in terms of mass of atomic Nitrogen — partly because the reported mass of emitted nitrogen compounds becomes independent from the partitioning ratio between NO and NO₂. Additionally, the anthropogenic and top-down emissions estimates are primarily derived for NO₂. In this study, the mean primary NO₂ emissions were not considered, and all NO_x emissions are being reported as the mass of Nitrogen. For that purpose soil biogenic emissions of NO and HONO (given as mass) were multiplied by the respective ratios of the corresponding molecular weights (M_N/M_{NO} , M_N/M_{HONO}).

For the comparison of biogenic bottom-up emissions ($F_{biogenic}$) with top-down emissions ($F_{satellite}$) only the data around the time of the satellite overpass around 13:00LT was considered (bottom-up results for 12:45LT (12:30-13:00) and 13:15 LT(13:00-13:30)). To estimate the effect of the diurnal cycle of the emissions, we calculated the ratio of the bottom-up emission at the satellite overpass (at 13:00 LT) and the daily average emissions.

2.4 Bottom-up anthropogenic NO_x emission estimates

Tohsun Oasis's anthropogenic NO_x emissions predominantly originate from fossil fuel combustion of the energy and traffic sectors. To quantify the amount of an emitted substance from a source like fossil fuel consumption, specific emission factors have to be applied, which are expressed as the fraction of the substance emitted from the mass or volume of the fuel. In P.R. China, emission factors for different economic sectors and fuel types are available but are quite variable during the last decade. Based on sparsely available statistical data, the fuel types consumed in Tohsun are ranking

from coal to coke, crude oil, natural gas, diesel, and gasoline. For the calculation of bottom-up anthropogenic NO_x emissions, we used those NO_x emission factors (mass of emitted NO_x per mass of fuel, weighted as NO_2) which are widely used in P.R. China (see Table S1; supplement). According to Hao et al. (2002), Zhang et al. (2009), and Shi et al. (2014) an algorithm (see eq. (S13), supplement) has been applied to calculate the emitted mass (E^N ; in kg NO_2) from emission factors K^N (in kg t^{-1}), dimensionless removal efficiencies P^N of corresponding emission reduction technology, and the particular fuel consumption F (in t). Unfortunately, data on fossil fuel consumption from the different economic sectors of Tohsun County (see sect. 2.2) are only available on an annual basis. Mean monthly data of Tohsun Oasis have been assimilated (downscaled) by multiplicative consideration of known mean monthly percentages of annual NO_2 emissions of Urumqi (140 km NNW of Tohsun). This is justified by: (a) coal is the dominating fuel type of energy consumption in both areas (Mamtimin and Meixner, 2011; Pu, 2011), (b) identical arid climate conditions (resulting in identical heating periods), and (c) only from Urumqi there are known mean monthly percentages of annual NO_2 emissions. More details are given in sect. S3.3 of the supplement. Monthly anthropogenic emission estimates expressed as in terms of mass of atomic Nitrogen because these have to be comparable the biogenic ones.

2.5. Top-down total NO_x emission estimates from satellite observations

The satellite retrieved tropospheric vertical column densities of NO_2 (VCD_{NO_2}) over the Tohsun Oasis, providing a daily measure of the atmospheric NO_2 concentration vertically integrated over the entire troposphere (during the time of overflight, around 13:00 LT). Only a few assumptions are necessary to derive related NO_2 fluxes (representing total NO_x emissions) from this data: (1) the NO_2 molecules of the tropospheric vertical column originate exclusively from NO_x emissions (anthropogenic + biogenic) from the area of the Tohsun Oasis; (2) due to the surface source, the abundance of NO_2 molecules of the tropospheric vertical column is within its lowermost part, the Atmospheric Boundary Layer; (3) the depletion of NO_x in the Atmospheric Boundary Layer is primarily due to the reaction of NO_x with the hydroxyl radical OH (leading to the formation of gaseous nitric acid, HNO_3), and (4) the chemical lifetime of the NO_x is approximately known.

2.5.1 Satellite-derived tropospheric VCD_{NO_2}

OMI satellite data of tropospheric NO_2 were chosen because of their smaller pixel size (13 x 24 km^2 in nadir) compared to data from SCIAMACHY (60x30 km^2) or GOME (320 x 40 km^2). OMI is

operated in a sun-synchronous orbit such that measurements are taken at about 13:00 local time. OMI data also provides daily global coverage (Boersma et al., 2007). For our study, we used the OMI monthly mean tropospheric NO₂ data, which is calculated on the basis of the results of daily OMI overflights (around noon) and is provided by TEMIS (Tropospheric Emission Monitoring Internet Service, European Space Agency (ESA); <http://www.temis.nl/>). The OMI monthly mean tropospheric NO₂ data product was averaged on a 0.125° x 0.125° grid and has been retrieved for cloud fractions < 20%.

It should be noted that the tropospheric VCDs derived from satellite measurements can be systematically affected by the a priori assumptions needed for the calculation of the air mass factor AMF (reflecting the satellite sensitivity for tropospheric NO₂), such as cloud fraction, pressure at cloud level, surface albedo, and trace gas profile (Boersma et al., 2007, 2011). Fortunately, the region of Tohsun County provides relatively favorable conditions for accurate calculation of tropospheric AMFs, since the desert region is typically only little affected by clouds and aerosols; also, lightning activity, due to the predominant absence of convective rains, is rather weak, if not negligible. The AMF for OMI DOMINO v2.0 has been calculated using TM4 model NO₂ profiles with a longitude-latitude resolution of 3° x 2°, a surface reflectance climatology (0.5° x 0.5°), and cloud information (Boersma et al., 2011). To test whether the assumed surface albedo is appropriate for the Tohsun Oasis, we examined the OMI surface reflectance climatology for the study area and compared it with the high-resolution MODIS surface reflectance product (0.05° x 0.05°, MOD43B). We used the MODIS albedo products from channel 3 (at 459- 479 nm) because this channel is close to the spectral window (405-465 nm) used for the OMI retrieval. According to Kleipool et al. (2008), the surface albedo difference between 470 nm (center of MODIS channel) and 440 nm (OMI surface reflectance climatology) is very small for land surfaces.

To account for any background NO₂ from upwind (desert) areas, representative VCD_{NO2} observed over the Taklimakan Desert (400 km away from the oasis, at 85.5129°E, 40.0669°N) were subtracted from the VCD_{NO2} observed over the Tohsun area.

To check the representativeness of satellite-derived NO₂ on the regional scale, we investigated the inter-annual variability of tropospheric VCD_{NO2} from 2006 to 2010. That is because a mean value of longer periods leads to significantly reduced uncertainties, and it can better demonstrate the representativeness of satellite-derived NO₂. Evidence of clear seasonal pattern in the long-term observations can reflect the true seasonal effect on tropospheric VCD_{NO2}, which is of substantial

importance with respect to the intended comparison of "bottom-up" versus "top-down". Seasonal patterns (i.e. December–February, March–May, June–August, September–November) of satellite-derived NO₂ column densities were evaluated using long-term cloud-free (cloud fraction <20%) measurements from 2006 to 2010.

5 Satellite observations reflect contributions from different emission sources. In principle, the retrieval of NO₂ emissions over a city or oases is similar. However, usually the emissions from cities are higher, and the corresponding enhancements can be better identified compared to the background. In order to establish the relationship between biogenic NO₂ and satellite-derived NO₂, it is necessary to understand their spatial patterns with respect to the locations and shapes of the potential sources.

10 Thus, four different areas (see Fig. 3) were selected to represent (1) typical agricultural areas (study area) as the biogenic source, (2) mixed land use areas (agricultural & small urban) as the biogenic and anthropogenic sources, (3) large urban areas as the anthropogenic source, and (4) desert area as the background source.

2.5.2 Monthly total NO_x emissions of Tohsun Oasis (top-down)

15 For the top-down inventory, the given molecular weight of NO₂, Avogadro's number, a lifetime of NO_x, and pixel area (m²) of NO₂ were considered. Top-down NO_x emissions from Tohsun Oasis were calculated from all VCD_{NO₂} — whose pixels cover the area of Tohsun Oasis and where each represents the particular monthly mean of 2010 — as follows: (a) from each individual VCD_{NO₂} (in NO₂ molecules cm⁻²) the representative "desert" VCD_{NO₂} value was subtracted to account for any

20 background NO₂ from upwind (desert) areas, (b) all these VCD_{NO₂} were multiplied by their respective pixel area and summed up to obtain the mean number of (vertically integrated) NO₂ molecules for each month of 2010 over Tohsun Oasis (for the area indicated in Fig. 3), (c) this value was converted to mass of NO₂ per unit area (m²) and divided by the characteristic lifetime of NO_x, τ_{NO_x} (with respect to its reaction with the hydroxyl radical OH), (d) in order to compare the top-

25 down and bottom-up emission estimates, the monthly mean top-down emissions and their daily averages were expressed in terms of mass of atomic Nitrogen.

The corresponding result represents the monthly mean total NO_x emission (i.e., from anthropogenic and biogenic sources) from the area of the Tohsun Oasis at the time of the OMI satellite overflight (and a few hours before). Here, it should be noted that meteorological information does not have to

30 be taken into account explicitly because from the satellite observations (Fig. 9), we can conclude that

most of the NO_x (about more than 90%) is destroyed before it is blown outside the considered area by wind. The characteristic lifetime of NO_x can be expressed as a short lifetime. It has been investigated by Beirle et al. (2011), for example, and can be estimated at about $\tau_{\text{NO}_2} = 4\text{h}$ for low and mid-latitudes, particularly for the dryland cities of Isfahan (32.6°N) and Riyadh (24.6°N).

5 3 Results and Discussion

3.1 Bottom-up soil biogenic and anthropogenic emissions from Tohsun Oasis

3.1.1 Laboratory-derived net potential NO fluxes

Results of the laboratory-derived net potential NO fluxes (F_{NO}) from soils of the desert and the irrigated and fertilized cotton and grape fields are shown in Fig. 4. The highest mean net potential NO flux at 25°C occurred from the cotton soils, with a maximum net potential NO flux of $57.5\text{ ng m}^{-2}\text{ s}^{-1}$, followed by grape soils ($18.9\text{ ng m}^{-2}\text{ s}^{-1}$) and desert soils ($4.1\text{ ng m}^{-2}\text{ s}^{-1}$). Common to all net potential NO fluxes from the major land use types of the Tohsun Oasis is the exponential response to soil temperature, due to strong enzymatic activities associated with microbial processes of soil NO production. During the growing period (April to September), soil temperatures of 45°C plus are easily reached in the soils of the Tohsun Oasis, particularly for the desert soils (see supplement, Fig. S1). At $T_{\text{soil}} = 50^\circ\text{C}$, the maximum net potential NO fluxes of 384 (cotton soils), 115 (grape soils), and $46\text{ ng m}^{-2}\text{ s}^{-1}$ (desert soils) are reached at an optimum gravimetric soil moisture content ($\theta_{g,\text{opt}}$) of 0.021, 0.146, and 0.0158, respectively. These $\theta_{g,\text{opt}}$ -values, particularly those of the cotton and desert soils, are much lower than those of natural and agriculturally used soils of temperate latitudes (> 0.25 , c.f. Oswald et al., 2013; Behrendt et al., 2014).

Emphasizing, significant net potential NO fluxes from desert soil only occurs if θ_g is higher than 0.01 and less than 0.03. Since the observed θ_g -value of the Tohsun desert soils is 0.0028 (see sect. 2.3.3), no significant biogenic NO emissions are expected from there. As stated in sect. 2.3.3, the chosen irrigation schedules of cotton and grape fields resulted in certain, pre-defined ranges of gravimetric soil moisture content (depending on the field capacity [FC] of the respective soils). Immediately after each irrigation event, θ_g -values of 0.514 (grape soils) and 0.586 (cotton soils) occur; according to Fig. 4, there will be no significant biogenic NO emissions at this stage. However, after 14 days (just before the next irrigation event), θ_g -values as low as 0.086 (grape soils) and 0.167 (cotton soils) are found; consequently, regarding the results in Fig. 4, maximum biogenic NO emissions from grape soils have to be expected for the end of the 14-day irrigation period ($\theta_{g,\text{opt}} = 0.146$), while at that time,

biogenic NO emissions from cotton soils will be (even at $T_{soil} = 50^{\circ}\text{C}$) less than $4.6 \text{ ng m}^{-2} \text{ s}^{-1}$ since then the θ_g value for cotton soils (0.167) is far above the corresponding optimum value ($\theta_{g,opt} = 0.021$). This means that despite the overwhelming potential of cotton soils to dominate the biogenic NO emissions of the Tohsun Oasis (see Fig. 4), their net actual contribution is almost negligible over the full 14-day irrigation cycle (see below). It should be noted that for other oases—with other irrigation cycles—the contribution to cotton soils might be much larger.

3.1.2 Land-use-type specific net NO fluxes based on soil temperature, soil moisture content, and enhancement by fertilizer application

The land-cover classification of the Tohsun Oasis has also been derived from Landsat images. Based on these results, the dominant land cover types were cotton and grapes, building/residential areas, other vegetation, and desert (see Fig. 5).

Biogenic net NO fluxes (in $\text{ng m}^{-2} \text{ s}^{-1}$, in terms of NO) from the three land-use types of the Tohsun Oasis have been calculated from laboratory derived, land-use-specific net potential NO fluxes (see above) by eqs. (2) – (5) from assimilated data sets of soil temperature, gravimetric soil moisture content, and the enhancement of biogenic net NO fluxes caused by regular fertilizer application (see sect. 2.3.3).

3D graphs of the seasonal variation (01 April 2010, DOY 90 – 30 September 2010, DOY 273) of the mean diel soil temperature (at 30 min resolution) are presented in Fig. 6 for desert, grape, and cotton soils of the Tohsun Oasis. As expected, soil temperature in desert soils exhibits the largest variation on both diel and seasonal scales, while—due to the shading by the considerably dense canopy of cotton plants—the corresponding variations of the soil temperature in cotton fields are smallest. The corresponding seasonal variations of the gravimetric soil moisture content, as well as the (dimensionless) fertilizer factors FF and $Q_{10}F$ (at 30 min resolution) for Tohsun Oasis' cotton and grape soils, are shown in Fig. S10 (supplement), clearly demonstrating regular temporal patterns due to the chosen irrigation and fertilization schedules.

The seasonal variation of the diel variation of the biogenic net NO flux from soils of land use types "grape soils" and "cotton soils" are shown in Fig. 7. Results of the biogenic net NO fluxes from desert soils are not shown. Despite very high values of soil temperature, the net NO fluxes from Tohsun Oasis' desert soils are $\ll 0.46 \text{ ng m}^{-2} \text{ s}^{-1}$ due to the extremely low gravimetric soil water content assumed for Tohsun's desert soils ($\theta_{g,desert} = 0.0028$). The highest NO emissions were

observed from grape soils (3220 ng m⁻² s⁻¹), while the highest NO emissions from cotton soils only reached 0.6 ng m⁻² s⁻¹. Considering the entire growing period, biogenic net NO fluxes from grape soils dominate, and exceed those from cotton soils by a factor of 1–2 × 10³ on average. In both soils, the seasonal and diel variations of the net NO fluxes clearly mirror those of the corresponding soil temperature. On the seasonal scale, there is striking evidence for the impact of the chosen irrigation schedules particularly on the net NO fluxes from cotton soils (through the assumed regular 2 weekly variations of the corresponding gravimetric soil moisture content). Immediately after (flooding) irrigation, soils might be waterlogged to prevent any diffusion of gases out of the soil; but even after the evaporation of the surface waters, the chosen "drying-out" curves (see supplement Fig. S9) prescribe θ_g -values of 0.514 ("grape soils") and 0.586 ("cotton soils"), which are well above the corresponding values in field capacity conditions. There, soil diffusivity and soil microbial processes are severely suppressed (c.f. Skopp et al., 1990). This is clearly reflected in the results of laboratory incubations (see Fig. 4), where the corresponding net potential NO fluxes are close to zero for $\theta_g > 0.4$. Near the end of the chosen 14-day irrigation period, θ_g -values reach 0.086 and 0.167 for grape soils and cotton soils, respectively. Then, soil diffusivity is no longer limited in the two soils, but soil microbial processes in cotton soils are still far from their maximum activity level ($\theta_{g,opt} = 0.021$), while soil microbial processes in grape soils have even passed their maximum activity level ($\theta_{g,opt} = 0.146$). This is why biogenic net NO fluxes from grape soils of the Tohsun Oasis dominate those from cotton soils. Furthermore, the impact on net NO emission by fertilizer application on 01 April (DOY 91), 27 May (DOY 147), 10 June (DOY 161), 22 July (DOY 203), and 05 August (DOY 217; Fig. S10, supplement) amplifies the already higher net NO fluxes from grape fields. As a consequence, NO emissions from cotton soils can be neglected if compared with emissions from grape soils, even though the net potential emission of cotton soils is more than three times higher than for grape soils. It should, however, be emphasized that a small change to the low optimum soil moistures of cotton soils may cause higher NO emissions than initially estimated.

3.1.3 Monthly soil biogenic emissions of NO and HONO from Tohsun Oasis (bottom-up)

Given the areal contributions of the three land use types of the Tohsun Oasis (1117, 80, and 150 km² for desert, grape, and cotton soils), the corresponding monthly bottom-up biogenic NO and HONO emissions have been calculated by (a) summing up 30 min data of related biogenic net NO fluxes (presented in the preceding section) for each month of the growing period (April–September), and (b) multiplying the results by the area of appropriate land use types. Based on the results of Oswald et al.

(2013), monthly biogenic emissions of nitrous acid (HONO) have been calculated by land-use-type specific factors applied to the monthly means of biogenic NO emissions from grape and cotton soils (see sect. 2.3.4). For comparison with anthropogenic emissions, respective numbers of monthly soil biogenic NO and HONO emissions have been multiplied by the respective ratios of corresponding molecular weights (M_N/M_{NO} , M_N/M_{HONO}) and are shown in terms of mass of N Fig. 8 (NO: green bars; NO+HONO: pink bars). Summing up the monthly data of NO emissions for the entire oasis, corresponding totals (calculation of grapes+cotton+desert) of April, May, June, July, August, and September are 13, 23, 52, 68, 66 and 3 tons, respectively (see Fig.8). Corresponding monthly bottom-up data for HONO are 10 (April), 19 (May), 42 (June), 55 (July), 53 (August) and 2.4 tons (September), respectively. It is noteworthy that the bottom-up biogenic soil emissions at the monthly scale seem to be under the primary control of the soil temperature; indeed, the seasonal variation of the soil biogenic emissions mirrors greatly that of the soil temperature (see Fig.6; Fig. S8, supplement). Particularly during July, when soil temperatures are highest, both, monthly biogenic soil NO emissions (68 t) and soil HONO emissions (55 t) are too. It is stressed, however, that the estimated HONO emissions are an upper bound to the HONO source since we used the ratio for the optimum condition ($F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$). The lower bounds can be determined when the HONO emissions source is omitted (see Fig. 8).

3.1.4 Monthly anthropogenic emissions from Tohsun Oasis (bottom-up)

Annual anthropogenic NO_x emissions (in terms of N) of the Tohsun Oasis have been determined from published information on annual consumption of different fossil fuel types and related NO_x emission factors, which are widely used in P.R. China (see sect. 2.4). The results of the Tohsun Oasis's NO_x emissions per fuel type are shown in Fig. S11 (see supplement). Like other parts of China, coal combustion is the largest contributor to NO_x emissions, and accounts for approx. 58 % (1512 tons) of the NO_x emission inventory. As the second largest contributor, coke combustion contributed about 10 %. Monthly anthropogenic emissions (given in terms of mass of N) have been calculated from Tohsun County's annual NO_x emission data, which were downscaled by appropriate mean monthly percentages (see Sect. 2.4); corresponding results are also shown in Fig. 8 (black bars). As expected, the overwhelming part of anthropogenic NO_x (180–276 t N month⁻¹) was emitted in the winter, when air temperatures (well below 0°C; see Fig. 2) necessitate substantial domestic heating (predominantly by coal), while in July (approx. +35°C) anthropogenic NO_x emissions shrunk to

approx. one-tenth of the winter value ($45 \text{ t N month}^{-1}$) which might mainly be attributed to traffic emissions.

3.1.5 Soil biogenic vs. anthropogenic emissions of Tohsun Oasis

On an annual basis (not shown), anthropogenic sources contributed 81.4 %, and biogenic sources 18.6 % (10.3 % NO, 8.3 % HONO) to Tohsun Oasis' total emissions (2174 t, in terms of N) of reactive nitrogen in 2010. However, if only the growing period (April–September) is considered, where 40 % (865 t) of Tohsun Oasis' total annual emissions occur, the anthropogenic emissions contribute about 53.2 % and biogenic sources about 46.8 % (26.0% NO, 20.8 % HONO). As already mentioned in Section 3.1.3, soil biogenic emissions at monthly scales seemed to be primarily controlled by the soil temperature. Consequently, during June, July, and August, total biogenic emissions (NO and HONO) exceeded anthropogenic emissions by factors of 1.8, 2.8, and 1.5, respectively (see Fig. 8). Therefore, biogenic soil emissions of NO and HONO during the growing period are much more important contributors to the regional NO_x budget than previously thought.

3.2 Top-down satellite-derived total NO_x emissions from Tohsun Oasis

3.2.1 Spatio-temporal variation of the tropospheric VCD_{NO_2} measured from satellite

Fig. 9 shows the seasonal means for spring, summer, autumn, and winter (from 2006 to 2010) of the tropospheric NO_2 VCD around the Tohsun Oasis. Comparing the mean distribution (2006–2010) of the different seasons, it is clearly visible that enhanced values are found over the area of Tohsun Oasis (compared to the surrounding desert) for all seasons. Even stronger enhancements of VCD_{NO_2} values are also found in other regions, which are always dominated by anthropogenic emissions, especially the growing mega-city of Urumqi (cf. Mamtimin and Meixner, 2011). To investigate these seasonal and spatial variations in more detail, time series of monthly means are calculated for four selected areas (see Fig. 3): an exclusively agriculturally used area (A: study area), an area of mixed land use (B: agricultural and urban), a large urban area (Urumqi; C), and a desert area (D). The seasonal variation of mean tropospheric VCD_{NO_2} of areas A – D is shown in Fig. 10. These data can distinctively be classified: highest VCD_{NO_2} values ($3\text{--}15 \times 10^{15} \text{ NO}_2 \text{ molecules cm}^{-2}$) over the large urban area Urumqi (C), $1\text{--}6.5 \times 10^{15} \text{ NO}_2 \text{ molecules cm}^{-2}$ over Tohsun Oasis (A) and Tohsun & Turpan area (B), and less than $1 \times 10^{15} \text{ NO}_2 \text{ molecules cm}^{-2}$ over the chosen desert area (D). From these seasonal cycles, clear indications of the relative contributions from fossil fuel combustion and soil emissions can be drawn: Over Urumqi (C), clear maxima are found during winter, indicating the

dominating contribution from fossil fuel combustion, while there are evidently clear minima during the summer months. In contrast, over the desert (D), where only low VCD_{NO_2} values prevail, small but distinctive maxima are found during summer, which might be caused by soil emissions. Here, we have to mention that the desert VCD_{NO_2} values are higher than in comparison to the NO emission of the GGTP model results (see supplement S1.9, Fig S6). This is indeed an interesting finding which can be attributed to the fact that in the desert region, a small but still substantial diurnal variation in soil moisture is present. However, in our GGTP model, we used a constant value for the soil moisture (0.0028); as a result, the diurnal cycle of soil moisture was not considered in the model calculation. It might indeed indicate that the desert soil emissions are underestimated. Alternatively, it might be partly also caused by inflow from NO_x-reach air from the surrounding regions.

Over Tohsun Oasis (A) and Tohsun & Turpan area (B), a clear maximum, however 2–3 fold lower than that over (C), is also found in every winter certainly related to fossil fuel combustion during the heating period. Unique for all seasonal cycles are secondary maxima found in over (A) and (B) during the summer months, which amount to approximately half of the winter maxima and indicate that during summer soil emissions substantially contribute to total NO_x emissions.

3.2.2 Monthly total NO_x emissions from Tohsun Oasis (top-down)

As described in sect. 2.5.2, top-down monthly total NO_x emissions (particularly from anthropogenic and biogenic sources) of Tohsun Oasis were calculated from satellite-derived, background-corrected VCD_{NO_2} over Tohsun Oasis and the characteristic lifetime of NO_x, τ_{NO_x} (with respect to its reaction with the hydroxyl radical OH). In addition, a correction for the partitioning between NO and NO₂ in the atmosphere has to be made. For that purpose, we multiply the NO₂ values by the typical ratio between NO_x and NO₂ of about 1.3 (see e.g. Seinfeld and Pandis, 2012). The results are shown in Fig. 11. Since a prescribed and constant value for τ_{NO_x} (4.h) has been applied, the seasonal course of monthly total NO_x emissions is directly proportional to that of VCD_{NO_2} over the area of the Tohsun Oasis ((A) in Fig. 10). In 2010, the highest total NO_x emissions were observed in January and December (103–93 ng m⁻² s⁻², in terms of N), and the lowest (30–33 ng m⁻² s⁻²) in May, September, and October (see Fig. 11). Between July and August, there is the already mentioned secondary maximum of total NO_x emissions (53 ng m⁻² s⁻²), approximately half of the value in January and December, and approximately twofold the values of May, September, and October.

3.3 NO_x emissions of Tohsun Oasis: bottom-up vs. top-down

Finally, we compare the satellite-derived (top-down) total NO_x emissions of the Tohsun Oasis with the bottom-up total emission estimates (anthropogenic + biogenic) for the year 2010. As mentioned before (see sec. 2.3.4), we calculated the ratio of bottom-up emissions at the satellite overpass (13:00 LT) and the daily average emissions to estimate the effect of the diurnal emissions cycle. The highest ratios are found for July and August (2.4), while it is only 1.01 for April (see Fig. S12).
Monthly means of bottom-up biogenic emissions at satellite overpass (13:00 LT) with consideration to the diurnal cycle of the bottom-up estimates from the Tohsun Oasis are also shown in Fig. 11. Bottom-up anthropogenic NO_x emissions are shown individually to emphasize the contribution of soil biogenic emissions (NO+HONO).
The seasonal course of the bottom-up total emissions (anthropogenic + biogenic; in terms of N) qualitatively exhibits nearly the identical shape as the seasonal course of the top-down total NO_2 emissions (in terms of N). Interestingly, the second maximum in summer is only found if the soil emissions are taken into account. This finding confirms that during summer soil emissions play an important (if not the dominant) role in Tohsun Oasis's total emissions. However, a well quantitative agreement between bottom-up and top-down total emissions can be observed for the months of April, May and October. For the months of March, June, July, and August, total bottom-up emissions are always higher than the top-down ones between 10–62%. This finding seems to confirm the soil's biogenic emission evidence for the tropospheric NO_x through the impact of monthly variation of soil temperature, irrigation schedules, and fertilizer application. The most important error sources of the bottom-up and top-down emission estimates are discussed below.

Top-down emission estimates:

(a) satellite retrieval: air mass factor (*AMF*) has to be calculated for the conversion of the retrieved slant column densities into the vertical column densities. Uncertainties of the *AMF* can lead to uncertainties of the derived NO_2 VCD of about 50%. Here, particular assumptions on the trace gas profile and the surface albedo have to be made. For NO_2 , vertical profiles from a global model (TM4, see. sect. 2.5.1) with a rather coarse spatial resolution are used. The derived NO_2 VCDs probably underestimate the true NO_2 VCDs because the true NO_2 profile peaks more closely to the ground than the profile used in the satellite retrieval. It should be noted that the uncertainties of the spectral retrieval are much smaller because many measurements are averaged. As a consequence, the true *AMF* is probably smaller than the one used in the OMI retrieval, and thus the VCD_{NO_2} from the operational product probably underestimates the true tropospheric VCD_{NO_2} . In contrast, the surface

albedo used in the operational product is very similar to those from other data sets (MODIS and MERIS). Here, it is interesting to note that the spatial patterns of the surface albedo and the tropospheric VCD_{NO_2} show no similarities.

5 (b) assumption of the NO_x lifetime of 4 hours: The lifetime of NO_x in the troposphere depends on season and altitude and varies from **several** hours to **several** days. Due to the lower wintery OH concentration, lifetime in winter is longer than corresponding values in summer. However, to keep the estimation of the top-down inventory simple, we used a temporally constant mean lifetime of 4 hours, **which** leads to a certain overestimation of the emissions in winter. Nevertheless, the considered lifetime within **the** study is a good approximation for the growing season, **which is the**
10 **focus of the study**. Thereby, the potential uncertainties might be neglected if one considers the uncertainties **that** may be caused by the Air Mass Factor (*AMF*).

(c) satellite overpass time period: top-down emission estimates are only valid for the time of the satellite overpass (around 13:00 LT) and a few hours before. Thus, we compared the top-down emissions to the results from the bottom-up emissions during the time of the satellite overlap (Fig.
15 11). Fortunately, the soil emissions during the satellite overpass time are strongest because of the high temperatures around noon.

Bottom-up emission estimates:

(a) soil biogenic NO: The soil temperature at a 30-minute resolution **is** calculated by using satellite-derived surface temperature and in-situ measurements. The interpolation of the satellite-derived data
20 was done by a 3rd order polynomial. From sensitivity analysis **for second and third order models (see sec. 2.3.3)**, we found that the uncertainties of the derived temperatures are up to about 6°C. **As a consequence, the interpolation of the data just by the third order polynomial fit yielded the most consistent results.** Substantial deviations of soil temperatures (from the interpolated values) between Day 115 and Day 225 might be unlikely since surface temperatures in (hyper-) arid regions (even
25 with sparse vegetation covering) are predominantly controlled by insolation only as long there is no impact of (convective) precipitation (indeed, Turpan's Meteorological Station has not reported any precipitation events during the entire growing period). **Since the dependence of the NO flux on soil temperature is exponential (see sec. 2.3.4), the calculated relative errors of NO by taking into consideration errors of soil temperature (1.5°–2.5°C) at $Q_{10}=2$ accounts for 20% so that a total**
30 **uncertainty of 25 % was assumed for the NO emission estimates.**

(b) soil biogenic HONO: Since the NO and HONO emissions have a similar dependence on soil moisture for soil properties in arid climate conditions (Oswald et al., 2013), we used the land use specific constant scale factor, namely, the ratio of HONO and NO releases for the optimum conditions to estimate the HONO emissions ($F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$). Nevertheless, the optimum soil water content (SWC_{opt}) has a strong influence on the ratio of $F_{N,opt}(HONO)$ to $F_{N,opt}(NO)$. We used this ratio for the calculation of monthly HONO emissions by scaling corresponding NO emissions. However, particularly for cotton soil, the value of the optimum gravimetric soil water content for NO (2.1 %) is slightly lower than the corresponding value for HONO (3.6 %, s. Oswald et al., 2013). Taking the relative errors of the underlying concentration measurements, and the resulting scale factor into account, a relative error of the calculated optimum HONO emissions accounts for 10%. It is difficult, however, to estimate the total uncertainty of the calculated HONO emissions, because it is not clear how representative the emissions ratios determined by Oswald et al. (2013) are for the actual emissions from Tohsun Oasis. However, we can safely assume that these HONO emissions lie between zero and the value shown in Fig. 8, which constitute emissions for optimum conditions. Thus, we estimate the total uncertainty of the HONO emissions to be about 50%. We, therefore, expect the uncertainty of total biogenic bottom-up emissions (NO+HONO) to be about 40%. Nevertheless, these uncertainties do not question the basic message of the study.

(c) anthropogenic NO_x : Furthermore, one should keep in mind that the percentage factors for temporal down-scaling of annual anthropogenic NO_x emissions of Tohsun Oasis to monthly have to be adapted from the growing mega-city of Urumqi.

Because of these uncertainties, the good agreement between top-down and bottom-up emission estimates should be treated with caution. Nevertheless, the agreement between bottom-up and top-down estimates provides support for the broader applicability of the lab-derived HONO-NO emission relationships in space and time. The combination of independent methods applied in our present study was the first attempt to prove the comparison of soil NO emissions of different scales, ranging from the size of a soil sample to the size of a satellite pixel. Nevertheless, some improvements in these methods for future work might be necessary:

(a) including the derivation of individual NO and HONO net release rates for bottom-up biogenic emissions from a series of simultaneous incubation experiments in the laboratory under well-defined conditions (full soil temperature and gravimetric soil moisture scales),

- (b) temporally high resolution in-situ measurements of top soil temperature and gravimetric soil moisture by suitable (and simple) sensors at representative sites of all considered land use types (at least during the growing period),
- (c) **and the** temporally resolved consideration of the NO_x lifetime **for top-down emission estimates**.

5 **4 Summary**

This study **focused** on the investigation and quantification of biogenic NO **and HONO** emissions from **the** agriculturally managed soils of the Tohsun Oasis (i.e. from soils of grape and cotton cultivation). Biogenic emissions of nitrous acid (HONO, concurrently emitted with NO) were also estimated using scaling factors applied to the calculated NO emissions. The following methodology was applied: Firstly, the Geoscience General Tool Package (GGTP) **was** developed to obtain the soil temperatures and classification of land use types in the oasis from Landsat satellite data. Secondly, mean diel and land use specific variations of the normalized soil temperature, gravimetric soil moisture content, and fertilizer factors were assimilated from **the** (sparsely) available data sources (of different spatial and temporal scales as well as data quality). These have been used to calculate the mean monthly land-use-specific bottom-up biogenic NO emissions from so-called net potential NO fluxes which in turn have been derived from laboratory incubation of soil samples from the three considered land use types (cotton, grape, and desert soils). Thirdly, land-use-specific factors of HONO to biogenic NO emissions from grape and cotton soils were applied to calculate the monthly biogenic bottom-up HONO emissions during the growing period. Fourthly, data **for** anthropogenic NO_x emissions (downscaled from annual to monthly values) were estimated and compared to the mean monthly soil biogenic emissions (NO+HONO). Fifthly, **total** top-down NO_x emissions from the Tohsun Oasis have been derived from satellite observations (monthly means of Vertical Column Densities of NO_2 , VCD_{NO_2}) and prescribed values of the characteristic lifetime of NO_x , τ_{NO_x} (with respect to its reaction with the hydroxyl radical OH). Finally, we compared the biogenic bottom-up emissions at **midday** (13:00 LT) to that of the top-down emissions with the consideration of the diurnal cycle of bottom-up estimates.

The importance of soil biogenic emissions to the regional NO_x budget of **the** Tohsun Oasis has been demonstrated by the comparison **of** monthly biogenic soil emissions (NO and HONO, expressed in terms of **N**) and the corresponding anthropogenic NO_x emissions (**in terms of N**). During the growing period, particularly between June and August, biogenic emissions **constitute** up to twofold of

anthropogenic emissions. From the three considered land use types of the Tohsun Oasis (desert, grape, and cotton soils), the soil biogenic emissions from grape soils (fertilized and irrigated) dominated the summertime soil biogenic emissions of the oasis; emissions from cotton soils (fertilized and irrigated) were several orders of magnitude lower (particularly because of the soil's physical nature and the chosen irrigation schedule); soil biogenic emissions from desert soils could be completely neglected. It should be noted that the contribution from cotton soils might be considerably higher for other oases. During winter, Tohsun Oasis' soils are frozen and biogenic emissions are virtually zero; thus total NO_x emissions of the Tohsun Oasis during that season are exclusively due to anthropogenic emissions. As a consequence of both anthropogenic and biogenic contributions, the seasonal (monthly) variation of total emissions is characterized by two peaks (a strong peak in winter, and a weaker, secondary peak in summer). However, the uncertainty of the total biogenic bottom-up emission estimates is estimated to be about 40%.

The monthly variation of the top-down total emissions (derived from satellite observations) reveals the identical two-peak shapes, and agrees qualitatively and truly satisfactorily to that of bottom-up emissions. Also, a good quantitative agreement between the top-down and the bottom-up estimates is found. Here it should be noted that the emissions around noon (the satellite overpass time) are up to about two-times higher than the daily averaged emissions during the growing season. Therefore, these results provide strong evidence that the biogenic emissions from soils of managed drylands (irrigated, fertilized) in the growing period exceed local anthropogenic emissions, hence contributing substantially to the local tropospheric NO_x levels. Summarizing, it is concluded that soil biogenic emissions of NO and HONO during the vegetation period could be much more important contributors to the regional NO_x budget (hence to regional photochemistry) of dryland regions than thought before.

Author contributions.

B. Mamtimin analyzed the data and performed the bottom-up estimates; B. Mamtimin and T. Behrendt carried out the field experiments; T. Behrendt performed laboratory experiments; B. Mamtimin and T. Wagner performed the top-down estimates; B. Mamtimin and M. Badawy developed the GGTP model; B. Mamtimin, F.X. Meixner and T. Wagner wrote the paper and all Authors contributed to the discussion of the paper.

Acknowledgements.

This work was funded through the German Research Foundation (DFG) project “DEQNO – Desert Encroachment in Central Asia – Quantification of soil biogenic Nitric Oxide” (DFG-MA 4798/1-1), the Max Planck Society (MPG). The authors like to thank Zhaopeng Wu for his field assistance and his substantial support before, during and after the field campaign. We acknowledge the free use of tropospheric NO₂ column data from the OMI sensor from www.temis.nl. We thank the Xinjiang Meteorological Bureau, PR China and the United States Geological Survey for their providing meteorological data and Landsat images, respectively. The authors would like to thank S. Beirle, E. Falge, R. Shaiganfar, Y. Wang and J. Lampel for useful discussions.

10 Reference

- Ashuri, F. A.: Der Austausch von Stickstoffmonoxid zwischen Boden und Atmosphäre unter besonderer Berücksichtigung des Bodenwassergehaltes, Einfluss kulturlandschaftlicher Verhältnisse auf den Umsatz eines Spurengases. Ph.D. thesis, Johannes Gutenberg University Mainz, Mainz, Germany, 1–169, 2009.
- 15 Bargsten, A., Falge, E., Pritsch, K., Huwe, B., and Meixner, F. X.: Laboratory measurements of nitric oxide release from forest soil with a thick organic layer under different understory types, *Biogeosciences*, 7, 1425–1441, doi:10.5194/bg-7-1425-2010, 2010.
- Behrendt, T., Veres, P.R., Ashuri, F., Song, G., Flanz, M., Mamtimin, B., Bruse, M., Williams, J., and Meixner, F.X.: Characterisation of NO production and consumption: new insights by an improved laboratory dynamic chamber technique. *Biogeosciences*, 11, 5463–5492, doi:10.5194/bg-11-5463-2014, 2014.
- 20 Beirle, S., Boersma, K.F., Platt, U., Lawrence, M.G., and Wagner, T.: Megacity emissions and lifetimes of nitrogen oxides probed from space. *Science* 333, 1737, 2011.
- Boersma, K.F., Eskes, H.J., Veefkind, J.P., Brinksma, E.J., R.J. van der A, M. Sneep, G.H.J. van den Oord, P.F. Levelt, P. Stammes, J.F. Gleason and Bucsela, E.J.: Near-real time retrieval of tropospheric NO₂ from OMI, *Atm. Chem. Phys.*, 2013-2128, sref:1680-7324/acp/2007-7-2103, 2007.
- 25 Boersma, K. F., Eskes, H. J., Dirksen, R. J., van der A, R. J., Veefkind, J. P., Stammes, P., Huijnen, V., Kleipool, Q. L., Sneep, M., Claas, J., Leitão, J., Richter, A., Zhou, Y., and Brunner, D.: An improved tropospheric NO₂ column retrieval algorithm for the Ozone Monitoring Instrument, *Atmos. Meas. Tech.*, 4, 1905–1928, doi:10.5194/amt-4-1905-2011, 2011.
- 30 Chameides, W. L., Fehsenfeld, F., Rodgers, M. O., Cardelino, C., Martinez, J., Parrish, D., Lonneman, W., Lawson, D. R., Rasmussen, R. A., Zimmerman, P., Greenberg, J., Middleton, P., and Wang, T.: Ozone precursor relationships in the ambient atmosphere, *J. Geophys. Res.*, 92, 6037–6055, 1992.
- 35 Chander, G. and Markham, B.: Revised Landsat-5 TM radiometric Calibration procedures and postcalibration dynamic ranges. *IEEE Transaction on Geoscience and Remote Sensing*, Vol. 41, No. 11, 2674-2677, 2003.

- Chen, S.H., Zhang, Y., Liu, J., Cui, S.S., and Shen, J.P.: Present Situation, Problems and Countermeasure of Applying Fertilizer to Cotton Xinjiang. *Xinjiang Agricultural Sciences*, Vol. 45-1, 147-150, 2008.
- 5 Chen, X.P., Cui, Z.L., Vitousek, P.M., Cassman, K.G., Matson, P.A., Bai, J.S., Meng, Q.F., Hou, P., Yue, S.C., Römheld, V., and Zhang, S.F.: Integrated soil-crop system management for food security. *PNAS*, Vol. 108-16, 6399-6404, 2011.
- Conrad, R.: Soil Microorganisms as controllers of atmospheric trace gases (H_2 , CO, CH_4 , N_2O , and NO), *Microbiol. Rev.*, 60, 609–640, 1996.
- 10 Crutzen, P. J.: Role of the tropics in atmospheric chemistry, in: *The Geophysiology of Amazonia*, edited by: Dickinson, R. E., John Wiley & Sons, New York, 107–132, 1987.
- Davidson, E. A. and Kinglerlee, W.: A global inventory of nitric oxide emissions from soils, *Nutr. Cycl. Agroecosys.*, 48, 37–50, 1997.
- 15 Delon, C., Mougou, E., Serça, D., Grippa, M., Hiernaux, P., Diawara, M., Galy-Lacaux, C., and Kergoat, L.: Modelling the effect of soil moisture and organic matter degradation on biogenic NO emissions from soils in Sahel rangeland (Mali). *Biogeosciences*, 12, 3253–3272, doi:10.5194/bg-12-3253-2015, 2015.
- 20 Denman, K.L., Brasseur, G.P., Chidthaisong, A., Ciais, P., Cox, P.M., Dickinson, R.E., Hauglustaine, D., Heinze, C., Holland, E.A., Jacob, D.J., Lohmann, U., Ramachandran, S., da Silva Dias, P.L., Wofsy, S.C., and Zhang, X.: Couplings between changes in the climate system and biogeochemistry. In S. Solomon, D. Qin, M. Manning, Z. Chen, M. Marquis, K.B. Averyt, M. Tignor & H.L. Miller (Ed.), in *Climate Change 2007: The physical science basis. contribution of working group 1 to the fourth assessment report of the Intergovernmental Panel on Climate Change* (pp. 499-588). Cambridge: Cambridge University Press, 2007.
- 25 Diallo, D., and Mariko, A.: Field capacity (FC) and permanent wilty point (PWP) of clay soils developed on Quaternary alluvium in Niger River loop (Mali). *International Journal of Engineering Research and Applications*, 3, 1085-1089, 2013.
- Fechner, A.: The release of nitric oxide from agriculturally managed soils of selected oases on the fringe of the Taklimakan desert (Xinjiang, P.R. China) - Investigation of fertilizers' impact (in German), MSc thesis, 135 pp., Institute of Geography, Johannes Gutenberg University, Mainz, Germany, 2014.
- 30 Feig, G.T., Mamtimin, B., and Meixner, F.X.: Soil Biogenic emissions for nitric oxide from a semi-arid savanna in South Africa. *Biogeosciences*, 5, 1723–1738, doi:10.5194/bg-5-1723-2008, 2008.
- Gelfand, I., Feig, G., Meixner, F. X., and Yakir, D.: Afforestation of semi-arid shrubland reduces biogenic NO emission from soil, *Soil Biol. Biochem.*, 41, 1561–1570, 2009.
- 35 Goward, S. N. and Williams, D. L.: Landsat and Earth Systems Science: Development of terrestrial monitoring, *Photogr. Eng. Remote Sens.*, vol. 63, pp. 887-900, 1997.
- Gödde, M. and Conrad, R.: Influence of soil properties on the turnover of nitric oxide and nitrous oxide by nitrification and denitrification at constant temperature and moisture, *Biology and Fertility of Soils*, 32, 120-128, 2000.
- 40 Hao, J.M., Tian, H.Z., and Lu, Y.Q.: Emission Inventories of NO_x from Commercial Energy Consumption in China, 1995 – 1998. *Environ. Sci. Technol.*, 36, 552-560, 2002.
- IPCC: *Climate Change 2001: The Scientific Basis, Contribution of Working Group I to the Third Assessment Report of the Intergovernmental Panel on Climate Change (IPCC)*, in: Chapter 4:

- Atmospheric Chemistry and Greenhouse Gases, edited by: Houghton, J. T., Ding, Y., Griggs, D. J., Noguera, M., van der Linden, P. J., and Xiaosa, D., Cambridge University Press, Cambridge, New York, 239–287, 2001.
- 5 Irish, R.: Landsat 7 Science Data Users Handbook, NASA Goddard Space Flight Cent., Greenbelt, Md. (Available at http://ftpwww.gsfc.nasa.gov/IAS/handbook/handbook_toc.html), 2003.
- Jensen, J.R.: Introductory Digital Image Processing: A Remote Sensing Perspective. 3rd Edition, Prentice-Hall, Upper Saddle River, 198-210, 337-401, 2005.
- Jin, J.X. and Ma, X.D.: Xinjiang Statistical Yearbook 2009. China Statistics Press, Beijing, 2009.
- Jin, J.X. and Ma, X.D.: Xinjiang Statistical Yearbook 2011. China Statistics Press, Beijing, 2011.
- 10 Kasibhatla, P. S., Levy, H., and Moxim, W. J.: Global NO_x, HNO₃, PAN, and NO_y Distributions from Fossil-Fuel Combustion Emissions— a Model Study, *J. Geophys. Res.-Atmos.*, 98(D4), 7165–7180, 1993.
- Kirkman, G.A., Yang, W.X., and Meixner, F.X.: Biogenic nitric oxide emissions upscaling: an approach for Zimbabwe, *Global Biogeochemical Cycles*, 15(4), 1005-1020, 2001.
- 15 Kottek, M., Grieser, J., Beck, C., Rudolf, B., and Rubel, F.: World Map of the Köppen-Geiger climate classification Updated, *Meteorologische Zeitschrift*, 15 (3), 259-263, 2006.
- Lai, R.: Potential of desertification control to sequester carbon and mitigate the greenhouse effect. *Climatic Change* 51, 35-72, 2001.
- 20 Li, Z.X., Zhu, Z.J., Yang, L.L., Yang, Z.Q., Cui, K.B., Liu, K., Liu, J., Shen, X.H., and Maihemujiang.: Study on technical Countermeasure of promoting Xinjiang Raisin into International Market. *Xinjiang Agricultural Science*, 49 (6), 129-135, 2012.
- Liang, S., Fang, H., Morisette, J. T., Chen, M., Shuey, C. J., Walthall, C. L., and Daughtry, C. S. T.: Atmospheric Correction of Landsat ETM+ Land Surface Imagery: II. Validation and Applications. *IEEE Transactions on Geoscience and Remote Sensing*, 2002.
- 25 Lu, D., Mausel, P., Brondizio, E., and Moran, E.: Assessment of atmospheric correction methods for Landsat TM data applicable to Amazon basin LBA research. *Int. j. remote sensing*, vol. 23, no. 13, 2651–2671, 2002.
- Ludwig, J., Meixner F.X., Vogel, B., and Förstner, J.: Soil-air exchange of nitric oxide: An overview of processes, environmental factors, and modeling studies. *Biogeochemistry*, 52, 225-257, 2001.
- 30 Ma, X.C.: Map of Xinjiang, Star Map Press, Beijing, 2010.
- Mamtimin, B.: Climate of arid and semi-arid regions and the possibilities of sustainable agriculture utilization in Xinjiang (China) as an example. Ph.D. thesis, Johannes Gutenberg University Mainz, Mainz, Germany, 1–206, 2005.
- Mamtimin, B. and Meixner, F. X.: Air pollution and meteorological processes in the growing dryland city of Urumqi (Xinjiang, China), *Science of the Total Environment*, 409, 1277-1290, 2011.
- 35 Mamtimin, B., Behrendt, T., Badawy, M.M., Wagner, T., Qi, Y., Wu, Z., and Meixner, F.X.: Tropospheric vertical column densities of NO₂ over managed dryland ecosystems (Xinjiang, China): MAX-DOAS measurements vs. 3-D dispersion model simulations based on laboratory-derived NO emission from soil samples. *Atmos. Chem. Phys.*, 15, 867–882, doi: 10.5194/acp-15-867-2015, 2015.
- 40

- Mao, X.Q, Xing, Y.K., Hu, T., Zeng, A., and Liu, S.Q.: An environmental-economic analysis of carbon, sulfur and nitrogen co-reduction path for China's power industry. *China Environmental Science*, 2012, 32(4): 748~756, 2012.
- 5 Markham, B. L. and Barker J. L.: Landsat MSS and TM postcalibration dynamic ranges, exoatmospheric reflectance and at-satellite temperatures, EOSAT Landsat Tech. Notes 1, pp. 3 – 8, Earth Obs. Satell. Co., Lanham, Md., 1986.
- Mayer, J. C., Bargsten, A., Rummel, U., Meixner, F. X., and Foken, T.: Distributed Modified Bowen Ratio method for surface layer fluxes of reactive and non-reactive trace gases, *Agr. Forest Meteorol.*, 151, 655–668, 2011.
- 10 Meixner, F.X. and Yang, W.X.: Biogenic emissions of nitric oxide and nitrous oxide from arid and semi-arid land. In P. D'Odorico, and A. Porporat (Ed.), *Dryland Ecohydrology*, 233-255, Springer, Dordrecht, 2006.
- Naegele, W. and Conrad, R.: Influence of soil pH on the nitrate-reducing microbial population and their potential to reduce nitrate to nitric oxide and nitrous oxide, *FEMS Microbiology Ecology*, 74, 49-58, 1990.
- 15 Oswald, R., Behrendt, T., Ermel, M., Wu, D., Su, H., Cheng, Y., Breuninger, C., Moravek, A., Mougín, E., Delon, C., Loubet, B., Pommerening-Röser, A., Sörgel, M., Pöschl, U., Hoffmann, T., Andreae, M.O., Meixner, F.X., and Trebs, I.: HONO emissions from soil bacteria as a major source of atmospheric reactive nitrogen, *Science*, 341, 1233-1235, 2013.
- 20 Otter, L. B., Yang, W. X., Scholes, M. C., and Meixner, F. X.: Nitric Oxide emissions from a southern African Savanna, *J. Geophys. Res.*, 104(D15), 18 471–18 485, 1999.
- Pu, Y.P.: *Tulufan (Turpan) Statistical Yearbook 2008*. China Statistics Press, Beijing, 2009.
- Pu, Y.P.: *Tulufan (Turpan) Statistical Yearbook 2010*. China Statistics Press, Beijing, 2011.
- 25 Schott, J. R. and Volchok, W. J.: Thematic Mapper thermal infrared calibration, *Photogramm. Eng. Remote Sens.*, 51, 1351–1357, 1985.
- Seinfeld, J. H. and Pandis, S. N.: *Atmospheric Chemistry and Physics: From Air Pollution to Climate Change*, John Wiley & Sons., Chapter 6.5, 2012.
- Shi, Y., Xia, Y.F., Lu, B.H., Liu, N., Zhang, L., Li, S.J., and Li, W.: Emission inventory and trends of NO_x for China, 2000–2020, *Journal of Zhejiang Univ-Sci A(Appl Phy & Eng)*, 15, 454-464, 2014.
- 30 Skopp, J., Jawson, M.D., and Doran, J.W.: Steady-State Aerobic Microbial Activity as a Function of Soil-Water Content, *Soil Science Society of America Journal*, 54 (6), 1619-1625, 1990.
- Soergel, M., Trebs, I., Serafimovich, A., Moravek, A., Held, A., and Zetsch, C.: *Simultaneous HONO measurements in and above a forest canopy: influence of turbulent exchange on mixing ratio differences*, *Atmos. Chem. Phys.*, 11, 841–855, 2011.
- 35 Stotzky, G., Goos, R. D., and Timonin, M. I.: Microbial changes occurring in soil as a result of storage, *Plant Soil*, 16, 1–18, 1962.
- Su, H., Cheng, Y., Oswald, R., Behrendt, T., Trebs, I., Meixner, F. X., Andreae, M. O., Cheng, P., Zhang, Y., and Pöschl, U.: Soil Nitrite as a Source of Atmospheric HONO and OH Radicals, *Science*, 333, 1616-1618, 10.1126/science.1207687, 2011.
- 40 Van Dijk, S.M., Gut, A., Kirkman, G.A., Meixner, F.X., and Andreae, M.O.: Biogenic NO emissions from forest and pasture soils: Relating laboratory studies to field measurements, *Journal of Geophysical Research*, 107 (D20), LBA25-1 – LBA25-11, 2002.
- Wan, Y.: Strategy of foreign trade office of several companies to develop raisins international market.

Baidu Wenku/Baidu Library published by the Government of the PR China.
www.wenku.baidu.com, 14.11.2012, 2012.

Weggel, O.: Xinjiang (Sinkiang), Hamburg. Germany p. 76, 1985.


5 Yang, W. X. and Meixner, F. X.: Laboratory studies on the release of nitric oxide from subtropical
grassland soils: the effect of soil temperature and moisture, in: Gaseous Nitrogen Emissions from
Grasslands, Wallingford, England, 67–70, 1997.

Yu, J., Meixner, F. X., Sun, W., Liang, Z., Chen, Y., Mamtimin, B., Wang, G., and Sun, Z.: The
biogenic nitric oxide emission from saline sodic soils in semiarid region, Northeastern China: A
laboratory study. *J. Geophys. Res.*, Vol. 113, 1-11, 2008.

10 Zhang, Q., Street, D.G., and Carmichael, G.R.: Asian emissions in 2006 for the NASA INTEX-B
mission. *Atmospheric Chemistry and Physics*, 9, 5131-5153, doi:10.5194/acp-9-5131-2009, 2009.

Zhou, X.Q.: China Electric Power Yearbook. China Power Press, Beijing, 2006.

Figures:



5 Fig.1: Satellite map of the Tohsun Oasis (Landsat ETM+, 13 August 2010; “gamma correction” was applied to enhance the contrast of this Landsat image). Green color identifies arable soils of the Tohsun Oasis, red and yellow dots represent the locations of soil sampling from grape fields and cotton fields, respectively. The blue line represents the seasonal Bai Yanggou River. The study area of the Tohsun Oasis is approx. 50 km SW of Turpan city.




Fig. 2: Climate diagram of the Tohsun Oasis. Red dots represent monthly means of air temperature, blue bars monthly means of potential evaporation for the period 1971-2005 (data source: Xinjiang Meteorological Bureau, Urumqi, P.R. China).

5






Fig. 3: Selected areas for the examination of the spatial seasonal variation of the tropospheric NO_2 VCDs: rectangles “A”, “B”, “C”, and “D” represent agricultural area (Tohsun), mixed land use area (Tohsun and Turpan city), large urban area (Urumqi) and desert area, respectively.

10



5 Fig.4: Results of laboratory incubation measurements on soil samples of the Tohsun Oasis taken in 2010: The net potential NO fluxes F_{NO} ($\text{ng m}^{-2} \text{s}^{-1}$, in terms of mass of N) from the three major land use types of the Tohsun Oasis (desert, grape, and cotton soils) are shown as functions of soil temperature and the gravimetric soil moisture content. The soil samples have been taken in 2010. Note the different scales of net potential NO fluxes and the gravimetric soil water content.



10

Fig. 5: Land-cover classification map (2010) derived from a Landsat Image (13 August 2010)





Fig. 6: Seasonal variation of the diel soil temperature (30 min resolution) for "desert soils", "grape soils" and "cotton fields" of the Tohsun Oasis for the entire growing period of 2010 (01 April (DOY 90) – 30 September (DOY 273)).



5

Fig. 7: Seasonal variation of diel net NO flux (at 30 min resolution) for "grape soils" and "cotton fields" of the Tohsun Oasis for the entire growing period of 2010 (01 April (DOY 90) – 30 September (DOY 273)). All data are given in terms of mass of N.




Fig. 8: Anthropogenic NO_x emissions vs. soil biogenic from NO and HONO emissions of the Tohsun Oasis in 2010; biogenic emissions of nitrous acid (HONO) have been estimated according to Oswald et al. (2013). All data are given in terms of mass of N.

5




Fig. 9: Seasonal 5 year-mean Tropospheric Vertical Column Densities of NO₂ (2006- 2010); the “circumference line” represents the agriculturally managed part of the Tohsun Oasis (230 km²).

10




Fig. 10: Monthly mean tropospheric NO₂ VCD during 2006 - 2010 over selected areas (unit: 10¹⁵ molec cm⁻²)




Fig. 11: Monthly mean top-down emissions (from satellite observations) are compared to bottom-up (soil biogenic & antropogenic) and antropogenic emissions (in terms of ng m⁻² s⁻¹, N). The biogenic bottom-up emissions around 13:00LT (at satellite overpass) are selected. They are systematically higher than the daily averages (see Fig. S12).

5

10