

# Retrieval of temperature profiles from CHAMP for climate monitoring: intercomparison with Envisat MIPAS and GOMOS and different atmospheric analyses

A. Gobiet<sup>1,2</sup>, G. Kirchengast<sup>1,2</sup>, G. L. Manney<sup>3,4</sup>, M. Borsche<sup>1,2</sup>, C. Retscher<sup>5</sup>, and  
G. Stiller<sup>6</sup>

<sup>1</sup>Wegener Center for Climate and Global Change, University of Graz, Austria

<sup>2</sup>Institute for Geophysics, Astrophysics, and Meteorology, University of Graz, Austria

<sup>3</sup>Jet Propulsion Laboratory, California Institute of Technology, CA, USA

<sup>4</sup>New Mexico Institute of Mining and Technology, NM, USA

<sup>5</sup>ESA/ESRIN, Frascati, Italy

<sup>6</sup>Institut für Meteorologie und Klimaforschung, Forschungszentrum Karlsruhe, Germany

Received: 13 December 2006 – Accepted: 20 February 2007 – Published: 27 February 2007

Correspondence to: A. Gobiet (andreas.gobiet@uni-graz.at)

**CHAMP temperature  
retrieval and  
validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

## Abstract

This study describes and evaluates a Global Navigation Satellite System (GNSS) radio occultation (RO) retrieval scheme particularly aimed at delivering bias-free atmospheric parameters for climate monitoring and research. The focus of the retrieval is on the sensible use of a priori information for careful high-altitude initialisation in order to maximise the usable altitude range. The RO retrieval scheme has been meanwhile applied to more than five years of data (September 2001 to November 2006) from the German CHALLENGING Minisatellite Payload for geoscientific research (CHAMP) satellite. In this study it was validated against various correlative datasets including the Michelson Interferometer for Passive Atmospheric Sounding (MIPAS) and the Global Ozone Monitoring for Occultation of Stars (GOMOS) sensors on Envisat, five different atmospheric analyses, and the operational CHAMP retrieval product from GeoForschungsZentrum (GFZ) Potsdam. In the global mean within 10 to 30 km altitude we find that the present validation observationally constrains the potential RO temperature bias to be  $<0.2$  K. Latitudinally resolved analyses show biases to be observationally constrained to  $<0.2$ – $0.5$  K up to 35 km in most cases, and up to 30 km in any case, even if severely biased (about 10 K or more) a priori information is used in the high altitude initialisation of the retrieval. No evidence is found for the 10–35 km altitude range of RO bias sources other than those potentially propagated downward from initialisation, indicating that the widely quoted RO promise of “unbiasedness and long-term stability due to intrinsic self-calibration” can indeed be realized given care in the data processing to strictly limit structural uncertainty. The results demonstrate that an adequate high-altitude initialisation technique is crucial for accurate stratospheric RO retrievals and that still common methods of initialising the involved hydrostatic integral with an upper boundary temperature or pressure value derived from meteorological analyses is prone to introduce biases from the initialisation data to the retrieved temperatures down to below 25 km. Above 30 to 35 km, GNSS RO delivers a considerable amount of observed information up to around 40 km, which is particularly interesting for numerical weather prediction

ACPD

7, 3229–3268, 2007

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

EGU

(NWP) systems, where direct assimilation of non-initialized (a priori-free) observed RO bending angles is thus the method of choice. The results underline the value of RO for climate applications.

## 1 Introduction

5 The Global Navigation Satellite System (GNSS) radio occultation (RO) technique (e.g., Kursinski et al., 1997) is an active satellite-to-satellite limb sounding concept using GNSS signals to probe the atmosphere. It provides atmospheric parameters like refractivity, geopotential height (or pressure), and temperature with high vertical resolution (0.5 to 1.5 km), high accuracy (<1 K), long-term stability, virtual all-weather capability (insensitivity to clouds), and global coverage over an altitude range from the lower troposphere to the upper stratosphere showing best performance in the upper troposphere-lower stratosphere region (5 to 35 km) (e.g., Steiner and Kirchengast, 2005). A key asset of the RO technique for climate applications is its traceability to the most reliable and accurate calibration standard available, the S.I. (Système International d'Unités) definition of the second (Leroy et al., 2006), which enables long-term stability without need for instrument or satellite inter-calibration, usually termed "self-calibration" property of RO.

Owing to these characteristics the RO technique is a unique new data source for atmospheric and climate sciences. Particularly the high accuracy in so far data-sparse regions (e.g., over remote oceanic areas and in the polar regions) opens new possibilities for the evaluation and advancement of analyses and forecasts of numerical weather prediction (NWP) systems (e.g., Gobiet et al., 2005; Healy et al., 2005; Borsche et al., 2007; Healy and Thépaut, 2006) and for stratospheric process studies (e.g., Alfred et al., 2006). In addition, its "self-calibrating" nature makes it ideal for providing benchmark datasets for the validation of other remote sensing systems

### CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

(Schroeder et al., 2003; Wang et al., 2004; 2005; Steiner et al. 2007<sup>1</sup>) the evaluation and advancement of climate models (Goody et al., 1998; Leroy et al., 2006) and for climate monitoring in general (Foelsche et al., 2005, 2006).

Evaluation studies showed that RO temperatures are generally derived with an accuracy of better than 1 K (e.g., Hajj et al., 2002; Wickert et al., 2004; Steiner et al., 2004) though it has also been found that RO retrieval results of major processing centres show, compared to other remote sensing instruments, radiosondes, and amongst themselves, biases exceeding 1 K above 25 km (e.g., Wang et al., 2004; Wickert et al., 2004; von Engel, 2006) which is mainly due to the methodology of integrating a priori information in the high-altitude initialisation of the retrieval process as will be discussed in this study. Biases induced by downward propagated a priori information are a particular concern for climate applications like, e.g., long-term trend studies, since a priori data (often meteorological analyses) are on one hand particularly prone to model errors due to sparse observational data at high altitudes, and on the other hand they are far from long-term stable due to frequent model, observational data, and data assimilation system changes and improvements. Systematic changes in the a priori information could therefore severely degrade the basic self-calibrating nature of RO measurements by introducing artificial trends down into the lower stratosphere below 30 to 35 km. It is thus of high importance to maximise the altitude range of unbiased RO data upwards by as adequate data processing as possible (Gobiet and Kirchengast, 2004; Steiner and Kirchengast, 2005).

This study proceeds as follows: In Sect. (2) the developed operational RO retrieval scheme for data from the German CHALLENGING Minisatellite Payload for geoscientific research (CHAMP) satellite, with particular focus on the requirements of climate monitoring and bias minimisation at high altitudes, is described. The subsequent validation of the performance of this retrieval scheme in Sects. (3) and (4) is based on a broad

<sup>1</sup>Steiner, A. K., Kirchengast, G., Borsche, M., and Schoengassner, T.: A multi-year comparison of lower stratospheric temperatures from CHAMP radio occultation data with MSU/AMSU records, submitted, J. Geophys. Res., 2007.

**CHAMP temperature retrieval and validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

range of correlative data sources including Envisat limb sounding instruments, various NWP analyses, and a different RO retrieval scheme. This provides a reliable basis for the summary and conclusions in Sect. (5), where the biases (upper bounds) are summarised based on the intercomparison results and the conclusions are drawn.

## 2 Retrieval of RO temperature profiles

The presented retrieval scheme (CHAMPCLIM Retrieval, CCR) aims at optimal exploitation of RO data for climate research with a particular focus on avoidance of systematic errors and eventual drifts by minimising the influence of a priori information used for initializing the retrieval at high altitudes (upper stratosphere upwards) as a potential source of temporarily inhomogeneous biases. A related aim is to minimise the amount of background information entering the retrieval process and to make the influence of the background information traceable. Based on these measures, CCR aims to extend the altitude range of reliable, accurate retrieval results (currently up to about 25 km; see Sect. (4); Wang et al. (2004); Wickert et al. (2004); von Engel, 2006) towards the upper stratosphere (up to about 35 km). The development of the algorithmic basis and careful performance assessment via end-to-end simulation studies by Gobiet and Kirchengast (2004) and Steiner and Kirchengast (2005) have demonstrated that this improvement potential exists.

The described CCR scheme is currently applied to data from the first satellite providing RO measurements on a longer term, CHAMP (Wickert et al., 2001, 2004), and is the basis for the first RO-based multi-year temperature climatology, which has been developed in the framework of the CHAMPCLIM project (Foelsche et al., 2005, 2006), a cooperation of the Wegener Center, University of Graz, Austria and the Geo-ForschungsZentrum (GFZ) Potsdam, Germany.

### CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

## 2.1 Basic RO retrieval

The basic CCR scheme developed and applied here is a so-called dry air retrieval scheme. It is briefly summarized here; a detailed treatment of basic RO retrieval techniques is given in a review-type manner by Kursinski et al. (1997) and Hajj et al. (2002).

5 The primary observables of RO measurements are phase delays of GNSS signals, i.e., the consequences of deceleration of electromagnetic wave's phase velocities by the atmosphere. Doppler shifts and subsequently the total bending angle ( $\alpha$ ) and impact parameter ( $a$ ) of an occultation ray are deduced from phase delays involving transmitter and receiver orbit data using geometric optics and local spherical symmetry assumptions. Using GNSS signals from the Global Positioning System (GPS), two different  
10 carrier frequencies are available, which allow to remove large parts of the dispersive ionospheric contribution to the signal by linear combination of bending angles of both frequencies (Vorob'ev and Krasil'nikova, 1994). The refractive index of the neutral atmosphere ( $n$ ) can then be derived via the inverse Abel transform (Fjeldbo et al., 1971),

$$15 \quad n(a) = \exp \left[ \frac{1}{\pi} \int_a^{\infty} \frac{\alpha(a')}{\sqrt{a'^2 - a^2}} da' \right], \quad (1)$$

from which refractivity as a function of height,  $N(z)$ , is obtained via the relation  $N(a) = 10^6(n(a)-1)$  and  $z(a) = a/n(a) - R_C$ .  $R_C$  is the radius of curvature of the Earth along the occultation plane (approximately Earth's radius; Syndergaard, 1998). Refractivity is related to atmospheric pressure ( $p$ ), temperature ( $T$ ), and the partial pressure of water vapour ( $p_w$ ) via  
20

$$N = k_1 \frac{p}{T} + k_2 \frac{p_w}{T^2}, \quad (2)$$

where  $k_1$  and  $k_2$  are constants ( $k_1 = 77.60 \text{ K/hPa}$ ,  $k_2 = 3.73 \cdot 10^5 \text{ K}^2/\text{hPa}$ ; e.g., Bevis et al., 1994).

### CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

Using the refractivity equation (Eq. 2), the hydrostatic equation, the equation of state, and the gravity formula, atmospheric parameters can be derived. For example, dry pressure  $p_d(z)$  (which equals the total air pressure  $p(z)$  if humidity can be neglected, i.e., above the middle troposphere) is obtained via hydrostatic integration,

$$p_d(z) = \frac{M_d}{k_1 R} \int_z^{\infty} g(z') N(z') dz', \quad (3)$$

where  $R$  is the universal gas constant ( $8.3145 \cdot 10^3 \text{ JK}^{-1} \text{ kg}^{-1}$ ),  $M_d$  is the molar mass of dry air ( $28.964 \text{ kg kmol}^{-1}$ ), and  $g(z')$  is the acceleration of gravity. Dry temperature (which, similarly to dry pressure, absorbs the effect of water vapour) is then obtained as

$$T_d(z) = k_1 \frac{p_d(z)}{N(z)}. \quad (4)$$

We note that if the air is sufficiently moist so that humidity cannot be neglected, as is typically the case in the lower and middle troposphere, then temperature and water vapour can only be retrieved separately if a priori information on at least one of the two parameters is available (e.g., Kursinski et al., 1997; Healy and Eyre, 2000). This moist air retrieval, a part of the CCR follow-on retrieval scheme at the Wegener Center, is not further treated here since the lower and middle troposphere is below our analysis domain limited to above 10 km in this study. We thus exclusively regard dry temperature as defined above, assuming the contribution of the water vapour to be negligible, which is generally a very good assumption above 10 km (e.g., Gobiet, 2005).

## 2.2 High-altitude initialisation and statistical optimisation

The integrate formulae, Eqs. (1) and (3), are crucial links in the RO retrieval chain. Equation (1) indicates that the inversion of bending angles leads to downward propagation of high altitude errors. Due to the localized kernel  $(a'^2 - a^2)^{-1/2}$  of the inverse

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

---

**CHAMP temperature  
retrieval and  
validation**A. Gobiet et al.

---

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[⏪](#)[⏩](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

Abel transform, this vertical correlation is limited in  $N(z)$  but further and stronger error propagation occurs in the hydrostatic integration, Eq. (3). A detailed theoretical analysis of this error propagation has been performed by Rieder and Kirchengast (2001). It is thus vital to use adequate bending angles also at altitudes above any height of interest. On the other hand, since atmospheric density decreases exponentially with height and residuals from the ionospheric correction significantly disturb the RO signal above about 45 km, the high-altitude signal-to-noise ratio (SNR) is low. Without careful initialization of the two integrals, errors in temperature profiles may propagate down to 20 km or even below (Gobiet and Kirchengast, 2004), which are altitudes generally considered to be “optimal” for RO retrieval performance, however.

To cope with this problem, usually both integrals (1) and (3) are initialized by some kind of a priori information about the atmosphere at high altitudes. The standard approach, inherited from planetary occultation (e.g., Fjeldbo et al., 1971), is to independently initialize both integrals. The Abel transform is often initialized by extrapolating the bending angle profile exponentially (e.g., Kursinski et al., 1997). Since the resulting refractivity profile usually lacks quality at high altitudes, the hydrostatic integral is again initialized at some fixed altitude between 30 and 50 km with temperature (or pressure) upper boundary “guess” value (e.g., Kursinski et al., 1997; Hajj et al., 2004; Wickert et al., 2004), usually derived from a meteorological analysis. A modification of the extrapolation approach is so-called statistical optimisation (Sokolovskiy and Hunt, 1996), which combines a bending angle profile derived from climatology or a meteorological analysis with the observed bending angles taking into account the altitude dependant error characteristics of both profiles yielding an optimal combination in a least-squares error sense (see Gobiet and Kirchengast (2004) for details). Usually, the hydrostatic integral is subsequently still initialized as described above.

Steiner and Kirchengast (2005) have, in the context of an error analysis based on ensembles of GNSS RO profiles from end-to-end simulations, discussed the weakness of the double initialization approach and found: “Regarding the climatological use of geopotential heights and temperature this approach is problematic, since it leads to in-



5 tricate error characteristics and a priori-dependence in the stratospheric data down to about 20 km, which threatens the crucial aims of un-biasedness and a clear understanding of the degree of residual biasedness.” Gobiet and Kirchengast (2004) presented a retrieval scheme avoiding the 2nd initialisation by using full downward integration of the hydrostatic integral from 120 km in order to eliminate these problems and the related over-accentuation of a priori information in the retrieval.

10 Following these findings we use in the CCR scheme a statistical optimisation approach that introduces background information exclusively to the bending angles, yielding high-quality refractivity profiles up to high altitudes so that no “2nd initialisation” is needed to initialize the hydrostatic integral subsequently. This ingests minimal a priori information and allows clear tracing of the amount of non-observed information entering the retrieval. As will be shown below based on real data, rather than on simulated data as used by Gobiet and Kirchengast (2004), a significantly higher degree of independence from a priori information can be achieved in the critical 30 to 40 km altitude range compared to retrieval schemes applying “2nd initialization” of the hydrostatic integral. A more detailed description of the general methodology can be found in Gobiet and Kirchengast (2004), its specific application to CHAMP data is described as part of the following subsection.

### 2.3 The CHAMPCLIM retrieval

20 The CHAMPCLIM retrieval (CCR) scheme, more precisely the dry air retrieval core scheme of interest here, starts with phase delays from CHAMP provided by GFZ (“level 2 data”) and returns (dry air) profiles of refractivity, density, pressure, geopotential height, and temperature, respectively. Compared to the pre-operational retrieval scheme described in Gobiet and Kirchengast (2004) several aspects were improved for its operational application to CHAMP data and to improve the retrieval performance. Table 1 provides an overview on the main ingredients of the scheme and we briefly describe the main (improvement) aspects below; some more details are described in Gobiet (2005).

---

## CHAMP temperature retrieval and validation

A. Gobiet et al.

---

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

---

**CHAMP temperature  
retrieval and  
validation**A. Gobiet et al.

---

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[⏪](#)[⏩](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

More stable ionospheric correction could be achieved by low-pass filtering the signals before dual-frequency correction and adding the high-pass fraction of the stronger signal afterwards (Hajj et al., 2002; Hocke et al., 2003). Tests identified a 1 km-width boxcar filter applied to bending angles and impact parameters being most effective, whilst broader filters created biases above 30 km and more narrow filters were less effective in terms of retrieval efficiency (i.e., a smaller number of occultation events could be successfully processed). Additionally, the retrieval quality in terms of statistical error could be slightly improved in the 15 to 20 km altitude range.

The statistical optimisation of bending angles needs an estimation of the error characteristics of the data. Unlike several retrieval schemes that use the root-mean-square differences relative to the a priori for this purpose (which results in overemphasis of background information as soon as the background information is biased) we derive observation errors independently from the background by analysing the altitudinal variance of the ionosphere corrected bending angle profiles at high altitudes, where it predominantly contains noise and the neutral atmospheric contribution to the signal is close to negligible. The error estimation was derived from the height interval between 65 and 80 km. Though a lower boundary of 70 km would better fulfil the low-atmospheric-signal assumption, 65 km was used in case of CHAMP as compromise for the sake of higher retrieval efficiency. For more recent RO receivers with nominally higher SNR like the GNSS Receiver for Atmospheric Sounding (GRAS) on MetOp (GRAS-SAG, 1998; Loiselet et al., 2000) or the Integrated GPS Occultation Receivers (IGOR) on the COSMIC constellation (Rocken et al. 2000; Wu et al. 2005), it might be meaningful to raise the lower boundary.

As background information we used what we consider to be the best dataset available, the operational analyses of the European Centre for Medium-Range Weather Forecasts (ECMWF, cf. Sect. 3.3.3). For each observed bending angle profile, one co-located set of atmospheric parameters was extracted from the temporally closest of the six-hourly ECMWF analysis fields, converted into a refractivity (Eq. 2) profile, expanded upwards from ~60 km to 120 km using refractivity derived from the MSISE-90 climatol-

---

**CHAMP temperature  
retrieval and  
validation**A. Gobiet et al.

---

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[⏪](#)[⏩](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

ogy (Hedin, 1991), and transformed into a bending angle profile using the forward Abel transform the inverse of Eq. (1); e.g. Rieder and Kirchengast, 2001; their Eq. (14). The error of the background profile was assumed to amount to 15% of the background bending angle value at each altitude, which is in reasonable agreement with the climatological variability in the upper stratosphere and lower mesosphere and ensures that the background profile dominates only at the uppermost part of the profile, where the SNR of the observation is small (cf. also Healy, 2001; Rieder and Kirchengast, 2001). Since the bending angle in the atmosphere increases exponentially with decreasing height, the a priori error estimate grows very fast with decreasing height and is not very sensitive to the actual percentage value (values of 5 to 20% are commonly used and yield comparable results). The transition zone between background-dominance and observation-dominance in the optimized bending angle profile typically lies between 45 and 60 km, primarily depending on the observation error estimate for every given profile.

Statistical optimisation restricted to altitudes above 30 km was performed using the inverse covariance weighting approach (Healy, 2001; Rieder and Kirchengast, 2001), which combines the observed and background profile in a statistically optimal way regarding their error characteristics, including vertical error correlation. After application of the inverse Abel transform, a high quality refractivity profile is available, which can be directly processed via the hydrostatic integral without adding further background information. For the sake of correctness, the integral is initialised with pressure derived from MSISE-90 at 120 km, but simply starting the integration from zero produces negligible differences in the results in the domain of interest below 50 km.

Finally, a rough quality control is applied in order to remove outlier profiles featuring a relative refractivity difference greater than 10% between 5 and 35 km or a temperature difference greater than 20 K between 8 and 25 km, respectively, compared to the co-located ECMWF profile. The acceptance ranges have been deliberately chosen that large (more than an order of magnitude larger than the standard errors of any of the two datasets) to ensure that indeed only severe outliers, caused by technically corrupted

data, are rejected and that eventual biases in the reference dataset (ECMWF) are not introduced into the statistics of the RO retrieval results.

### 3 Validation methodology and correlative data

A range of suitable correlative datasets were used to validate the CCR scheme temperature product in order to derive a well-founded estimation of the retrieval performance characteristics. Though the correlative data in general feature error characteristics larger than can be expected from the RO method, the combination of these comparisons provides a well-balanced picture of the retrieval performance, particularly on upper bounds of eventual biases.

#### 3.1 Validation periods and spatial setup

Out of 20 available seasons analysed (September 2001 to August 2006; cf., e.g., Borsche et al., 2007), two representative seasons were selected to be closely validated and presented in more detail here: September, October, and November 2002 (SON 2002) and June, July, and August 2003 (JJA 2003). Figure 1 illustrates the coverage. SON 2002 is, regarding the comparison of CCR RO to correlative data, a representative typical season and JJA 2003 stands for a more “extreme” season featuring prominent deviations between the datasets. A further practical reason for selecting these periods was the limited availability of the Envisat correlative datasets (see Sect. 3.3.2) in many other seasons.

In order to be able to analyse not only seasonal, but also latitudinal effects, the two seasonal samples were further separated into latitudinal sub-samples: low latitudes ( $-30^{\circ}$  to  $+30^{\circ}$ ), mid latitudes ( $\pm 30^{\circ}$  to  $\pm 60^{\circ}$ ), and high latitudes ( $\pm 60^{\circ}$  to  $\pm 90^{\circ}$ ) for the depiction of error statistics profiles, and 18 ten-degree latitude samples (bounded by black lines in Fig. 1) for the depiction of zonal-mean latitude versus altitude plots of the bias (Sect. 4). The latitudinal separation is particularly important since the quality

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

of both the CCR and the correlative data may depend on latitude. Additionally, bias estimates including significance level indication are summarised in a more compact manner (Sect. 5) by averaging over 10 km altitude intervals (10 to 20 km, 20 to 30 km, 30 to 40 km). The uppermost interval is of particular interest for judging the influence of a priori information on the retrieval and the lower and middle intervals mark the best performance RO retrieval range.

The spatial coverage of CHAMP occultation events is denser near the poles than at low latitudes due to the high inclination (87 degree) of the CHAMP orbit. This affects particularly the density of coincidences with profiles from a dataset with qualitatively similar coverage characteristics such as MIPAS, as clearly visible in Fig. 1.

### 3.2 Validation methodology

The validation methodology is based on simple statistics of differences between CCR RO dry temperature profiles and temperature profiles from the other data sources. Since no data below 10 km are compared, the water-vapour effect in dry temperature can be neglected for our purposes (e.g., Gobiet, 2005) and dry temperatures can be regarded as actual temperatures (small potential differences remaining in the tropical latitudes up to about 12 km are easily diagnosed). For each CCR profile, a co-located correlative profile is searched (the definition of co-location is given in the following subsections) and, if found, vertically linearly interpolated to the CCR standard altitude levels (regular 200 m level spacing). The correlative profile is then subtracted from the CCR profile and the difference profile  $\Delta x$  is added to the validation ensemble from which error statistics are derived. The ensemble mean profile represents the systematic difference (bias profile  $\mathbf{b}$ ) and the subtraction of  $\mathbf{b}$  from each difference profile gives a centred (unbiased) ensemble of difference profiles from which the ensemble variance profile (mean squared centred difference at each altitude level) and its square root, the standard deviation profile  $\mathbf{s}$ , are estimated. While  $\mathbf{s}$  characterises the statistical variability of the differences, the uncertainty of the bias  $\mathbf{b}$  is characterised at any given

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

altitude level by the standard deviation profile of the mean,  $\mathbf{s}/N^{1/2}$ ,  $N$  being the ensemble size. All comparisons in this study are based on  $\mathbf{b}$  and  $\mathbf{s}$ , separating the systematic ( $\mathbf{b}$ ) from the random ( $\mathbf{s}$ ) part of the more frequently used aggregate root-mean-square error. Furthermore,  $2 \times \mathbf{s}/N^{1/2}$  is used as a  $2\sigma$ -measure of statistical significance (95% level) of the estimated biases (Sect. 5).

Since we are not only interested in quantifying the discrepancies between different observational and modelled data but also in their relation to the actual state of the atmosphere, including effects of inadequate vertical resolution, we did deliberately not match the resolutions, e.g., by adjusting the averaging kernels as described by Rodgers and Connor (2003). Resolution-induced differences were found to point to interesting atmospheric structures so we considered it counterproductive to smooth them out in the context of this study. Regions featuring differences primarily due to lacking resolution of correlative data are readily diagnosed by comparing the full-resolution bias profiles with 10 km-mean biases.

We note that the validation and error analysis presented here is not intended to quantify the climatological error of gridded RO climatologic datasets derived from CHAMP (see Foelsche et al. 2007<sup>2</sup> for this purpose), which would additionally include sampling errors caused by the non-uniform and limited spatial and temporal measurement profile distribution and resolution effects. Here, we rather restrict the analysis to combined observational error of co-located temperature profiles, i.e., we minimise sampling errors. This allows direct insight into the RO retrieval accuracy, together with the accuracy of the correlative datasets, and, based on the diversity and various known strength and weaknesses of the different datasets allows isolation of valuable information on the individual dataset quality.

<sup>2</sup>Foelsche, U., Borsche, M., Steiner, A. K., Gobiet, A., Pirscher, B., Kirchengast, G., Wickert, and J., Schmidt, T.: Observing Upper Troposphere–Lower Stratosphere Climate with Radio Occultation Data from the CHAMP Satellite, submitted, *Clim. Dynamics*, 2007.

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

### 3.3 Correlative datasets

#### 3.3.1 Operational GFZ retrieval

Temperature profiles from the operational CHAMP-GFZ retrieval (version 5; e.g., Wickert et al., 2004) are used for a focused analysis of the effects of different elements in RO retrieval strategies. This yields no comprehensive information on the overall RO retrieval performance but rather estimates structural uncertainty similar to von Engel (2006). Since in the altitude region regarded here the main difference between the GFZ and the CCR scheme is the treatment of background information, this effect can be clearly analysed. The GFZ retrieval employs statistical optimisation of bending angle profiles using the MSISE-90 climatology (Hedin et al., 1991) as a priori data and adds further a priori information derived from operational ECMWF analyses by initializing the hydrostatic integral at 43 km (i.e., the systematic and random error compared to ECMWF at 43 km is zero). This results, similar to other double-initialisation schemes described in literature (e.g., Hajj et al., 2004), in a mixture of three different sources of information (one observational and two a priori) leading to overemphasis of a priori information and physically inconsistent refractivity and temperature profiles near the “2nd initialisation” upper boundary. Evaluation studies showed that RO temperatures in general and CHAMP-GFZ temperatures in particular are derived with a statistical error of less than 1 K between 10 and 30 km (Hajj et al., 2002; Wickert et al., 2004) though it has also been shown that GFZ temperatures above 25 km are cold biased by 1–2 K (Wang et al., 2004; Wickert et al., 2004).

The vertical resolution of GFZ profiles can be regarded to be similar to CCR profiles (~1 km), neglecting minor differences in the retrieval process. Co-location of CCR and GFZ profiles is trivially achieved by selecting the same CHAMP measurement. Since CCR uses quality controlled phase delay data from GFZ (i.e., only data that could be processed with the operational GFZ retrieval as well), the entire set of CCR temperature profiles could be used and a total of 26 605 difference profiles entered the error statistics, 12 950 in SON 2002 and 13 655 in JJA 2003, 10 926 at high latitudes,

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



9 299 at mid-latitudes, and 6 344 at low latitudes.

### 3.3.2 Envisat instruments MIPAS and GOMOS

Comparison to other remote sensing instruments is of particular importance in order to independently evaluate CCR results. We present comparisons with two instruments onboard ESA's (European Space Agency) Envisat satellite, the Michelson Interferometer for Passive Atmospheric Sounding (MIPAS) (Fischer and Oelhaf, 1996; European Space Agency, 2000) and the Global Ozone Monitoring by Occultation of Stars (GOMOS) (Bertaux et al., 1991; Kyrölä et al., 2004) instrument.

MIPAS is a Fourier transform spectrometer for the measurement of gaseous mid-infrared emission spectra at the Earth's limb. It is dedicated to distribute profiles of atmospheric constituents from 6 km to 70 km altitude with a vertical resolution of about 3 km between 6 and 42 km and a horizontal resolution between 300 km and 500 km along track. Since thermal emissions in the infrared are sensitive to temperature, MIPAS is also capable to measure temperature. The temperature profiles used for this study were retrieved by the Institut für Meteorologie und Klimaforschung (IMK) in Karlsruhe (version V3O\_T\_8). Though ECMWF analyses are used as a priori in the retrieval process, MIPAS is not biased against ECMWF, since the latter data are used as smoothing constraint rather than for Bayesian combination. For the focus of this study, inspection of biases, MIPAS can be regarded as entirely independent from CCR RO and ECMWF. More details about the MIPAS temperature retrieval are described in von Clarmann et al. (2003a,b).

For individual profiles, MIPAS temperatures have been reported to be retrieved with a total error of 0.5 to 1.5 K (von Clarmann et al., 2003a) and comparisons to other instruments confirmed these figures in principle (with few exceptions) (Wang et al., 2004, 2005). It has also been demonstrated that the difference in vertical resolution to RO measurements significantly influences the comparison with RO profiles only in the tropopause region (Wang et al., 2004).

Due to MIPAS' sensitivity to clouds, the number of available measurements per

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



---

**CHAMP temperature  
retrieval and  
validation**A. Gobiet et al.

---

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[⏪](#)[⏩](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

day varies from several tens to hundreds. When this study was performed, 68 days of MIPAS data from the most recent retrieval version were available in the two evaluation periods (SON 2002: 04/09/2002, 05/09/2002, 12–14/09/2002, 1–28/09/2002, 17/10/2002, 25/10/2002, 26/10/2002, 4/11/2002, 5/11/2002, 7–9/11/2002, 11–13/11/2002, 15/11/2002, 22/11/2002, 23/11/2002, 29/11/2002, 30/11/2002; JJA 2003: 05-09/06/2003, 12/06/2003, 13/06/2003, 24/06/2003, 25/06/2003, 29/06/2003, 30/06/2003, 01/07/2003, 05/07/2003, 06/07/2003, 14/07/2003, 16–18/07/2003, 26–31/07/2003, 05/08/2003, 06/08/2003, 16–18/08/2003, 26–28/08/2003, 30/08/2003, 31/08/2003), all together yielding 24 187 profiles. As co-location criteria a maximum horizontal distance of 300 km and a maximum time difference of 3 h were allowed. 622 CHAMP profiles met these criteria, most of them at high latitudes (441), but still a statistically reasonable number at mid (122) and low (59) latitudes (cf. Fig. 1). In cases where more than one MIPAS profile met the co-location criteria, the average of the co-located profiles was used for comparison with CCR RO.

GOMOS, a further Envisat instrument for atmospheric sounding, exploits stellar occultation (i.e., the information carried by a star's light when it is modified during its travel through the Earth's atmosphere as the star sets behind the horizon) with the major objective of monitoring ozone and ozone depleting trace gases in the altitude range between 15 km and 90 km. In addition, GOMOS data can be addressed to retrieve bending angle, density, pressure, and temperature profiles. Results from a temperature retrieval based on bending angle profiles extracted from GOMOS star tracker data are used for comparison with CCR RO. The retrieval chain roughly follows the CCR scheme explained in Sect. (2.3). Details are discussed in Retscher et al. (2004, 2006). The vertical resolution of GOMOS temperature profiles is about 1.7 km corresponding to a sampling rate of 2 Hz.

Only a very limited amount of GOMOS data was available for this study, resulting in 49 co-located temperature profiles (same co-location criteria as for MIPAS), most of them at high latitudes. In order to retain reliable statistics, no further separation into latitudinal sub-ensembles was performed.

### 3.3.3 NWP analyses

Analyses of numerical weather prediction (NWP) centres combine short-range model forecasts with various sources of observational data. In the stratosphere they are predominantly constrained by radiosondes (up to 25–30 km) as well as low vertical resolution satellite-derived radiances like those of the Advanced Microwave Sounding Unit A (AMSU-A). Their reliability is best in the troposphere and lower stratosphere and decreases in the middle and upper stratosphere due to decreasing availability and quality of observations, particularly over polar regions and the oceans. We collected data from five major analysis systems for comparison with CCR RO temperature profiles.

The first ones, ECMWF operational analyses are also used in CCR as a priori information above 30 km (cf. Sect. 2.3.) and can therefore not be regarded as an entirely independent evaluation dataset. Their importance here as correlative dataset is for assessment of the level of (in)dependence of CCR RO temperatures from its ECMWF constraint at high altitudes (above 25 km) and for use as independent evaluation dataset below about 25 km. The analysis version operational during our evaluation periods used 60 vertical levels up to 0.1 hPa, spectral representation in the horizontal with triangular truncation at wave number 511 (T511, corresponds to ~40 km grid spacing) for upper air fields and horizontal derivatives, and a Gaussian grid in the horizontal for dynamic tendencies and diabatic physical parameterisations (ECMWF, 2004). The operational forecasts are started twice a day from the initial state (i.e., the previous analysis), produced via four-dimensional data assimilation. Analyses are produced for 00:00, 06:00, 12:00, and 18:00 UTC every day.

For this comparison, ECMWF analyses have been extracted from the ECMWF data archive on model levels at full vertical resolution (>1.5 km in the tropopause region, i.e., somewhat coarser than CCR RO) and reduced horizontal resolution (T42, corresponds to ~300 km, which is roughly the horizontal resolution of RO measurements). Vertical profiles of temperature bi-linearly interpolated to the mean tangent point of the occultation event were derived from the nearest analysis time layer, which ensured that

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

the maximum time difference between the CCR and the ECMWF profile corresponds to the co-location criteria for MIPAS and GOMOS, and linearly interpolated to the CCR standard altitude levels. Since ECMWF analyses are available for the entire evaluation periods, the entire set of CCR profiles (26 605) could be used for evaluation, as for the comparison to GFZ RO retrievals.

Further analyses used for comparison were provided in the framework of the Stratospheric Processes And their Role in Climate (SPARC) project and are particularly important to estimate the uncertainty of recent analyses in different altitudes and at different latitudes in order to allow a proper interpretation of the comparison results. These analysis data are interpolated linearly in time, bi-linearly in the horizontal to the CHAMP observation locations, and linearly to the CCR standard altitude levels. Descriptions of each of the assimilation/analysis systems are given by Manney et al. (2005a).

GEOS-4 (Goddard Earth Observing System, Version 4.03; Bloom et al., 2005) analyses from NASA's Global Modeling and Assimilation Office are provided on a  $1^\circ \times 1.25^\circ$  latitude  $\times$  longitude grid on 55 model levels from the surface to 0.01 hPa. The fields are 6-h averages valid at 00:00, 06:00, 12:00, and 18:00 UTC. Analyses from the UK Met Office (referred to as MetO analyses; Swinbank et al., 2002) are provided by the British Atmospheric Data Centre (BADC) once daily at 12:00 UTC. They are on a  $2.5^\circ \times 3.75^\circ$  latitude  $\times$  longitude grid, on 6 levels per decade in pressure ("UARS pressure levels", 40 levels in total) from 1000 to 0.1 hPa. NCEP/CPC (National Centers for Environmental Prediction/Climate Prediction Center) analyses are available once daily at 12:00 UTC, provided on a  $65 \times 65$  point polar stereographic grid for each hemisphere. The fields used here have been interpolated bi-linearly to a  $2.5^\circ \times 5^\circ$  latitude  $\times$  longitude grid prior to the interpolation to the CHAMP locations. They are available on 18 pressure levels from 1000 to 0.4 hPa. The NCEP/NCAR (NCEP, National Center for Atmospheric Research) 50 year reanalysis (NCEP Rean) data are daily average fields valid at 12:00 UTC, on a  $2.5^\circ \times 2.5^\circ$  latitude  $\times$  longitude grid. There are 17 pressure levels from 1000 to 10 hPa. NCEP Rean data are considered unsuitable for detailed stratospheric studies, since the temperatures are severely biased according to Manney

**CHAMP temperature  
retrieval and  
validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

## 4 Results and discussion

The results of the comparisons are presented as latitude versus altitude slices of zonal-mean bias as well as in form of bias  $\pm$  standard deviation profiles separated into global domain and low, mid, and high latitudes, respectively. For GOMOS, due to the limited co-location ensemble, only global mean difference statistics are presented and discussed. For the analyses other than ECMWF, the results are shown and discussed as latitude versus altitude slices only. The displayed altitude range is 10 to 40 km, of which 10 to 30 km is generally regarded as the reliable (best performance) range for RO measurements, and 30 to 40 km marks the potentially a priori influenced, but still measurement dominated range. The maximum usable altitude of properly processed stand-alone RO products can be expected to be found within 30 to 40 km. Soon above 40 km a RO profile typically and quickly becomes a priori dominated (details depending on the high altitude initialization strategy used; cf. Gobiet and Kirchengast, 2004). White areas in the plots correspond to missing correlative data. Statistical significance is not displayed, but generally any bias larger than  $\sim 0.2$  K can be regarded as statistically significant on the  $2\sigma$ -level ( $\sim 95\%$  significance). A more condensed view on the results including significance indication follows in Sect. (5).

### 4.1 Comparison to operational GFZ CHAMP temperatures

Figure 2 illustrates the intercomparison results between CCR and GFZ retrievals from CHAMP. Due to the decreasing accuracy above 30 km, operational CHAMP temperature profiles from GFZ are delivered for altitudes up to 35 km only. Generally, as Fig. 2 shows, the differences to CCR temperatures are small below about 26 km ( $< 0.5$  K) with standard deviations of 1 to 2 K. At higher altitudes CCR is increasingly warmer than GFZ, reaching about 3 K difference at 35 km. Since the major difference between

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

the CCR and the GFZ retrieval scheme is the treatment of a priori information (see Sect. 3.3.1) these deviations can be clearly attributed to the sensitivity of the RO retrieval to the high-altitude initialisation. As will be shown in Sect. (4.4) later, the source of this bias is a general cold bias (except southern JJA high latitudes) in ECMWF temperatures above 30 km, to which the GFZ retrieval is stronger attached than the CCR one. A similar bias of the GFZ operational temperatures has been found by Wang et al. (2004) relative to MIPAS (1 to 1.5 K at 30 km), by Wickert et al. (2004) relative to radiosondes (about 2 K at 35 km), and by von Engel (2006) relative to UCAR (University Cooperation for Atmospheric Research) RO retrievals (about 2 K at 31 to 33 km). The important conclusion of this comparison is that the way of introducing a priori data into the RO retrieval can significantly influence the retrieved temperature profile result down to about 26 km even in well tested operational retrieval schemes, in line with studies by, e.g., Steiner et al. (1999), Marquardt et al. (2003), Hajj et al. (2004), and Steiner and Kirchengast (2005). Additionally, a bias reaching to about 20 km is visible at southern high latitudes of JJA 2003, which will be discussed in Sect. (4.4).

## 4.2 Comparison to Envisat MIPAS temperatures

Figure 3 illustrates the intercomparison results between CCR CHAMP and MIPAS, which exhibits a different picture than Fig. 2. In the global mean, the bias stays below 0.5 to 1 K in the entire altitude range up to 40 km, except for a deviation caused by a severe bias in the JJA 2003 southern high latitudes (bottom, right panel; also see Sect. 4.4). In the latitudinal comparison the bias stays at below 2 K (standard deviation about 2.5 K) except for a peak in JJA 2003 at low latitudes near 29 km (bottom, middle-left panel) which can be attributed to the lower MIPAS vertical resolution and also the rather small ensemble size of less than 30 profile pairs, and the JJA high latitude bias mentioned before. There is no sign of a general CCR warm bias above 30 km like in the comparison to GFZ. Since MIPAS can be regarded as independent from ECMWF in a bias-sense, this indicates that CCR is as well independent to significant extent from its high-altitude initialisation data (ECMWF) up to 40 km. We find that the

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

only severe deviation that cannot be explained by the different CHAMP and MIPAS vertical resolution is in the JJA 2003 southern high latitudes above 30 km (Sect. 4.4), which is also present in the comparison to other correlative datasets (see Sect. 4.5). The systematic differences are statistically significant in most regions but fairly small compared to the combined general error characteristics of RO (~1 K) and MIPAS (0.5 to 1.5 K). This is particularly encouraging, since MIPAS and CCR RO are independent from each other.

### 4.3 Comparison to Envisat GOMOS temperatures

Due to the limited GOMOS data availability for this study, only a small ensemble could be used for intercomparison here (49 co-locations in total) and no latitudinal separation has thus been done. All profiles analysed are in the period SON 2002 plus one day of December 2002. Figure 4 shows the intercomparison results (the scale of the abscissa is extended compared to other figures). Recall that GOMOS temperatures are from star tracker data (Sect. 3.3.2). The comparison shows a severe deviation below 25 km (up to about 6 K), and biases below 2 K from 25 to 35 km with a standard deviation of 5 to 8 K. Due to the large standard deviation and the small ensemble only biases larger than about 2 K can be regarded as statistically significant at the  $2\sigma$ -level. Since the GOMOS temperature retrieval is preliminary and the dataset is small (a more advanced temperature product based on GOMOS fast photometer data is currently under development (V. Sofieva, FMI Helsinki, Finland, personal communications, 2006)), this comparison mainly demonstrates the value of CCR RO data for evaluation of new remote sensing products. The bias below 25 km is significant and can be attributed to GOMOS, since CCR comparisons to the other correlative dataset give no indication for such a bias in CCR retrievals. Further results from comparisons of GOMOS data to CHAMP and ECMWF data are discussed by Retscher et al. (2006).

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

#### 4.4 Comparison to ECMWF analysis temperatures

Figure 5 illustrates the intercomparison results between CCR CHAMP and ECMWF temperatures. ECMWF analyses generally agree very well with CCR temperatures (bias  $<0.5\text{ K}$  in most regions below 30 km, accompanied by standard deviations of  $\sim 1.5$  to  $2.5\text{ K}$ ) with three remarkable exceptions: An oscillatory bias structure in JJA 2003 at southern high latitudes (polar vortex), a bias in the vicinity of the low latitude tropopause, and a general bias over all latitudes above 30 km.

The oscillatory bias has been shown to be a feature of ECMWF's representation of the polar vortex in the analyses and is probably an artefact from bias adjustments in the ECMWF data assimilation system in data sparse regions (Gobiet et al., 2005). It can be found in any JJA season from 2002 to 2006 to varying extent (not shown). The polar vortex bias seems to be the most severe bias in ECMWF analyses and a combined inspection of Fig. 3 (CCR vs. MIPAS) and Fig. 5 (CCR vs. ECMWF) indicates that this bias (relative to the presumed "true" state of the atmosphere) above 30 km might be even larger than displayed in Fig. 5 (about 10 K or more). Such a large bias in the high-altitude initialisation data degrades the CCR retrievals down to about 30 km (see Figs. 2, 3, and 6). However, this comparative inspection indicates as well that this downward propagated bias is restricted to the JJA southern high latitudes above 30 km in CCR RO data.

The tropical tropopause bias is present in any season from 2002 to winter 2005/2006 and has been found as well to be attributable to ECMWF analyses (Gobiet et al., 2005; Borsche et al., 2007). It was probably related to under-represented atmospheric wave activity in the ECMWF model and is found strongly reduced since an update and resolution improvement of the ECMWF model system (Borsche et al., 2007), which became operational in February 2006.

The general warm bias above 30 km is of particular interest here since it demonstrates the relative independency of CCR retrievals from their high-altitude initialisation data, thanks to the careful initialisation approach. CCR shows no warm bias compared

### CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



to any other correlative dataset except GFZ, which is strictly tied to ECMWF at high altitudes (cf. Sect. 3.3.1). The bias above 30 km visible in Fig. 5 is thus attributable as cold bias to the ECMWF analyses. Particularly the comparison to MIPAS (Fig. 3) indicates no CCR bias between 30 and  $\sim 37$  km (except the JJA polar vortex bias), which in turn indicates that the CCR high-altitude initialisation scheme is insensitive to moderate biases ( $\sim 3$  K) in the a priori data at least up to 35 km (a potential residual cold bias above 35 km is discussed in Sect. 4.5). Comparison to other analyses (see next Sect. 4.5) indicate no warm CCR bias above 30 km as well.

#### 4.5 Comparison to other atmospheric analyses

Figure 6 shows the intercomparison results between CCR CHAMP and four atmospheric analyses (as introduced in Sect. 3.3.3), which allows to cross-check and further assess the consistency of the results found so far. Generally, Fig. 6 indicates that the bias in JJA at southern high latitudes above 30 km is partly attributable to CCR. It is visible in all JJA 2003 differences except for NCEP Rean which does not reach high enough. Below 30 km, the biases are in general found below 1 K in most altitudes and latitudes but several exceptions occur: In the MetO, NCEP/CPC, and NCEP Rean comparisons, a cold bias appears near the low latitude tropopause. This can be mainly attributed to the lower vertical resolution of the analyses relative to CCR. In case of NCEP Rean (see Sect. 5) also a further bias plays a role. In addition to the tropopause features, there are several severe biases visible (e.g., around 25 km in GEOS-4), but none of these appear consistently in more than one analysis. This implies that they are related to the specific problems in the different analysis systems and underlines the value of the RO data as reference dataset.

Above about 35 km, a consistent (cold) bias shows up in the GEOS-4, MetO, and to a lesser extent the NCEP/CPC comparisons. This could be partly a CCR cold bias (though not visible in the comparison to MIPAS), at least above 35 km, which would be reasonable given the upper stratosphere cold bias in the ECMWF analyses serving as initialisation data.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Generally, these comparisons are consistent with and add confidence to the results of the previous sections. Additionally, interesting details about the specific analyses can be derived, for example, the significant cold bias (now viewed relative to CCR) of GEOS-4 in the JJA 2003 southern high latitudes between about 25 and 30 km and the strong warm bias of NCEP Rean in about the same region.

## 5 Summary and conclusions

This study described and evaluated the CCR RO processing scheme of the Wegener Center, Univ. of Graz, which particularly aims at delivering bias-free atmospheric profiles for climate monitoring and research. The CCR RO temperature retrievals from CHAMP data of two representative seasons (SON 2002 and JJA 2003) were validated against correlative datasets from operational GFZ Potsdam CHAMP retrievals, Envisat MIPAS and GOMOS temperatures, ECMWF analyses, and four further atmospheric analyses.

Figure 7 provides a summary overview on the validation results of the study in the form of an “error portrait diagram”, which shows 10 km-altitude-mean systematic differences (biases) for all comparisons presented and indicates statistically insignificant differences with crosses.

Figure 7 shows that temperatures in the region above 30 km are strongly varying between the correlative datasets. ECMWF and GFZ are significantly colder than CCR (1.3 to 1.8 K), all other analyses are warmer than CCR (0.4 to 1.7 K). MIPAS is closest to CCR, with mean biases below 0.5 K. This gives confidence in the CCR temperatures above 30 km, since MIPAS is the only (in a bias-sense) model-independent correlative dataset in this evaluation study and uses an entirely different measurement principle than CCR. However, a consistent CCR cold bias against three different analyses above 35 km (Sect. 4.5) is also to be noted. Additionally, it has been found (Sect. 4.4) that an extremely biased a priori (about 10 K or more) degrades CCR RO temperature accuracy down to 30 km (JJA southern high latitudes).

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

**CHAMP temperature  
retrieval and  
validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

Below 30 km, no systematic biases were found for CCR RO. NCEP Rean stands out a little bit being generally warmer than CCR ( $\sim 0.7$  K), in accordance with Manney et al. (2005a), who concluded that NCEP Rean is not suited for stratospheric studies due to extensive biases. The global mean intercomparison bias (over all correlative datasets, all regions, and both seasons) between 10–20 km and 20–30 km amounts to  $-0.2$  K, whereby half of this biases is caused by NCEP Rean. The following main conclusions can be drawn.

1. In the global mean within 10–30 km altitude we find that the present validation observationally constrains the potential RO temperature bias to be  $<0.2$  K. Latitudinally resolved analyses show biases to be observationally constrained to  $<0.2$ – $0.5$  K up to 35 km in most cases and up to 30 km in any case, even if a severely biased (about 10 K or more) a priori information is used in the high altitude initialisation of the retrieval.

2. No evidence is found for the 10 to 35 km altitude range of residual RO bias sources other than potentially propagated downward from initialisation. This indicates that the widely quoted RO promise of “unbiasedness and long-term stability due to intrinsic self-calibration” can indeed be realized given care in the data processing to strictly limit structural uncertainty.

3. Adequate high-altitude initialisation is crucial for accurate stratospheric RO retrievals. Still common methods of initialising, in addition to bending angle initialisation, the hydrostatic integral with an upper boundary temperature or pressure value derived from meteorological analyses, are prone to introduce biases from the initialisation down to below about 25 km.

4. Also above 30 to 35 km GNSS RO still delivers a considerable amount of observed information up to around 40 km. This is particularly interesting for NWP assimilation systems where direct assimilation of non-initialized (a priori-free) observed RO bending angles appears thus to be the method of choice.

Overall we conclude that the RO method in general, and the Wegener Center CCR scheme based on GFZ Potsdam phase delay and orbital data in particular, is capable of providing high quality and essentially unbiased atmospheric profiles up to about

35 km with high vertical resolution ( $\sim 1$  km) and global coverage, adequate for climate monitoring and research.

While this study based on single-satellite CHAMP data clearly underlined the value of RO for climate applications, upcoming data from new missions such as Formosat-3/COSMIC (launched in April 2006) and MetOp (launched in October 2006) will strongly further enhance the utility of RO for improved operational monitoring of climate variability and change in the future.

*Acknowledgements.* We thank J. Wickert and T. Schmidt (GFZ Potsdam) for excellent cooperation and the provision of CHAMP data, D.-Y. Wang (Univ. of New Brunswick, NB, Canada; formerly IMK Karlsruhe) for support and advice regarding MIPAS data, ECMWF for access to their operational analysis data, the British Atmospheric Data Centre for MetO data, the GSFC ACD Science Data System for NCEP/CPC data, and NASA's GMAO for GEOS-4 data. NCEP reanalysis data were provided by the NOAA/CIRES Climate Diagnostics Center, Boulder, CO. Work at the Jet Propulsion Laboratory, CalTech, CA, was done under contract with the National Aeronautics and Space Administration. A. Gobiet received funding for the work from the START research award of G. Kirchengast funded by the Austrian Ministry for Education, Science, and Culture and managed under Program Y103-N03 of the Austrian Science Fund (FWF). M. Borsche received funding from the Austrian Aeronautics and Space Agency (FFG-ALR) via the CHAMPCLIM project.

## References

- Alfred, J., Fromm, M., Bevilacqua, R., Nedoluha, G., Strawa, A., Poole, L., and Wickert, J.: Observations and analysis of polar stratospheric clouds detected by POAM III and SAGE III during the SOLVE II/VINTERSOL campaign in the 2002/2003 Northern Hemisphere winter, *Atmos. Chem. Phys. Discuss.*, 6, 11 391–11 426, 2006.
- Bertaux, J. L., Megie, G., Widemann, T., Chassefiere, E., Pellinen, R., Kyrölä, E., Korpela, S., and Simon, P.: Monitoring of ozone trends by stellar occultations: the GOMOS instrument, *Adv. Space Res.*, 11, 237–242, 1991.
- Bevis, M., Businger, S., Herring, T. A., Rocken, C., Anthes, R. A., and Ware, R. H.: GPS

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

meteorology: Mapping zenith wet delays onto precipitable water, *J. Appl. Met.*, 33, 379–386, 1994.

Bloom, S. C., da Silva, A. M., Dee, D. P., et al.: The Goddard Earth Observing Data Assimilation System, GEOS DAS Version 4.0.3: documentation and validation, Technical Report No. 104606 V26, NASA, 2005.

Borsche, M., Kirchengast, G., and Foelsche, U.: Tropical tropopause climatology as observed with radio occultation measurements from CHAMP compared to ECMWF and NCEP analyses, *Geophys. Res. Lett.*, 34, L03702, doi:10.1029/2006GL027918, 2007.

ECMWF: IFS documentation CY28r1, ECMWF, Reading, U.K., 2004.

European Space Agency: Envisat, MIPAS An instrument for atmospheric chemistry and climate research, ESA Publications Division, SP-1229, ESTEC, Noordwijk, The Netherlands, 2000.

Fischer, H. and Oelhaf, H.: Remote sensing of vertical profiles of atmospheric trace constituents with MIPAS limb-emission spectrometers, *Appl. Opt.*, 35, 2787–2796, 1996.

Fjeldbo, G. F., Eshleman, V. R., and Kliore, A. J.: The neutral atmosphere of Venus as studied with the Mariner V radio occultation experiments, *Astron. J.*, 76, 123–140, 1971.

Foelsche, U., Gobiet, A., Loescher, A., Kirchengast, G., Steiner, A. K., Wickert, J., and Schmidt, T.: The CHAMPCLIM project: An overview, in: *Earth observation with CHAMP: Results from three years in orbit.* edited by: Reigber, C., Luehr, H., Schwintzer, P., Wickert, J., Springer, Berlin Heidelberg, 615–619, 2005.

Foelsche, U., Gobiet, A., Steiner, A.K., Kirchengast, G., Borsche, M., Schmidt, T., and Wickert, J.: Global climatologies based on radio occultation data: The CHAMPCLIM project. in: *Atmosphere and climate: Studies by occultation methods*, edited by: Foelsche, U., Kirchengast, G., Steiner, A. K., Springer, Berlin Heidelberg, 303–314, 2006.

Gobiet, A. and Kirchengast, G.: Advancements of GNSS radio occultation retrieval in the upper stratosphere for optimal climate monitoring utility, *J. Geophys. Res.*, 109, D24110, doi:10.1029/2004JD005117, 2004.

Gobiet, A., Foelsche, U., Steiner, A. K., Borsche, M., Kirchengast, G., and Wickert, J.: Climatological validation of stratospheric temperatures in ECMWF operational analyses with CHAMP radio occultation data, *Geophys. Res. Lett.*, 32, L12806, doi:10.1029/2005GL022617, 2005.

Gobiet, A.: Radio occultation data analysis for climate monitoring and first climatologies from CHAMP (Ph.D. thesis), Scientific Report No. 6-2005, 140 pp, Wegener Center Verlag, University of Graz, Austria, 2005.

Goody, R., Anderson, J., and G. North; Testing climate models: an approach, *Bull. Am. Met.*

**CHAMP temperature retrieval and validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

- Soc., 79, 2541–2549, 1998.
- GRAS-SAG: The GRAS instrument on MetOp, ESA/EUMETSAT Rep. (ESA No. VR/3021/PI, EUMETSAT No. EPS/MIS/IN/9), ESA/ESTEC, Noordwijk, Netherlands, 1998
- Hajj, G. A., Kursinski, E. R., Romans, L. J., Bertinger, W. I., and Leroy, S. S.: A technical description of atmospheric sounding by GPS occultation, *J. Atmos. Sol.-Terr. Phys.*, 64, 451–469, 2002.
- Hajj, G. A., Ao, C. O., Iijima, P. A., Kuang, D., Kursinski, E. R., Mannuchi, A. J., Meehan, T. K., Romans, L. J., de al Torre Juarez, M., and Yunck, T. P.: CHAMP and SAC-C atmospheric occultation results and intercomparisons, *J. Geophys. Res.*, 109, D05109, doi:10.1029/2003JD003909, 2004.
- Healy, S. B. and Eyre, J. R.: Retrieving temperature, water vapour and surface pressure information from refractive index profiles derived by radio occultation: A simulation study, *Q. J. R. Meteorol. Soc.*, 126, 1661–1683, 2000.
- Healy, S. B.: Smoothing radio occultation bending angles above 40 km, *Ann. Geophys.*, 19, 459–468, 2001
- Healy, S. B., Jupp, A. M., and Marquardt, C.: Forecast impact experiment with GPS radio occultation measurements, *Geophys. Res. Lett.*, 32, L03804, doi:10.1029/2004GL020806, 2005.
- Healy, S. B. and Thépaut, J.-N.: Assimilation experiments with CHAMP GPS radio occultation measurements, *Q. J. R. Meteorol. Soc.*, 132, 605–623, doi:10.1256/qj.04.182, 2006.
- Hedin, A. E.: Extension of the MSIS thermosphere model into the middle and lower atmosphere, *J. Geophys. Res.*, 96, 1159–1172, 1991
- Hocke, K., Igarashi, K., and Tsuda, T.: High-resolution profiling of layered structures in the lower stratosphere by GPS occultation, *Geophys. Res. Lett.*, 30, 8, 1426, doi:10.1029/2002GL016566, 2003.
- Kursinski, E. R., Hajj, G. A., Schofield, J. T., Linfield, R. P., and Hardy, K. R.: Observing earth's atmosphere with radio occultation measurements using the global positioning system, *J. Geophys. Res.*, 102, 23 429–23 465, 1997.
- Kyrölä, E., Tamminen, J., Leppelmeier, G. W., et al.: GOMOS on Envisat: An overview, *Adv. Space Res.*, 33, 1020–1028, 2004.
- Leroy, S. S., Dykema, J. A., and Anderson, J. G.: Climate benchmarking using GNSS Occultation, in: *Atmosphere and climate: Studies by occultation methods*, Foelsche, U., Kirchengast, G., Steiner, A. K., Springer, Berlin-Heidelberg, pp 287–301, 2006.

**CHAMP temperature  
retrieval and  
validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

- Loiselet, M., Stricker, N., Menard, Y., Luntama, J.-P.: GRAS – MetOp’s GPS-based atmospheric sounder. *ESA Bulletin* 102, 38–44, 2000.
- Manney, G.L., Allen, D.M., Krüger, K., Naujokat, B., Santee, M.L., Sabutis, J.L., Pawson, S., Swinbank, R., Randall, C.E., Simmons, A.J., and Long, C.: Diagnostic comparison of meteorological analyses during the 2002 antarctic winter, *Mon. Weather Rev.*, 133, 1261–1278, 2005a.
- Manney, G.L., Krüger, K., Sabutis, J.L., Sena S.A, and Pawson, S.: The remarkable 2003–2004 winter and other recent warm winters in the Arctic stratosphere since the late 1990s, *J. Geophys. Res.*, 110, D04107, doi:10.1029/2004JD005367, 2005b.
- Marquardt, C., Schöllhammer, K., Beyerle, G., Schmidt, T., Wickert, J., and Reigber, C.: Validation and data quality of CHAMP radio occultation data, in: *First CHAMP Mission Results*, edited by: Reigber, C., Lühr, H., and Schwintzer, P., Springer, Berlin-Heidelberg-New York, 384–396, 2003.
- Retscher, C., Gobiet, A., and Kirchengast, G.: Stratospheric temperature and ozone sounding with ENVISAT/GOMOS stellar occultation, in: *Occultation for Probing Atmosphere and Climate*, edited by: G. Kirchengast, U. Foelsche, A. K. Steiner, Springer, Berlin-Heidelberg-New York, 299–308, 2004.
- Retscher, C., Kirchengast, G., and Gobiet, A.: Stratospheric temperature sounding with Envisat/GOMOS by exploitation of SFA/SATU data, in *Atmosphere and Climate: Studies by Occultation Methods*, Kirchengast, G., Foelsche, U., and Steiner, A. K. (eds.), Springer, Berlin-Heidelberg-New York, 55–66, 2006.
- Rocken, C., Kuo, Y., Schreiner, W. S., Hunt, D., Sokolovskij, S., and McCormick, C.: COSMIC system description. *Terr Atmos Ocean Sci* 11: 21–52, 2000
- Rodgers, C. D. and Connor, B. J.: Intercomparison of remote sensing Instruments, *J. Geophys. Res.*, 108, D3, 4116, doi:10.1029/2002JD002299, 2003.
- Schreoder, T., Leroy, S., Stendel, M., and Kaas, E.: Validating the microwave sounding unit stratospheric record using GPS occultation, *Geophys. Res. Lett.*, 30, 14, 1734, doi:10.1029/2003GL017588, 2003.
- Sokolovskiy, S. and Hunt, D.: Statistical optimization approach for GPS/Met data inversions, Paper presented at URSI GPS/Met Workshop, Tucson, Arizona, 1996.
- Steiner, A. K., Kirchengast, G., and Ladreiter, H. P.: Inversion, error analysis, and validation of GPS/MET occultation data. *Ann. Geophys.*, 17, 122–138, 1999, <http://www.ann-geophys.net/17/122/1999/>.

---

**CHAMP temperature  
retrieval and  
validation**A. Gobiet et al.

---

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

Steiner, A. K., Gobiet, A., Foelsche, U., and Kirchengast, G.: Radio occultation data processing advancements for optimizing climate utility, Tech. Report for ASA No. 3/2004, Inst. for Geophys., Astrophys. and Meteorol., Univ. of Graz, Austria, 2004.

Steiner, A. K. and Kirchengast, G.: Error analysis for GNSS radio occultation data based on ensembles of profiles from end-to-end simulations, *J. Geophys. Res.* 110, D15307, doi:10.1029/2004JD005251, 2005.

Swinbank, R., Ingleby, N. B., Boorman, P. M., and Renshaw, R. J.: A 3D variational data assimilation system for the stratosphere and troposphere, Met Office Numerical Weather Prediction Forecasting Research Scientific Paper, 71, UK Met Office, 2002.

Syndergaard, S.: Modeling the impact of Earth's oblateness on the retrieval of temperature and pressure profiles from limb sounding, *J. Atmos. Sol.-Terr. Phy.*, 60, 2, 171–180, 1998.

Syndergaard, S.: Retrieval analysis and methodologies in atmospheric limb sounding using the GNSS radio occultation technique, DMI Sci. Rep., 99-6, Danish Met. Inst., Copenhagen, Denmark, 1999.

Rieder, M. and Kirchengast, G.: Error analysis and characterization of atmospheric profiles retrieved from GNSS occultation data, *J. Geophys. Res.*, 106, D23, 31 755–31 770, 2001.

von Clarmann, T., Glatthor, N., Grabowski, U., et al.: Retrieval of temperature and tangent altitude pointing from limb emission spectra recorded from space by the Michelson Interferometer for Passive Atmospheric Sounding (MIPAS), *J. Geophys. Res.*, 108, D23, 4736, doi:10.1029/2003JD003602, 2003a.

von Clarmann, T., Ceccherini, S., Doicu, A., et al.: A blind test retrieval experiment for infrared limb emission spectrometry, *J. Geophys. Res.*, 108, D23, 4746, doi:10.1029/2003JD003835, 2003b.

von Engeln, A.: A first test of climate monitoring with radio occultation instruments: Comparing two processing centers, *Geophys. Res. Lett.*, 33, L22705, doi:10.1029/2006GL027767, 2006.

Vorob'ev, V. V. and Krasnil'nikova, T. G.: Estimation of the accuracy of the atmospheric refractive index recovery from Doppler shift measurements at frequencies used in the NAVSTAR system, *Phys. Atmos. Ocean*, 29, 602–609, 1994.

Wang, D.-Y., Stiller, G. P., von Clarmann, T., et al.: Cross-validation of MIPAS/ENVISAT and GPS-RO/CHAMP temperature profiles, *J. Geophys. Res.*, 109, D19311, doi:10.1029/2004JD004963, 2004.

Wang, D.-Y., von Clarmann, T., Fischer, H., et al.: Validation of stratospheric temperatures mea-

---

## CHAMP temperature retrieval and validation

A. Gobiet et al.

---

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

sured by Michelson Interferometer for Passive Atmospheric Sounding (MIPAS) on Envisat, J. Geophys. Res., 110, D08301, doi:10.1029/2004JD005342, 2005.

Wickert, J., Reigber, C., Beyerle, G., König, R., Marquardt, C., Schmidt, T., Grunwaldt, L., Galas, R., Meehan, T., Melbourne, W., and Hocke, K.: Atmosphere sounding by GPS radio occultation: First results from CHAMP, Geophys. Res. Lett., 28, 3263–3266, 2001.

Wickert, J., Schmidt, T., Beyerle, G., König, R., Reigber, C., and Jakowski, N.: The radio occultation experiment aboard CHAMP: Operational data analysis and validation of vertical atmospheric profiles. J. Met. Soc. Japan, 82, 381–395, 2004.

Wu, B.-H., Chu, V., Chen, P., and King, T.: FORMOSAT-3/COSMIC science mission update. GPS solutions 9: 111–121, doi:10.1007/s10291-005-0140-z, 2005.

ACPD

7, 3229–3268, 2007

## CHAMP temperature retrieval and validation

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

EGU



**Table 1.** Overview of the CHAMPCLIM retrieval (CCR) scheme, dry air.

Early outlier rejection	“3 $\sigma$ ” outlier rejection on 50 Hz sampling rate phase delay data, based on a one-second moving window over the profile.
Phase delay smoothing	Smoothing of 50 Hz phase delay profiles using regularization (third order norm, regularization parameter= $10^5$ , following Syndergaard, 1999).
Bending angle retrieval	Geometric optics retrieval (e.g., Kursinski et al., 1997) at both L1 and L2 frequencies.
Ionospheric correction	Linear combination of L1 and L2 bending angles (Vorob'ev and Krasil'nikova, 1994). Correction is applied to low-pass filtered bending angles (1 km moving average), L1 high-pass contribution is added after correction (Hocke et al., 2003). L2 bending angles <15 km derived via L1-L2 extrapolation.
Statistical optimisation of bending angles	Statistical optimisation of bending angles between 30 and 120 km. Vertically correlated background (corr. length =6 km) and observation (corr. length =1 km) errors. Observation error estimated from observed variance of observed profile >65 km. Background error: 15%. Background information: co-located profile derived from ECMWF operational analysis (T42L60). Above ~60 km: MSISE-90 (Hedin, 1991). Optional: MSISE-90 climatology as background profiles search library (following Gobiet and Kirchengast, 2004).
Abel transform	Numerical integration (Simpson's trapezoidal rule) from each height (impact parameter) to 120 km. Impact parameter to height conversion with radius of curvature at mean tangent point location following Syndergaard (1998).
Hydrostatic integral initialization	No initialization below 120 km. At 120 km: pressure = pressure(MSISE-90).
Lower cut-off altitude	The lowermost altitude, where retrieved data is kept, is set to the altitude where severe impact parameter ambiguities occur (impact parameter increase >0.2 km from one data point to the next downwards).
External quality control (for outlier profiles)	Refractivity 5 km–35 km: $\Delta N/N < 10\%$ ; Temperature 8 km–25 km: $\Delta T < 20$ K. Reference: Co-located ECMWF operational analysis profiles (T42L60 resp. T42L91 as of 01/02/2006).
Reference frame, vertical coordinate	Earth figure: WGS-84 ellipsoid; Vertical coordinate: mean-sea-level (MSL) altitude; conversion of ellipsoidal height to MSL altitude (at mean tangent point location) via EGM-96 geoid smoothed to $2^\circ \times 2^\circ$ resolution.

**CHAMP temperature retrieval and validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close


Full Screen / Esc

Printer-friendly Version

Interactive Discussion

**CHAMP temperature  
retrieval and  
validation**

A. Gobiet et al.




**Fig. 1.** Geographical distribution of CHAMP events (red squares) and coinciding MIPAS profiles (blue crosses) in SON 2002 (12 950 CHAMP profiles, 368 coincidences, left panel) and JJA 2003 (13 655 CHAMP profiles, 254 coincidences, right panel). The black circles of latitudes indicate the latitudinal separation into 18 ten-degree bands of zonal-mean sub-ensembles.

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[◀](#)[▶](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

CHAMP temperature  
retrieval and  
validation

A. Gobiet et al.



**Fig. 2.** CCR CHAMP temperature differences relative to operational GFZ CHAMP retrievals, i.e., positive values correspond to higher CCR temperatures. Top row: Systematic differences (bias) in 18 latitude bands (left: SON 2002, right JJA 2003). Middle and bottom row, from left to right: Global, low latitude ( $-30^{\circ}$  to  $30^{\circ}$ ), mid latitude ( $\pm 30^{\circ}$  to  $\pm 60^{\circ}$ ), and high latitude ( $\pm 60^{\circ}$  to  $\pm 90^{\circ}$ ) bias (black)  $\pm$  standard deviation profiles (grey) for SON 2002 (middle) and JJA 2003 (bottom), respectively.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close


Full Screen / Esc

Printer-friendly Version

Interactive Discussion

CHAMP temperature  
retrieval and  
validation

A. Gobiet et al.



**Fig. 3.** CCR CHAMP temperature differences relative to Envisat MIPAS retrievals. Same format as Fig. 2.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶


Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



**Fig. 4.** CCR CHAMP temperature differences relative to Envisat GOMOS retrievals from star tracker data. Bias (black)  $\pm$  standard deviation profiles (grey) for an ensemble from SON 2002 (plus one day in December 2002).

**CHAMP temperature retrieval and validation**

A. Gobiet et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close


Full Screen / Esc

Printer-friendly Version

Interactive Discussion

CHAMP temperature  
retrieval and  
validation

A. Gobiet et al.



**Fig. 5.** CCR CHAMP temperature differences relative to ECMWF analyses. Same format as Fig. 2.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close


Full Screen / Esc

Printer-friendly Version

Interactive Discussion

## CHAMP temperature retrieval and validation

A. Gobiet et al.



**Fig. 6.** CCR CHAMP zonal-mean systematic temperature differences (bias) in 18 latitude bands (left column: SON 2002, right column JJA 2003) relative to four meteorological analyses. Top row: GEOS-4 (GEOS4), upper middle row: MetO (MetOf), lower middle row: NCEP/CPC (NCEP), bottom row: NCEP Rean (NECPR).

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

CHAMP temperature  
retrieval and  
validation

A. Gobiet et al.

		CHGFZ		MIPAS		ECMWF		GEOS-4		MetO		NCEP/CPC		NCEP Rean		Mean
		SON	JJA	SON	JJA	SON	JJA	SON	JJA	SON	JJA	SON	JJA	SON	JJA	
30–40 km	high NH	1.6	1.1	0.8	-0.4	1.0	1.1	0.7	-0.4	-0.4	-2.0	-0.8	-1.2			0.1
	mid NH	2.1	1.9	<del>0.1</del>	<del>0.1</del>	1.4	1.5	0.4	<del>0.1</del>	-1.2	-1.6	-0.4	-0.3			0.3
	low NH	1.8	2.1	-0.7	-0.4	1.6	1.2	-1.4	-0.8	-2.4	-1.9	-0.8	-0.8			-0.2
	low SH	2.1	2.4	-1.1	-0.4	1.6	1.3	-1.3	-0.4	-2.4	-1.8	<del>0.2</del>	-0.4			-0.1
	mid SH	1.9	1.8	-0.3	0.4	1.5	1.0	-0.5	<del>0.0</del>	-2.1	-1.1	-0.5	-0.6			0.1
	high SH	1.2	-1.7	-0.9	1.6	1.3	1.9	-1.6	-0.7	-1.8	-0.4	-0.8	-1.7			-0.3
20–30 km	high NH	-0.2	-0.2	<del>0.1</del>	<del>0.1</del>	<del>0.0</del>	<del>0.1</del>	-0.2	-0.3	<del>0.0</del>	<del>0.0</del>	-0.6	-0.6	-1.2	-1.2	-0.3
	mid NH	0.4	0.2	-0.3	<del>0.0</del>	0.4	0.3	0.2	<del>0.0</del>	0.3	0.1	0.2	<del>0.1</del>	-0.3	-0.5	0.1
	low NH	<del>0.0</del>	0.2	-1.1	-0.7	-0.2	-0.2	-0.1	-0.6	-0.3	-0.1	<del>0.1</del>	0.7	-0.4	-0.2	-0.2
	low SH	<del>0.0</del>	0.2	-0.8	-0.6	-0.2	-0.1	<del>0.1</del>	-0.4	<del>0.0</del>	<del>0.0</del>	<del>0.0</del>	0.6	-0.5	<del>0.1</del>	-0.1
	mid SH	0.2	0.2	-0.2	<del>0.0</del>	0.2	0.1	0.2	0.8	0.5	0.6	-0.6	0.2	-1.0	-0.8	0.0
	high SH	0.3	-0.9	-0.3	-0.5	-0.2	-0.4	<del>0.1</del>	1.4	-0.7	-0.3	-0.3	-1.3	-0.5	-2.9	-0.5
10–20 km	high NH	<del>0.0</del>	<del>0.0</del>	<del>0.0</del>	0.3	-0.3	-0.1	-0.3	-0.3	0.2	0.2	<del>0.0</del>	0.1	0.1	0.1	0.0
	mid NH	0.2	0.1	-0.6	0.3	<del>0.0</del>	0.1	-0.2	-0.2	<del>0.0</del>	-0.1	-0.1	-0.2	-0.3	-0.4	-0.1
	low NH	<del>0.0</del>	<del>0.0</del>	-0.3	-0.5	<del>0.1</del>	0.2	-0.1	-0.6	-0.5	-0.5	-0.9	-0.8	-1.4	-1.5	-0.5
	low SH	-0.0	0.1	-0.5	0.5	<del>0.0</del>	0.3	-0.5	-0.1	-0.5	-0.3	-0.9	-0.5	-1.7	-1.6	-0.4
	high SH	0.2	0.2	0.3	0.4	<del>0.0</del>	<del>0.1</del>	-0.3	-0.2	<del>0.0</del>	<del>0.0</del>	-0.1	0.2	-0.6	-0.3	-0.0
	high SH	0.3	<del>0.0</del>	0.7		-0.1	-0.4	-0.3	-0.4	<del>0.0</del>	-0.2	-0.2	<del>0.1</del>	-0.9	-0.7	-0.2
30–40 km	mean	1.8	1.3	-0.4	0.1	1.4	1.3	-0.6	-0.4	-1.7	-1.5	-0.6	-0.8			-0.0
20–30 km	mean	0.1	-0.1	-0.4	-0.3	-0.0	-0.0	-0.0	0.2	-0.0	0.0	-0.2	-0.1	-0.6	-1.0	-0.2
10–20 km	mean	0.1	0.1	-0.1	-0.0	-0.0	0.0	-0.3	-0.3	-0.1	-0.1	-0.4	-0.2	-0.8	-0.7	-0.2
10–40 km	mean	0.7	0.4	-0.3	-0.1	0.5	0.4	-0.3	-0.2	-0.6	-0.5	-0.4	-0.4	-0.7	-0.8	-0.1

**Fig. 7.** CCR CHAMP average temperature differences [K] relative to the operational CHAMP retrieval results from GFZ (CHGFZ), Envisat MIPAS, ECMWF operational analyses, GEOS-4 analyses, MetO analyses, NCEP/CPC analyses, and NCEP Reanalyses in SON 2002 and JJA 2003, respectively, at low ( $0^\circ$  to  $30^\circ$ ), mid ( $30^\circ$  to  $60^\circ$ ), and high ( $60^\circ$  to  $90^\circ$ ) latitudes of the northern (NH) and the southern hemisphere (SH) between 10–20 km, 20–30 km, and 30–40 km. Aggregate means (averages of the individual comparison means) are also shown (rightmost column and four bottom lines). The colours in each cell visualize the magnitude (if  $>0.5$  K) of a cold (blue) and warm (red) difference, respectively, crosses indicate statistically insignificant ( $<2\sigma$ -level) differences/biases. Empty white cells indicate that there was no comparison due to insufficient correlative data.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion