

Influence of sea salt aerosols on the development of Mediterranean tropical-like cyclones

Enrique Pravia-Sarabia¹, Juan José Gómez-Navarro¹, Pedro Jiménez-Guerrero^{1,2}, and Juan Pedro Montávez¹

¹Physics of the Earth, Regional Campus of International Excellence (CEIR) “Campus Mare Nostrum”, University of Murcia, 30100 Murcia, Spain

²Biomedical Research Institute of Murcia (IMIB-Arrixaca), 30120 Murcia, Spain

Correspondence: Juan Pedro Montávez (montavez@um.es)

Abstract. Medicanes are mesoscale tropical-like cyclones that develop in the Mediterranean basin and represent a great hazard for the coastal population. The skill to accurately simulate them is of utmost importance to prevent economical and personal damages. Medicanes are fuelled by the latent heat released in the condensation process associated to convective activity, which is regulated by the presence and activation of cloud condensation nuclei, mainly originated from sea salt aerosols (SSA) for marine environments. Henceforth, the purpose of this contribution is twofold: assessing the effects of an interactive calculation of SSA on the strengthening and persistence of medicanes; and providing insight on the casuistry and sensitivities around their simulation processes. To this end, a set of simulations has been conducted with a chemistry/meteorology coupled model considering prescribed aerosols (PA) and interactive aerosol concentrations (IA). The results indicate that IA produces longer-lasting and more intense medicanes. Further, the role of the initialization time and nudging strategies for medicane simulations has been explored. Overall, the results suggest that (1) the application of spectral nudging dampens the effects of IA; (2) the initialization time introduces a strong variability on the storm dynamics; and (3) wind-SSA feedback is crucial and should be considered when studying medicanes.

Copyright statement. TEXT

1 Introduction

Mediterranean tropical-like cyclones, also known as medicanes (from **mediterranean hurricanes**), are mesoscale perturbations that exhibit tropical characteristics, such as an eye-like feature and warm core. These storms are characterized by high wind speeds and vertically aligned geopotential height perturbations along different pressure levels. Just like regular tropical cyclones, medicanes represent a hazard for the population of coastal areas. However, given the relatively small extent of the Mediterranean basin and the lower sea surface temperatures of the Mediterranean Sea, [as well as the common presence of environmental wind shear at mid-latitudes](#), they do not reach the size and intensity of actual hurricanes. Still, they can produce heavy precipitation and intense wind gusts, reaching up to Category 1 in the Saffir-Simpson scale (Fita et al., 2007; Miglietta

and Rotunno, 2019). Thus, our ability to understand and simulate accurately medicanes with state-of-the-art meteorological modeling systems stands as a key factor to prevent their associated damages.

25 Tropical-like cyclones in general, and medicanes in particular, are usually considered to be a hybrid between tropical and extratropical cyclones. Although their triggering and early development mechanisms differ from those of tropical cyclones (Tous and Romero, 2013; Cavicchia et al., 2014; Miglietta and Rotunno, 2019; Dafis et al., 2020), such storms are generally maintained in the same way as tropical cyclones ~~at least~~ in their mature stage, ~~in which moist and warm air is advected towards the low pressure storm centre at the surface and lower tropospheric levels. This produces and maintains a thermal disequilibrium in the vertical direction that enhances convection, consequently producing condensation:~~ through the evaporation of water
30 from the ocean surface. The initial convective activity caused by potential instability produces condensation of moist rising air through adiabatic cooling. The condensation process releases latent heat that warms the cyclone core, which is the dominant mechanism that sustains the vortex structure (Lagouvardos et al., 1999).

Numerous studies have addressed the sensitivity of medicane simulations to different factors related to their intensification and track. Some authors have studied the effects of an increased sea surface temperature (SST) (Pytharoulis, 2018; Noyelle et al., 2019), while others focus on the role of air-sea interaction and surface heat fluxes (Tous et al., 2013; Akhtar et al., 2014; Ricchi et al., 2017; Gaertner et al., 2018; Rizza et al., 2018; Bouin and Lebeau-pin Brossier, 2020) or the influence of using several different physical parameterizations (Miglietta et al., 2015; Pytharoulis et al., 2018; Ragone et al., 2018; Mylonas et al., 2019). However, less attention has been paid ~~on~~ to the microphysical processes and aerosol-cloud interactions, still a great source of uncertainty for understanding convective systems (Fan et al., 2016). In fact, according to the Fifth Report of the Inter-
40 governmental Panel on Climate Change (Boucher et al., 2013), the quantification of cloud and convective effects in models, and of aerosol-cloud interactions, is still a major challenge. In this type of storms, the microphysics of both cold and warm clouds ~~play~~ plays a crucial role. The activation of aerosols as cloud condensation nuclei (CCN), the water absorption during the droplet growth, and the auto-conversion processes are main drivers in the core heating and dynamic evolution. In particular, the most common basis of aerosol-cloud interactions, constituted by the Köhler theory, treats the different characteristics of aerosols in terms of size, hygroscopic growth rate and solute mass to determine its activation as cloud condensation or ice nuclei, their later growth as hydrometeors, and their final conversion into raindrops or snow. In this regard, the different consideration of aerosols introduced in different aerosols models largely influences the cloud formation, and thus the intensification and evolution of the associated medicane structure. Hence, the use of an appropriate microphysics parameterization, along with the explicit solving of aerosols, seems to be fundamental for the development of the ~~medicane~~ medicanes in the model simulations. Gaining insight
50 ~~on~~ into these cloud microphysics processes is a key step for reaching a complete process-understanding. In this sense, the working hypothesis in this contribution is that aerosols play a role in a positive feedback with the surface winds that fuels the storm, maintaining its structure and intensity, and thus that an interactive calculation of sea salt aerosols (SSA) emissions and concentrations is fundamental for an accurate simulation of the medicane genesis-intensification and maintenance (Rizza et al., 2021), as in tropical cyclones (Rosenfeld et al., 2012; Jiang et al., 2019a, b, c; Luo et al., 2019).

55 In addition, given the ~~special cyclogenetic mechanisms of medicanes, which usually need a specific atmospheric configuration to start the~~ high sensitivity of both extra-tropical (Doyle et al., 2014) and tropical cyclones (Cao et al., 2011) in general, and

medicane in particular (Cavicchia et al., 2014), to the atmospheric configuration, which is fundamental to enable the start
of convective activity, the initial conditions feeding the simulations ~~highly affect the development of the medicane largely~~
impact the medicane development. In consequence, initialization time is an important source of variability (Cioni et al., 2016).

60 In this respect, constraining the synoptic scales to follow reanalysis while allowing the model to develop the small-scale dynamics, which is exactly the function of spectral nudging, stands as a good method to reduce this variability and effectively constrain the uncertainty of the simulations.

Within this framework, the present contribution aims at analyzing the role played by aerosols in the development of medicanes, together with the influence of the initialisation time and the potential benefits or caveats of using nudging techniques for
65 the simulations of these storms.

2 Methods

The results presented below are based on the analysis of an ensemble of 72 simulations, which consists of all the possibilities resulting from the combination of: three medicanes (Rolf, Cornelia and Celeno), two nudging configurations (no nudging -NN- and spectral nudging -SN-), two configurations for the aerosols concentration calculation (prescribed aerosols and interactively-
70 calculated aerosols, hereinafter referred to as PA and IA, respectively) and six run-up times (12, 36, 60, 84, 108 and 132 hours).

In this section, the main techniques applied to conduct and analyze the simulations are outlined, along with some details about the model parameterizations and the synoptic conditions associated to the studied events. It also contains a brief explanation on the interactive calculation of the SSA concentration, as included in the meteorology-chemistry coupled mesoscale model WRF-Chem.

75 2.1 Model setup

The Weather Research and Forecasting (WRF) Model (V3.9.1.1) is used to conduct the simulations object of this study (Skamarock et al., 2008). The same model configuration is employed for all simulations contained herein unless otherwise indicated. The Morrison et al. (2009) bulk microphysics scheme is used (*mp_physics=10*). This scheme allows for a double-moment approach, in which number concentration, along with the mixing ratio, is considered for each hydrometeor species included in the
80 subroutine. In its single-moment version (*progn=0*), only the mass (i.e. mixing ratio) is taken into account. Hence, while for the single-moment approach a constant concentration of an aerosol with a prescribed size is used, second-moment introduces the complexity degree of considering a size distribution for the aerosol population, thus being a more realistic approach.

With respect to the physical configuration, radiation is parameterized with the Rapid Radiative Transfer Model for GCMs (RRTMG) by Mlawer et al. (1997), both for short and long wave radiation, solved in 30 minutes intervals. Additionally, the
85 selected option for the surface layer parameterization uses the MM5 scheme based on the similarity theory by Monin and Obukhov (1954), while the *Unified NOAA LSM* option is used to simulate the land-surface interactions (Mitchell, 2005). The number of soil layers in land surface model is 4. Yonsei University scheme is employed for the boundary layer (Hong et al., 2006), solved every time step (*bldt=0*). For the cumulus physics, Grell 3D ensemble (*cu_physics=5; cudt=0*) is chosen to

parameterize convection (Grell and Dévényi, 2002). Heat and moisture fluxes from the surface are activated (*isfflx=1*), as well
90 as the cloud effect to the optical depth in radiation (*icloud=1*). Conversely, snow-cover effects are deactivated (*ifsnw=0*).
~~Land-use~~[Noah-modified 21-category IGBP-MODIS landuse data](#), land-sea mask topography ([Danielson and Gesch, 2011](#))
and soil category data ([DY and Fung, 2016](#)) were obtained from the WRF Users Page (WPS). SST is assimilated from ERA-
Interim (*sst_update=1*) every 6 hours (*auxinput4_interval_s = 21600*). The model top is fixed at 1000 Pa and 40 vertical levels
95 are used for the model runs. Urban canopy model is not considered (*sf_urban_physics=0*), and the topographic surface wind
correction from Jiménez and Dudhia (2012), later modified by Lorente-Plazas et al. (2015), is turned on. Both feedback from
the parameterized convection to the radiation schemes and SST update (every 6 hours, coinciding with the update of boundary
conditions) are also turned on.

ERA-Interim global atmospheric reanalysis is used to provide the required initial and boundary conditions every six hours.
This dataset comes from the ECMWF's Integrated Forecast System (IFS), configured for a reduced Gaussian grid with approx-
100 imately uniform 79 km spacing for surface and other grid-point fields (Berrisford et al., 2011). All simulations are run at a 9
km of horizontal grid [resolution](#)[spacing](#). A different domain is utilized for each medicane. Domains cover the regions [16°W,
25°E, 30°N, 49°N], [4°W, 35°E, 29°N, 48°N] and [3°W, 41°E, 26°N, 45°N] in Lambert conformal conic projection for Rolf,
Cornelia and Celeno medicanes, respectively. All the simulations within the ensemble of a medicane (24 runs per medicane)
are conducted in the same domain.

105 ERA5 reanalysis dataset has been used for tracking the three medicanes with the aim of comparing the tracks obtained from
the simulations with an independent source.

The specific dimensions that are changed to build up the ensemble of simulations, namely the aerosols scheme, the nudging
technique and the run-up time, are described below.

2.1.1 Interactive versus non-interactive calculation of SSA

110 In the WRF-Chem model, the dynamics core of WRF is coupled to a chemistry module (Grell et al., 2005). The model simulates
the emission, transport, mixing, and chemical transformation of trace gases and aerosols simultaneously with the meteorology.
Its main advantage with respect to WRF alone is the possibility to perform an online calculation of the chemistry processes,
allowing for chemistry-meteorology feedbacks. In the particular case under study in this contribution, when using WRF alone,
a fixed concentration of a given type of aerosols is prescribed in all cells of the modeling domain. Conversely, WRF-Chem cal-
115 culates the aerosol distribution interactively. Specifically, the Goddard Chemistry Aerosol Radiation and Transport (GOCART)
model simulates major tropospheric aerosol components, including sulfate, dust, black carbon (BC), organic carbon (OC), and
sea-salt aerosols, the latter being dominant in marine environments (Hoarau et al., 2018), as is our case study. GOCART in-
cludes SSA emission as a function of the surface wind speed, initially introduced by Gong (2003) and after modified to account
for SST dependence (Bian et al., 2019). For the emission, the dry size of particles is considered but the scheme also considers
120 the hygroscopic growth of aerosols, dependent on relative humidity, according to the equilibrium parameterization by Gerber
(1985). This dependence of SSA emission on surface wind intensity allows for the positive feedback between SSA concentra-
tion and surface wind speed that plays a major role in the medicane deepening process. When GOCART is used along with a

double-moment microphysics scheme, the emission for five bulk sea salt size bins in the range of 0.06 to 20 μm in dry diameter is interactively calculated. The double-moment approach (*progn=1*) has been employed to conduct all the simulations of this work. From here on, the simulations with double-moment microphysics and interactive calculation of aerosols by means of the GOCART scheme (*chem_opt=300*) will be referred to as "IA" simulations, while for those with double-moment microphysics but prescribed aerosol concentration (*chem_opt=0*) the term "PA" will be used.

2.1.2 Spectral nudging

Spectral nudging is a technique for constraining the synoptic scales to follow reanalysis while allowing the regional model to develop the small-scale dynamics (Miguez-Macho et al., 2004). Initially conceived for reducing the sensitivity of regional climate simulations to the size and position of the domain chosen for calculations, it has been suggested that this technique is necessary for all downscaling studies with regional models with domain sizes of a few thousand kilometers and larger embedded in global models, in order to avoid the distortion of the large-scale circulation. With this premise, we analyze the effects of considering spectral nudging for the simulation of medicanes. Particularly, a wavelength of 999 km in both horizontal directions has been used to ensure that only synoptic scale dynamics are constrained; wind, temperature and water vapor mixing ratio fields are nudged above the planetary boundary layer.

2.1.3 Run-up time

Run-up time makes reference to the time period (in hours) since the start of a simulation (reference time) to the time in which the medicane appears. To follow a consistent criterion, this reference time is extracted from the complete ensemble of each medicane. For example, for Celeno medicane, the start reference time is considered to be 1995 January 14 12:00 UTC (Figure 1). Hence, six different initialization times are considered for the ensemble of Celeno medicane simulations: from 1995 January 09 00:00 UTC to 1995 January 14 00:00 UTC with 1 day intervals, corresponding to 132, 108, 84, 60, 36 and 12 hours of run-up time, respectively. The same six run-up times are considered for Rolf (reference time 2011 November 06 12:00 UTC) and Cornelia (reference time 1996 October 06 12:00 UTC) medicanes. By considering an ensemble of initialization times, we are in practice changing the initial conditions to constrain the possible uncertainty associated to this factor, thus producing more consistent results when addressing the sensitivity to using (or not) an interactive aerosols calculation.

2.2 Synoptic environments of the events

The Rolf medicane, also known as Tropical Storm Rolf, Tropical Storm 01M (National Oceanic and Atmospheric Administration -NOAA-) or Invest 99L (U.S. Naval Research Laboratory) was a Mediterranean tropical-like storm occurred on 2011 November 06-09. It started from ~~the alignment of~~ a surface low-pressure system which evolved into a baroclinic environment near the Balearic Islands ~~and early November 06. Late on this day,~~ an extensive upper-level trough ~~early on November 06. provided the necessary environment for the triggering of the convective activity.~~ On November 07, the system revealed tropical characteristics such as a warm core and convective bands organized around a quasi-symmetric structure. Early on November

08, Rolf reached its maximum intensity, and NOAA officially declared the system a tropical storm (Win). Reaching its peak
155 intensity on that same day (~~990~~991 hPa of central pressure and maximum 1-minute sustained winds of ~~82~~83 km/h) (Rol), Rolf
started to weaken, transitioned to a tropical depression and finally lost its structure late on November 09 when it made landfall
in Southeast France (Ricchi et al., 2017; Dafis et al., 2018; Miglietta et al., 2013). Rolf was the first tropical-like cyclone ever
to be officially monitored by NOAA in the Mediterranean Sea.

Known to have formed from the interaction of a large ~~compact~~ low-pressure area that approached ~~to~~ Greece from the Ionian
160 Sea, and a middle tropospheric trough that extended from Russia to the Mediterranean, Celeno started its convective activity
early 1995 January 14. Initially remaining stationary between Greece and Sicily with a minimum atmospheric pressure of
1002 hPa, the newly formed system began to drift southwest-to-south in the following days influenced by northeasterly flow
incited by the initial low. It acquired a cloud-free distinct eye and a spiralling rainband, and started a rapid deepening phase. Its
track is generally depicted crossing the Ionian Sea southwards, from Southern Greece to the coast of Lybia (Pytharoulis et al.,
165 2000). ERA5 reanalysis provides an SLP of 990 hPa on 1995 January 14 12:00 UTC for this cyclonic structure. According to
Lagouvardos et al. (1999), a ship near to the vortex centre (35.7°N - 18.2°E) reported a 83 km/h surface wind and a pressure
of 1009 hPa on 1995 January 16 06:~~00~~00 UTC.

Last, the first phase of Cornelia medicane took place between the Balearic Islands and Sardinia, with an eye-like feature
clearly developed. It appeared on 1996 October 06 to the north of Algeria, and strengthened before temporarily losing its eye-
170 like structure when making landfall in Sardinia. On October 09, the system strengthened again over the Tyrrhenian Sea and
passed north of Sicily, reporting winds of 81 km/h at 100 km from the storm center (a ship in the position 40°N - 13°E). The low-
est model estimated atmospheric pressure reached in the storm center was 996 hPa (~~Reale and Atlas, 2001; Pytharoulis et al., 2000; Cioni, 2000~~
(Reale and Atlas, 2001; Cavicchia and Von Storch, 2012)).

2.3 Methods for the analysis of the simulations output

175 2.3.1 Tracking algorithm

TITAM (Pravia-Sarabia et al., 2020) is an algorithm specifically suited to allow for the detection and tracking of medicanes
even in adverse conditions, such as the existence of a large low in the domain, or the coexistence of multiple medicane
structures. This algorithm, based on a time-independent approach, has been used to study the intensity and duration of the
medicanes reproduced in the different simulations presented in this contribution. For the tracking of medicanes in both the
180 WRF simulations and the ERA5 reanalysis dataset, the following parameters have been chosen for running TITAM algorithm:
5 smoothing passes for the cyclonic potential field -the product of sea level pressure laplacian and 10-m vorticity-; 1020 hPa
of SLP threshold (no structure is discarded by the SLP filter); 0.5 ~~rad~~rad-h⁻¹ as vorticity lower threshold; a zero vorticity radius
required to be symmetric in 4 directions with lower and upper thresholds of 50 and 500 km, respectively, with a maximum
allowed asymmetry of 300 km; 5 minimum points in a cluster of candidate points to be considered a medicane structure;
185 a symmetry Hart parameter (B) calculated in four directions in the 900-600 hPa layer, having the maximum B an upper
threshold of 20 m -Hart proposed the threshold of 20 m for tropical cyclones, but medicanes are weaker structures with less

cyclonic character, and so we allow them to be less symmetric; and the lower and upper tropospheric thermal wind parameters calculated in the 900-600 and 600-300 hPa layers, respectively, required to be positive for the medicane to show a warm core. The zero vorticity radius, which is time- and point-dependent, is the radius used to calculate the Hart parameters for each medicane center candidate on each time step. This zero vorticity radius is calculated as the mean of the distance at which the vorticity is zero in eight directions, and is required to be non-infinite (below 300 km) at least in four directions.

2.3.2 Medicane duration

Duration is associated to the number of model time steps in which the algorithm detects a medicane. However, instead of using the total length, the duration of the medicane is calculated as the most compact set of points. This compact set, as shown in Figure 1 (grey boxes), serves as an objective measure of the real duration of the medicane, removing early starts and late endings in which the structure of the medicane is not well defined, noisily gaining and losing medicane condition. To calculate the compact set for a given simulation, after having run the tracking algorithm, it takes a vector X in which elements x_i , each one corresponding to an output step (e.g., hourly), are 1 if a medicane is found for the output step, and 0 if not. For each i in $1:(N_t - 1)$, and each j in $(i + 1):N_t$, find pair $[i, j]$ such that:

$$Q_{i,j} = \sum_{m=i}^{m=j} x_m + \sum_{m=i}^{m=j} (x_m - 1) \quad (1)$$

is maximum, being N_t the number of output steps in the simulation. Once the pair $[i_m, j_m]$ making $Q_{i,j}$ maximum is found, i_m and j_m are respectively the initial and final time steps of the medicane most compact set of points, and its difference is used hereinafter as the measure for the duration of the medicanes.

2.3.3 Kernel density estimation

In order to represent the density of medicane positions over space, Kernel Density Estimation (KDE) is employed. Let \mathbf{p}_i be the position of a medicane at a given time, defined by a pair (x_i, y_i) of longitudinal and latitudinal positions in the matrix. Then, the density estimate for a set of medicane positions is calculated as:

$$f_{\underline{H}\underline{H}}(\mathbf{x}) = \frac{1}{n} \sum_{i=1}^n \underline{n}\underline{\mathcal{K}}_{\underline{H}} \underline{n}\underline{\mathcal{K}}_{\underline{H}}(\mathbf{x} - \mathbf{p}_i) \quad (2)$$

where H is the bandwidth and n the number of points in the sample from which the density estimate is drawn. For the cases contemplated throughout this contribution, a Gaussian Kernel with a bandwidth of 2 grid points is used for \mathcal{K}_H , proportional to $\exp\left(-\frac{x^2}{2H^2}\right)$ in that case.

3 Results

3.1 Analysis of the ensemble of simulations

As an initial approach, a detailed view of each ensemble member for the three medicanes during their lifetime is shown in Figure 1. For each run-up time, the pair PA/IA is depicted; a circle represents a time step where a medicane is found, being its colour the SLP value for the medicane center. If a medicane is not found for a given time step, a grey cross is placed. Figure 1 shows how, when no nudging is used (left column plots), longer and deeper storms are ~~systematically~~ generally reproduced for IA simulations with respect to the PA simulations. The application of spectral nudging (right column plots) makes IA produce weaker medicanes than for the no nudging case, but the medicanes reproduced by IA are still longer and deeper in SLP than for PA. The role of initialization time is also clearly depicted in this Figure 1: it induces a noticeable but nearly random behavior on the medicane response, with differences up to 5 hPa on the central SLP of the medicanes for two consecutive run-up times (i.e., initialization times separated by 1 day), but in both directions and without a discernible pattern. However, spectral nudging reduces this variability introduced by the initial conditions, evening out the runs output, and sometimes even producing longer-lasting medicanes (e.g., for the case of Rolf). These results are consistently reproduced for the three medicane cases considered.




Figure 1. PA/IA pairs of simulations without (left) and with spectral nudging (right) represented for each run-up time of initialization for medicanes Rolf (top), Cornelia (middle) and Celeno (bottom). A circle represents a time step where a medicane is found, being its colour the SLP value for the medicane center. A grey cross is placed for the time steps in which no medicane is found. The grey frames include, for each simulation, the time steps inside the medicane more compact set of points, as described in Subsection 2.3.2.

230 The sensitivity of the medicane tracks for the different simulations is illustrated in Figure 2. The data is aggregated across the run-up times through the calculation of a KDE with Gaussian kernel from most-likely cyclone locations (Rosenblatt, 1956) built on top of the center of the medicane positions along the tracks belonging to the different ensembles of simulations. For each medicane (Rolf, left; Cornelia, center; Celeno, right), the four nudging-aerosols (NN vs SN; PA vs IA) simulations ensembles, each one with six run-up times, are converted into a KDE, normalized to the [0,1] range. The three medicanes tracks obtained as a result of running the TITAM tracking algorithm (Pravia-Sarabia et al., 2020) on ERA5 reanalysis data is-are superimposed

for the sake of comparison. Figure 2 depicts that the tracks are more spatially constrained for the IA ensemble. With the introduction of spectral nudging, Rolf tracks turn stationary and do not reproduce the observed movement of the storm, while a better agreement with the ERA5 track is achieved for Cornelia, specially in the latest phase, when the storm was moving towards Sicily. The case of Celeno is an extreme case in which the spectral nudging is needed for the simulations to replicate the real track (although a medicane does develop when no nudging is considered). Hence, IA produces deeper and longer medicanes with a more spatially constrained trajectory; and spectral nudging seems to be beneficial or detrimental depending on the case without a clear pattern.




Figure 2. Normalized KDEs built on top of the medicane positions along the tracks belonging to the nudging-aerosols ensembles for medicanes Rolf (left), Cornelia (center) and Celeno (right). In red, the track of each medicane as a result of running TITAM (Pravia-Sarabia et al., 2020) tracking algorithm on ERA5 hourly reanalysis data is superimposed for the time steps in which a medicane is found by the algorithm. Labels (in DD/HH format) and black points are placed every 6 hours for the sake of clarity.

To offer a more comprehensive view of the results, Figure 3 summarizes the main outcome for each member within the ensemble of simulations. Medicanes are separated in rings; and colours indicate, for the first two rows, the minimum SLP reached in each simulation for the four nudging-aerosols ensembles. The widths of the ring sector are proportional to the relative duration of the events (with respect to the maximum duration of a simulation inside the event simulations ensemble).

The two bottom panels focus on the difference in depth of the storm when the interactive calculation of aerosols is considered or not (reddish colours indicate deeper storms when IA is considered), thus being the third row the result of subtracting the first from the second row. For these two panels, widths of the outer rings are proportional to the length of the most compact set of points for the IA simulations, and widths of the inner rings to that length for the PA ones. Differences between left and right panels illustrate the impact of using spectral nudging (right) versus leaving simulation free (left). In line with what was concluded from previous figures, this Figure 3 summarizes and highlights the fact that in NN simulations, IA produces deeper and longer-lasting medicanes as compared to those reproduced with PA. With respect to the initialization time, there seems to be a nearly random response to the initial conditions (variability in the azimuthal direction). The use of SN drastically -yet not completely- reduces these differences but leads to even longer-lived medicane structures (which, for the cases of Cornelia and Celeno, approaches the simulations to the observed tracks), and reduces the variability introduced by the run-up time.




Figure 3. Medicanes are separated into rings across radial direction (inner Celeno, middle Cornelia, outer Rolf). The different run-up times are shown in six ring portions. In the first two rows, colours indicate the minimum SLP reached in each simulation, for the four nudging-aerosols simulations ensembles; ring sector widths are proportional to the relative duration of the events. In the last row, the absolute difference (colours) in the minimum SLP among the medicane centers reached during the medicane lifetime between the IA and PA simulations is shown, for each medicane and run-up time. Thus, a red colour represents a deeper SLP minimum of the medicane centers SLP values for the IA simulations, and the larger the asymmetry between the widths of the upper and lower halves of each portion of the rings, the higher the influence of using IA in the medicane duration. For each ring portion, the width of the outer half is proportional to the length of the compact set of points in the IA simulation, and that of the inner part to the one in the PA simulation. A dashed line separates both. All rings widths are normalized with respect to the maximum duration among all the simulations ensemble for the medicane (24 simulations).

255 A more quantitative analysis is shown in Tables 1 and 2, containing both the minimum SLP reached by the medicane center and the duration of the medicane (length of the compact set of points) reproduced in each simulation, respectively. The μ quantity reduces the ensemble through the sample mean for each aggregated recursive level (aerosols -ensemble with the different run-up times-; nudging -ensemble with the different run-up times and PA/IA configurations-; medicane -ensemble with the different run-up times, PA/IA configurations and NN/SN configurations-).

Table 1. Summary of the minimum SLP reached by the medicanes in the 72 simulations ensemble. The μ quantity reduces the ensemble through the sample mean for each aggregated recursive level.

Medicane →	Rolf				Cornelia				Celeno			
Nudging →	NN		SN		NN		SN		NN		SN	
Aerosols →	PA	IA	PA	IA	PA	IA	PA	IA	PA	IA	PA	IA
Run-up time ↓												
12h	1003.8	995.8	999.3	999.3	998.9	999.5	998.7	997.3	991.6	989.9	989.7	988.9
36h	998.8	993.5	1002.1	998.9	991.1	990.7	998.3	996.4	989.2	985.1	993.1	989.0
60h	1004.3	994.4	1002.8	1002.2	992.4	991.3	997.0	995.0	992.1	989.1	993.3	992.6
84h	1012.6	999.4	1002.6	1002.2	999.2	992.6	996.0	994.5	990.2	984.4	994.4	989.6
108h	1002.3	998.7	1003.1	1002.7	996.0	991.6	995.1	994.2	989.5	987.2	993.0	989.8
132h	1002.9	999.5	1002.5	1001.9	993.5	993.0	996.1	994.6	988.0	989.6	990.8	989.9
μ (aerosols)	1004.1	996.9	1002.1	1001.2	995.2	993.1	996.9	995.3	990.1	987.6	992.4	990.0
μ (nudging)	1000.5		1001.6		994.1		996.1		988.8		991.2	
μ (medicane)	1001.1				995.1				990.0			

Table 2. Summary of the medicane duration -number of points in the compact set- of the 72 simulations ensemble. The μ quantity reduces the ensemble through the sample mean for each aggregated recursive level.

Medicane →	Rolf				Cornelia				Celeno			
Nudging →	NN		SN		NN		SN		NN		SN	
Aerosols →	PA	IA	PA	IA	PA	IA	PA	IA	PA	IA	PA	IA
Run-up time ↓												
12h	9	32	72	70	10	7	56	13	43	51	50	53
36h	45	69	51	79	90	70	63	69	34	53	48	51
60h	15	44	48	56	41	99	72	74	28	35	43	43
84h	7	42	51	55	23	56	60	99	36	66	39	57
108h	20	33	50	58	37	57	83	80	34	54	46	58
132h	26	37	51	64	31	36	64	74	49	53	60	50
μ (aerosols)	20.3	42.8	53.8	63.7	38.7	54.2	66.3	68.2	37.3	52.0	47.7	52.0
μ (nudging)	31.6		58.8		46.4		67.3		44.7		49.8	
μ (medicane)	45.2				56.8				47.3			

260 With respect to the spectral nudging effect, although long-lived medicane structures are generated for SN configuration, they do not reach the intensity of those reproduced in the NN simulations. The explanation to this effect lies in the spectral nudging mechanism: forcing the meteorological fields to resemble ~~to~~ the large scale dynamics produces alterations in the nudged fields (temperature, humidity and wind) above the PBL. Henceforth, the temperature field does not freely evolve and deep convection may be interrupted, thus limiting the intensification potential of the medicane. Figure 4 supports this statement, showing that

265 the warm core is broken-off in the 500-800 hPa layer when SN is introduced. In Figure 4, a set of height-radius cross sections of the equivalent potential temperature (θ_e) is produced by time-averaging the cross-sections for the time steps in which a medicane is found for the NN (top) and SN (bottom) simulations of medicanes Rolf, Cornelia and Celeno, started with 36 hours of run-up time.




Figure 4. Time-averaged height-radius cross sections of the equivalent potential temperature (θ_e) over all time steps in which a medicane is found in the NN (top) and SN (bottom) simulations for medicanes Rolf (simulation starting 2011 Nov 05 00:00 UTC -36 hours of run-up time-), Cornelia (simulation starting on 1996 Oct 05 00:00 UTC -36 hours of run-up time-) and Celeno (simulation starting on 1995 Jan 09 13 00:00 UTC -36 hours of run-up time-).

3.2 Proposed intensification mechanism: SSA-wind feedback

270 It has been previously discussed that IA calculation leads to deeper and longer medicane tracks. As introduced in Section 1, our main initial hypothesis, given the close nature of medicanes to tropical cyclones, is that the online calculation of SSA allows for the existence of a positive feedback with surface wind. Although this feedback is irrelevant for an early emergence of convective activity, generally fostered by a cold cut-off low in upper levels ~~when it comes to in the case of~~ medicanes (Emanuel, 2005), it becomes essential once the core circulation is established. For the sake of examining the hypothesis of
 275 the existence of this feedback, we choose two NN simulations of Rolf starting on 2011 November 05 00:00 UTC, because of (1) their closeness to the observed medicane track; (2) the low SLP they reach; and (3) the robust and stable structure they develop (~~with the exception of the intensity, not in intensity, but in terms of their track,~~ it is the IA/PA pair in which ~~a~~ the most similar storm is developed in both simulations). Figure 5 depicts the temporal evolution of the differences in equivalent potential temperature (θ_e) between the IA and PA simulations along the vertical of the medicane center.




Figure 5. Difference in equivalent potential temperature between the IA and PA simulations for each output time step (horizontal axis) in which both the PA and IA simulations find a medicane for Rolf starting on 2011 Nov 05 00:00 UTC. Results are presented for each pressure level (vertical axis) in the vertical of the ~~center of the medicane~~ center. Red colours indicate higher equivalent potential temperatures, and thus more available energy, for the IA simulation. Blue marks in the horizontal axis refer to the time steps in which the medicane structure is lost and hence the tracking algorithm does not find a medicane center in any of the two compared cases. For these time steps, there is no vertical profile of temperature of the medicane core. The time axis labels (horizontal axis) are presented in day-hour format, being all dates referred to November 2011.

280 In general, higher (orange to red colours) θ_e values are found for the IA case, meaning that more convective potential energy comes into play in the form of hot moist air in the low troposphere when aerosols are interactively solved in each time step of the model. This is specially evident for time steps after November 07, when the medicane starts to gain strength, releasing more latent heat of condensation due to the stronger convection, and thus producing more water vapour under higher surface wind conditions. Another related aspect, the warm core structure, is presented in Figure 6 by means of the time-averaged
 285 height-radius cross sections of θ_e (top plots) along the latitudes of the medicane center, for both the PA (left) and IA (right) NN simulations of Rolf started with 36 hours of run-up time. Figure 6 clearly reveals that the core equivalent potential temperature is higher for the IA case, this being specially true for the lower tropospheric and surface levels given the strong presence of moist air in this layer; ~~these plots even depict the divergence of warm air aloft~~. In the bottom plots of Figure 6, the anomaly of potential temperature (θ') in time-averaged height-radius cross sections along the latitudes of the medicane center is presented

290 for the same two simulations, showing a net heating of the storm core, maximum in the 500-800 hPa layer, which seems to be related to core dynamics.




Figure 6. Top row: time-averaged height-radius cross sections of θ_e along the medicane center latitudes, for both the PA (left) and IA (right) NN simulations of Rolf started with 36 hours of run-up time. Bottom row: for the same two simulations, the in-level-anomaly of potential temperature (θ') -for each level, and with respect to the level time and spatially averaged θ - in time-averaged height-radius cross sections along the medicane center latitudes is presented.

To fully understand the processes undergone by aerosols and clouds, the distribution of hydrometeors is examined, revealing the form in which the thermal energy is handled by the system. This is shown in Figure 7, in which a time- and azimuthally-averaged ~~height-longitude~~ height-radius cross section is presented along the medicane centers found for the simulations of Rolf starting on 2011 November 05 00:00 UTC (36 hours of run-up time) with prescribed (left) and interactive (right) aerosols calculation, both simulations run without spectral nudging. [Figure 7](#) shows (from top to bottom) cloud water mixing ratio, rain water mixing ratio and droplet number mixing ratio, for both the PA (left column) and IA (right column) simulations.




Figure 7. From top to bottom, cloud water mixing ratio (QCLOUD, $kg\ kg^{-1}$), rain water mixing ratio (QRAIN, $kg\ kg^{-1}$) and droplet number mixing ratio (QNDROP, kg^{-1}). Time- and azimuthally-averaged height-radius cross sections are presented, for PA (left column) and IA (right column) simulations of Rolf starting with 36 hours of run-up time (i.e., on 2011 November 05 00:00 UTC), both without spectral nudging. Distance from the medicane center is represented in the horizontal axis and atmospheric pressure levels in the vertical axis. The three scales must be multiplied by the factor preceding the units in the legends titles.

Figure 7 indicates that in the case where the largest medicane deepening is found, although accompanied by a higher thermal energy, lower cloud droplet numbers and less cloud water content come into play, but more rain water is produced. Diving into
 300 the microphysics, a plausible explanation resides in the Köhler curves and mechanism of CCN activation as cloud droplets. Intense wind blowing over the ocean surface creates sea spray, which contains organic matter and inorganic salts that form

SSA (Gong et al., 1997). SSA are coarse particles quickly reaching the critical radius and being early activated as CCN at low supersaturation rates according to Köhler theory (Köhler, 1936), thus being highly prone to condensational growth (Jensen and Nugent, 2017). The existence of SSA enables an early, rapid and strong latent heat release in the lower troposphere, which enhances deep convection, ultimately leading to an intensification of surface winds under low supersaturation conditions in the early medicane stage. Conversely, prescribed aerosols concentrations used in PA simulations lead to a high amount of fine particles with low hygroscopicity hardly activated as CCN and competing for water vapor uptake, thus producing a higher number of small droplets which are barely converted into raindrops.

4 Summary and conclusions

In this contribution, an ensemble of 72 simulations has been conducted to analyze the role of SSA feedbacks in the development and intensification of three different medicanes. Results show a clear dependence of both the track and intensity of the medicanes simulated on the calculation of interactive aerosols, as their consideration leads to longer and deeper medicanes in the simulations. The proposed mechanism to explain this difference is that, by contrast with simulations with prescribed aerosols (as usually included in meteorological models), when interactive aerosols are introduced the presence of coarse particles is taken into account, and the hygroscopic characteristics of SSA are considered, thus allowing an early reaching of critical radius and an enhancement of a strong latent heat release in the lower tropospheric levels. Conversely, when aerosols are prescribed and constant, finer particles are considered and less activation of aerosols to CCN is produced, which lowers the velocity of condensational growth, leading to lower rates of latent heat production and suppression of warm rain provided the difficulty of small aerosols to grow up to droplet size. Hence, the coupling of the meteorological model to an online chemistry module seems to result of paramount significance for the formation and evolution of a medicane. An interactive calculation of aerosols provides realistic SSA concentrations which, combined with the ability of the model to introduce hygroscopic and microphysical properties for the different species, favours the simulation of intense deep convection processes, which are crucial in this type of storms.

Initialization time largely modulates the output of the medicane simulations, thus being a source of great variability. Highly influenced by the initial conditions, these simulations are prone to lose the necessary conditions for a medicane to be triggered and maintained. Despite this sensitivity, there seems to be no privileged run-up time to simulate medicanes, and no systematic deviation is produced by this factor. Hence, modifying the initialization time is analogous to perturbing the initial conditions in a system highly sensitive to initial conditions. This result needs to be highlighted, as the different run-up times can thus be regarded as an ensemble of perturbed initial conditions, and thus the results obtained related to the importance of an interactive aerosols calculation are robust within this ensemble.

Spectral nudging leads to longer but less intense medicane tracks. Besides the fact that it seems useful for producing 'realistic' medicanes in some cases, like that of Celeno, the storms do not seem to be fully developed when SN is introduced. Given the vertical character of medicane structures, any forcing introduced by synoptic scale dynamics may provoke a misalignment in the medicane core or a break in the deep convective structure. Specifically, the asymmetric upper-lower tropospheric forcing

335 derived from the spectral nudging technique without in-PBL influence deviates the vertical alignment of medicane core, intro-
ducing an artificial vertical shear that hampers the formation of deep convection. However, further analysis on the wavelength
and in-PBL spectral nudging would be required to completely determine whether spectral nudging could be beneficial for
medicane simulations. As for now, and despite our initial intuition related to the importance of binding the initial conditions,
340 the results confirm that the spectral nudging seems not to be valid for individual case studies, being its utility limited to the
downscaling of global climate models.

Finally, this contribution discusses the differences between simulations with and without SSA feedbacks, but no assessment
is provided on whether differences imply a better agreement with actual medicanes. The main reason for this is the lack of re-
liable observations over the sea to carry out a comprehensive validation of the simulations. Therefore the contribution focuses
on the physical mechanisms reproduced by the model, and provides arguments supporting their feasibility. Given the great
345 similarities of medicanes with tropical cyclones on their mature stage, it seems clear that the possibility for medicanes to pro-
duce ~~its~~their own SSA within a feedback process needs to be accounted by the simulations. The analysis included here indeed
shows that enabling this possibility leads to deeper and longer medicane tracks. Therefore the natural question emerging is to
what extent this deepening of the storm is realistic. Although the lack of observations to carry out validations hampers such an
assessment, including these processes can only lead to a more realistic simulation of medicanes. Models, and specifically their
350 microphysics or the presence and effects of aerosols, are strongly parameterized. Even if an eventual validation could demon-
strate that simulations without SSA feedback, i.e. shallower storms, are closer to observations, this would not mean that ignor-
ing this feedback produces better results. Instead, it would demonstrate that the model is heavily tuned to produce better results
when important feedback processes are ignored. ~~Therefore,~~An important factor to take into account is the change in the sea
surface roughness on the wind stress due to the presence of spume droplets (Liu et al., 2012b; Kudryavtsev and Makin, 2011)
355 . It is believed that at very high wind speeds a deep part of the marine atmospheric surface layer is filled with spray droplets
-spume-, originating from intensively breaking waves, which form the spray droplet suspension layer. Sea sprays generated by
wave breaking and wind tearing wave crests modify the wind profile and prevent the water surface from being dragged by the
wind directly, which in turn, reduces the drag coefficient and levels off the wind stress under high winds (Liu et al., 2012a)
. Considering this effect may be important for a correct reproduction of sea spray production under high wind conditions
360 (close to hurricane force, i.e. in the strongest medicanes), according to the results in Rizza et al. (2021) its omission may be
consequential for the particular case study addressed in this work, and a coupling with an ocean model would be useful for a
thorough inquiry on this question. However, according to the values provided in Liu et al. (2012a), the sea spray takes effect on
the drag coefficient as the wind speed approaches the range of $25\text{--}33\text{ m}\cdot\text{s}^{-1}$, which is hardly reached in the studied medicanes.
On this basis, the validity of the results presented herein should not suffer alterations due to this this effect of sea spray on
365 ocean surface roughness, and the conclusions here included should be valid. Therefore, from the results included in this paper
it becomes evident that the inclusion of SSA feedback is a fundamental mechanism in the development of tropical-like storms,
and simulations aiming at studying these phenomena should not neglect its importance.

Author contributions. EPS carried out the simulations and performed the calculations of this paper. JPM contributed to the design of the simulations and their analysis. He also provided ideas for new approaches in the analysis of the simulations that have been integrated in the final manuscript. JJGN, PJG and JPM provided substantial expertise on the topic that contributed to its understanding. The paper has been written by EPS, JJGN and JPM, and all authors have contributed reviewing the text.

Competing interests. The authors declare no conflict of interest.

Acknowledgements. The authors are thankful to the WRF-Chem development community and the G-MAR research group at the University of Murcia for the fruitful scientific discussions.

Financial support. This study was supported by the Spanish Ministry of Economy and Competitiveness/Agencia Estatal de Investigación and the European Regional Development Fund (ERDF/FEDER) through project ACEX-CGL2017-87921-R project.

References

- Tropical storm develops in the Mediterranean Sea, <https://www.eumetsat.int/tropical-storm-develops-mediterranean-sea>, accessed: 2021-07-11.
- 380 WPS V4 Geographical Static Data Downloads Page, https://www2.mmm.ucar.edu/wrf/users/download/get_sources_wps_geog.html, accessed: 2019-12-04.
- NOAA 2011 Tropical Bulletin Archive, <https://www.ssd.noaa.gov/PS/TROP/DATA/2011/bulletins/med/20111108000001M.html>, last accessed: 2020-12-22.
- Akhtar, N., Brauch, J., Dobler, A., Béranger, K., and Ahrens, B.: Medicanes in an ocean–atmosphere coupled regional climate model, *Natural Hazards and Earth System Sciences*, 14, 2189–2201, <https://doi.org/10.5194/nhess-14-2189-2014>, <https://nhess.copernicus.org/articles/14/2189/2014/>, 2014.
- 385 Berrisford, P., Dee, D., Poli, P., Brugge, R., Fielding, M., Fuentes, M., Kållberg, P., Kobayashi, S., Uppala, S., and Simmons, A.: The ERA-Interim archive Version 2.0, p. 23, <https://www.ecmwf.int/node/8174>, 2011.
- Bian, H., Froyd, K., Murphy, D. M., Dibb, J., Darmenov, A., Chin, M., Colarco, P. R., da Silva, A., Kucsera, T. L., Schill, G., et al.: Observationally constrained analysis of sea salt aerosol in the marine atmosphere, *Atmospheric Chemistry and Physics*, 19, 10773–10785, 2019.
- 390 Boucher, O., Randall, D., Artaxo, P., Bretherton, C., Feingold, G., Forster, P., Kerminen, V.-M., Kondo, Y., Liao, H., Lohmann, U., et al.: Clouds and aerosols, in: *Climate change 2013: the physical science basis. Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change*, pp. 571–657, Cambridge University Press, 2013.
- 395 Bouin, M.-N. and Lebeau-pin Brossier, C.: Surface processes in the 7 November 2014 medicane from air–sea coupled high-resolution numerical modelling, *Atmospheric Chemistry and Physics*, 20, 6861–6881, 2020.
- Cao, Y., Fovell, R. G., and Corbosiero, K. L.: Tropical cyclone track and structure sensitivity to initialization in idealized simulations: A preliminary study, *Terrestrial, Atmospheric and Oceanic Sciences*, 22, 559–578, 2011.
- Cavicchia, L. and Von Storch, H.: The simulation of Medicanes in a high-resolution regional climate model, *Climate Dynamics*, 39, <https://doi.org/10.1007/s00382-011-1220-0>, 2012.
- 400 Cavicchia, L., von Storch, H., and Gualdi, S.: A long-term climatology of medicanes, *Climate dynamics*, 43, 1183–1195, 2014.
- Cioni, G.: Thermal structure and dynamical modelling of a Mediterranean Tropical-like Cyclone, Ph.D. thesis, <https://doi.org/10.13140/RG.2.1.2000.4722>, 2014.
- Cioni, G., Malguzzi, P., and Buzzi, A.: Thermal structure and dynamical precursor of a Mediterranean tropical-like cyclone, *Quarterly Journal of the Royal Meteorological Society*, 142, 1757–1766, 2016.
- 405 Dafis, S., Rysman, J.-F., Claud, C., and Flaounas, E.: Remote sensing of deep convection within a tropical-like cyclone over the Mediterranean Sea, *Atmospheric Science Letters*, 19, e823, <https://doi.org/10.1002/asl.823>, <https://rmets.onlinelibrary.wiley.com/doi/abs/10.1002/asl.823>, 2018.
- Dafis, S., Claud, C., Kotroni, V., Lagouvardos, K., and Rysman, J.-F.: Insights into the convective evolution of Mediterranean tropical-like cyclones, *Quarterly Journal of the Royal Meteorological Society*, 146, 4147–4169, <https://doi.org/10.1002/qj.3896>, <https://rmets.onlinelibrary.wiley.com/doi/abs/10.1002/qj.3896>, 2020.
- 410 Danielson, J. and Gesch, D.: Global Multi-resolution Terrain Elevation Data 2010 (GMTED2010), US Geological Survey Open File Report 2011–1073, p. 26, 2011.

- Doyle, J. D., Amerault, C., Reynolds, C. A., and Reinecke, P. A.: Initial condition sensitivity and predictability of a severe extratropical cyclone using a moist adjoint, *Monthly Weather Review*, 142, 320–342, 2014.
- 415 DY, C. Y. and Fung, J. C. H.: Updated global soil map for the Weather Research and Forecasting model and soil moisture initialization for the Noah land surface model, *Journal of Geophysical Research: Atmospheres*, 121, 8777–8800, <https://doi.org/https://doi.org/10.1002/2015JD024558>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1002/2015JD024558>, 2016.
- Emanuel, K.: Genesis and maintenance of "Mediterranean hurricanes", *Advances in Geosciences*, 2, 217–220, <https://hal.archives-ouvertes.fr/hal-00296883>, 2005.
- 420 Fan, J., Wang, Y., Rosenfeld, D., and Liu, X.: Review of aerosol–cloud interactions: Mechanisms, significance, and challenges, *Journal of the Atmospheric Sciences*, 73, 4221–4252, 2016.
- Fita, L., Romero, R., Luque, A., Emanuel, K., and Ramis, C.: Analysis of the environments of seven Mediterranean tropical-like storms using an axisymmetric, nonhydrostatic, cloud resolving model, *Natural Hazards and Earth System Science*, 7, 41–56, <https://hal.archives-ouvertes.fr/hal-00301676>, 2007.
- 425 Gaertner, M. Á., González-Alemán, J. J., Romera, R., Domínguez, M., Gil, V., Sánchez, E., Gallardo, C., Miglietta, M. M., Walsh, K. J., Sein, D. V., et al.: Simulation of medicanes over the Mediterranean Sea in a regional climate model ensemble: impact of ocean–atmosphere coupling and increased resolution, *Climate dynamics*, 51, 1041–1057, 2018.
- Gerber, H. E.: Relative-humidity parameterization of the Navy Aerosol Model (NAM), Tech. rep., Naval Research Lab Washington DC, 1985.
- 430 Gong, S., Barrie, L., and Blanchet, J.-P.: Modeling sea-salt aerosols in the atmosphere: 1. Model development, *Journal of Geophysical Research: Atmospheres*, 102, 3805–3818, 1997.
- Gong, S. L.: A parameterization of sea-salt aerosol source function for sub- and super-micron particles, *Global Biogeochemical Cycles*, 17, <https://doi.org/10.1029/2003GB002079>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1029/2003GB002079>, 2003.
- 435 Grell, G. A. and Dévényi, D.: A generalized approach to parameterizing convection combining ensemble and data assimilation techniques, *Geophysical Research Letters*, 29, 38–1, 2002.
- Grell, G. A., Peckham, S. E., Schmitz, R., McKeen, S. A., Frost, G., Skamarock, W. C., and Eder, B.: Fully coupled "online" chemistry within the WRF model, *Atmospheric Environment*, 39, 6957–6975, 2005.
- Hoarau, T., Barthe, C., Tulet, P., Claeys, M., Pinty, J.-P., Bousquet, O., Delanoë, J., and Vié, B.: Impact of the generation and activation of sea salt aerosols on the evolution of Tropical Cyclone Dumile, *Journal of Geophysical Research: Atmospheres*, 123, 8813–8831, 2018.
- 440 Hong, S.-Y., Noh, Y., and Dudhia, J.: A new vertical diffusion package with an explicit treatment of entrainment processes, *Monthly weather review*, 134, 2318–2341, 2006.
- Jensen, J. B. and Nugent, A. D.: Condensational growth of drops formed on giant sea-salt aerosol particles, *Journal of the atmospheric sciences*, 74, 679–697, 2017.
- 445 Jiang, B., Lin, W., Li, F., and Chen, B.: Simulation of the effects of sea-salt aerosols on cloud ice and precipitation of a tropical cyclone, *Atmospheric Science Letters*, 20, e936, 2019a.
- Jiang, B., Lin, W., Li, F., and Chen, J.: Sea-salt aerosol effects on the simulated microphysics and precipitation in a tropical cyclone, *Journal of Meteorological Research*, 33, 115–125, 2019b.
- Jiang, B., Wang, D., Shen, X., Chen, J., and Lin, W.: Effects of sea salt aerosols on precipitation and upper troposphere/lower stratosphere water vapour in tropical cyclone systems, *Scientific reports*, 9, 1–13, 2019c.
- 450

- Jiménez, P. A. and Dudhia, J.: Improving the representation of resolved and unresolved topographic effects on surface wind in the WRF model, *Journal of Applied Meteorology and Climatology*, 51, 300–316, 2012.
- Köhler, H.: The nucleus in and the growth of hygroscopic droplets, *Transactions of the Faraday Society*, 32, 1152–1161, 1936.
- Kudryavtsev, V. N. and Makin, V. K.: Impact of ocean spray on the dynamics of the marine atmospheric boundary layer, *Boundary-layer meteorology*, 140, 383–410, 2011.
- 455 Lagouvardos, K., Kotroni, V., Nickovic, S., Jovic, D., Kallos, G., and Tremback, C.: Observations and model simulations of a winter sub-synoptic vortex over the central Mediterranean, *Meteorological Applications: A journal of forecasting, practical applications, training techniques and modelling*, 6, 371–383, 1999.
- Liu, B., Guan, C., and Xie, L.: The wave state and sea spray related parameterization of wind stress applicable from low to extreme winds, *Journal of Geophysical Research: Oceans*, 117, <https://doi.org/https://doi.org/10.1029/2011JC007786>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1029/2011JC007786>, 2012a.
- 460 Liu, B., Guan, C., Zhao, D., et al.: An investigation of the effects of wave state and sea spray on an idealized typhoon using an air-sea coupled modeling system, *Advances in Atmospheric Sciences*, 29, 391–406, 2012b.
- Lorente-Plazas, R., Montávez, J. P., Jimenez, P. A., Jerez, S., Gómez-Navarro, J. J., García-Valero, J. A., and Jimenez-Guerrero, P.: Characterization of surface winds over the Iberian Peninsula, *International Journal of Climatology*, 35, 1007–1026, <https://doi.org/https://doi.org/10.1002/joc.4034>, <https://rmets.onlinelibrary.wiley.com/doi/abs/10.1002/joc.4034>, 2015.
- 465 Luo, H., Jiang, B., Li, F., and Lin, W.: Simulation of the effects of sea-salt aerosols on the structure and precipitation of a developed tropical cyclone, *Atmospheric Research*, 217, 120–127, 2019.
- Miglietta, M. M. and Rotunno, R.: Development mechanisms for Mediterranean tropical-like cyclones (medicanes), *Quarterly Journal of the Royal Meteorological Society*, 145, 1444–1460, 2019.
- 470 Miglietta, M. M., Laviola, S., Malvaldi, A., Conte, D., Levizzani, V., and Price, C.: Analysis of tropical-like cyclones over the Mediterranean Sea through a combined modeling and satellite approach, *Geophysical Research Letters*, 40, 2400–2405, <https://doi.org/10.1002/grl.50432>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1002/grl.50432>, 2013.
- Miglietta, M. M., Mastrangelo, D., and Conte, D.: Influence of physics parameterization schemes on the simulation of a tropical-like cyclone in the Mediterranean Sea, *Atmospheric Research*, 153, 360–375, 2015.
- 475 Miguez-Macho, G., Stenchikov, G. L., and Robock, A.: Spectral nudging to eliminate the effects of domain position and geometry in regional climate model simulations, *Journal of Geophysical Research: Atmospheres*, 109, <https://doi.org/10.1029/2003JD004495>, <https://agupubs.onlinelibrary.wiley.com/doi/abs/10.1029/2003JD004495>, 2004.
- Mitchell, K.: The community Noah land-surface model (LSM), User’s Guide. Recovered from ftp://ftp.emc.ncep.noaa.gov/mmb/gcp/ldas/noahsm/ver_2, 7, 2005.
- 480 Mlawer, E. J., Taubman, S. J., Brown, P. D., Iacono, M. J., and Clough, S. A.: Radiative transfer for inhomogeneous atmospheres: RRTM, a validated correlated-k model for the longwave, *Journal of Geophysical Research: Atmospheres*, 102, 16 663–16 682, 1997.
- Monin, A. S. and Obukhov, A. M.: Basic laws of turbulent mixing in the surface layer of the atmosphere, *Contrib. Geophys. Inst. Acad. Sci. USSR*, 151, e187, 1954.
- 485 Morrison, H., Thompson, G., and Tatarskii, V.: Impact of cloud microphysics on the development of trailing stratiform precipitation in a simulated squall line: Comparison of one-and two-moment schemes, *Monthly weather review*, 137, 991–1007, 2009.
- Mylonas, M. P., Douvis, K. C., Polychroni, I. D., Politi, N., and Nastos, P. T.: Analysis of a Mediterranean Tropical-Like Cyclone. Sensitivity to WRF Parameterizations and Horizontal Resolution, *Atmosphere*, 10, 425, 2019.

- 490 Noyelle, R., Ulbrich, U., Becker, N., and Meredith, E. P.: Assessing the impact of sea surface temperatures on a simulated medicane using ensemble simulations, *Natural Hazards and Earth System Sciences*, 19, 941–955, 2019.
- Pravia-Sarabia, E., Gómez-Navarro, J. J., Jiménez-Guerrero, P., and Montávez, J. P.: TITAM (v1.0): the Time-Independent Tracking Algorithm for Medicanes, *Geoscientific Model Development*, 13, 6051–6075, <https://doi.org/10.5194/gmd-13-6051-2020>, <https://gmd.copernicus.org/articles/13/6051/2020/>, 2020.
- 495 Pytharoulis, I.: Analysis of a Mediterranean tropical-like cyclone and its sensitivity to the sea surface temperatures, *Atmospheric Research*, 208, 167–179, 2018.
- Pytharoulis, I., Craig, G. C., and Ballard, S. P.: The hurricane-like Mediterranean cyclone of January 1995, *Meteorological Applications*, 7, 261–279, <https://doi.org/10.1017/S1350482700001511>, <https://rmets.onlinelibrary.wiley.com/doi/abs/10.1017/S1350482700001511>, 2000.
- 500 Pytharoulis, I., Kartsios, S., Tegoulis, I., Feidas, H., Miglietta, M. M., Matsangouras, I., and Karacostas, T.: Sensitivity of a mediterranean tropical-like cyclone to physical parameterizations, *Atmosphere*, 9, 436, 2018.
- Ragone, F., Mariotti, M., Parodi, A., Von Hardenberg, J., and Pasquero, C.: A climatological study of western mediterranean medicanes in numerical simulations with explicit and parameterized convection, *Atmosphere*, 9, 397, 2018.
- Reale, O. and Atlas, R.: Tropical Cyclone–Like Vortices in the Extratropics: Observational Evidence and Synoptic Analysis, *Weather and Forecasting*, 16, 7 – 34, [https://doi.org/10.1175/1520-0434\(2001\)016<0007:TCLVIT>2.0.CO;2](https://doi.org/10.1175/1520-0434(2001)016<0007:TCLVIT>2.0.CO;2), https://journals.ametsoc.org/view/journals/wefo/16/1/1520-0434_2001_016_0007_tclvit_2_0_co_2.xml, 2001.
- 505 Ricchi, A., Miglietta, M. M., Barbariol, F., Benetazzo, A., Bergamasco, A., Bonaldo, D., Cassardo, C., Falcieri, F. M., Modugno, G., Russo, A., et al.: Sensitivity of a Mediterranean tropical-like cyclone to different model configurations and coupling strategies, *Atmosphere*, 8, 92, 2017.
- Rizza, U., Canepa, E., Ricchi, A., Bonaldo, D., Carniel, S., Morichetti, M., Passerini, G., Santiloni, L., Scremin Puhales, F., and Miglietta, 510 M. M.: Influence of wave state and sea spray on the roughness length: Feedback on medicanes, *Atmosphere*, 9, 301, 2018.
- Rizza, U., Canepa, E., Miglietta, M. M., Passerini, G., Morichetti, M., Mancinelli, E., Virgili, S., Besio, G., De Leo, F., and Mazzino, A.: Evaluation of drag coefficients under medicane conditions: Coupling waves, sea spray and surface friction, *Atmospheric Research*, 247, 105 207, <https://doi.org/10.1016/j.atmosres.2020.105207>, <https://www.sciencedirect.com/science/article/pii/S0169809520311431>, 2021.
- Rosenblatt, M.: Remarks on Some Nonparametric Estimates of a Density Function, *Ann. Math. Statist.*, 27, 832–837, 515 <https://doi.org/10.1214/aoms/1177728190>, 1956.
- Rosenfeld, D., Woodley, W. L., Khain, A., Cotton, W. R., Carrió, G., Ginis, I., and Golden, J. H.: Aerosol effects on microstructure and intensity of tropical cyclones, *Bulletin of the American meteorological Society*, 93, 987–1001, 2012.
- Skamarock, W., Klemp, J., Dudhia, J., Gill, D., Barker, D., Wang, W., and Powers, J.: A Description of the Advanced Research WRF Version 3, 27, 3–27, 2008.
- 520 Tous, M. and Romero, R.: Meteorological environments associated with medicane development, *International Journal of Climatology*, 33, 1–14, 2013.
- Tous, M., Romero, R., and Ramis, C.: Surface heat fluxes influence on medicane trajectories and intensification, *Atmospheric research*, 123, 400–411, 2013.